

REPUBLIQUE DU CAMEROUN  
 Paix – Travail – Patrie  
 MINISTRE DE LA DECENTRALISATION  
 ET DU DEVELOPPEMENT LOCAL  
 REGION DU NORD OUEST  
 DEPARTEMENT DE NGOKETUNJIA  
 ARRONDISSEMENT DE NDOP  
 COMMUNE DE NDOP  
 COMMISSION INTERNE DE  
 PASSATION DES MARCHES



REPUBLIC OF CAMEROON  
 Peace – Work – Fatherland  
 MINISTRY OF DECENTRALIZATION AND  
 LOCAL DEVELOPMENT  
 NORTH WEST REGION  
 NGOKETUNJIA DIVISION  
 NDOP SUB DIVISION  
 NDOP COUNCIL  
 NDOP COUNCIL INTERNAL  
 TENDERS' BOARD

## NDOP COUNCIL INTERNAL TENDERS BOARD

\*\*\*\*\*

### OPEN NATIONAL INVITATION TO TENDER

### EMERGENCY PROCEDURE

TENDER FILE No 02/ONIT /NC/ NCITB / 2020 of 8<sup>th</sup> January 2020

FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRE IN MBEBAH  
 BAMESSING IN NGOKETUNJIA DIVISION OF THE NORTH WEST REGION

PROJECT OWNER: THE LORD MAYOR OF NDOP COUNCIL

FINANCING: MINSANTE PUBLIC INVESTMENT BUDGET (PIB) - 2020

#### BUDGET HEADS

Lot	Name of project	Estimated cost of project	Amount of bid bond	imputation
1	CONSTRUCTION OF AN INTEGRATED HEALTH CENTRE IN MBEBAH	50 000 000	1 000 000	54 40.64 16 38 2221

FINANCIAL YEAR 2020

## TABLE OF CONTENTS

Document No. 1: Tender notice

Document No. 2: General Regulations of the invitation to tender

Document No. 3: Special Regulations of the invitation to tender

Document No. 4: Special Administrative Conditions

Document No. 5: Special Technical Conditions

Document No. 6: Schedule of unit prices

Document No. 7: Bill of quantities and estimates

Document No. 8: The sub-detail of prices

Document No. 9: Model contract

Document No. 10: Model documents to be used by bidders

Document No. 11: Justifications of preliminary studies

Document No. 12: List of banking establishments and financial bodies authorised to issue bonds for public contracts

Document No. 13: Plans

**DOCUMENT NO. 2:**  
**GENERAL REGULATIONS OF THE INVITATION TO TENDER**

- 5- Le non-respect de **20/25** des critères essentiels ;
- 6- Absence ou non-conformité d'une pièce administrative

### **B - Critères essentiels**

Les critères relatifs à la qualification des candidats porteront titre indicatif sur:

- 1- Présentation générale de l'offre ;
- 2- Capacité financière ;
- 3- Références de l'entreprise dans les réalisations similaires ;
- 4- Qualité du personnel ;
- 5- Organisation technique des travaux ;
- 6- Moyens logistiques ;
- 7- Attestation et rapport de visite du site ;
- 8- Cahier des Clauses Techniques Particulières paraphé à chaque page ;
- 9- Cahier des Clauses Administratives Particulières complété et paraphé à chaque page.

Les critères essentiels sont soumis à des minima dont le détail est donné dans le Règlement Particulier de l'Appel d'Offres (RPAO).

### **15. Attribution**

Cette évaluation se fera de manière purement positive (oui) ou négative (non) avec un minimum acceptable d'au moins **20/25** de l'ensemble des critères essentiels pris en compte.

Le marché sera attribué au soumissionnaire qui aura proposé l'offre la moins disante, conforme pour l'essentiel aux prescriptions du Dossier d'Appel d'Offres, ayant satisfait à **100%** des critères éliminatoires et au moins **20/25** des critères essentiels.

### **16. Durée de validité des offres**

Les soumissionnaires restent engagés par leur offre pendant 60 jours à partir de la date limite fixée pour la remise des offres.

### **17. Renseignements complémentaires**

Les renseignements complémentaires d'ordre technique peuvent être obtenus auprès de Mairie de Ndop - Services des Marchés Publics, **Tél. : 675447413**.

Fait à Ndop, le 08 JAN 2020

Le Maire de Ndop,

Copies :

- MINMAP
- ARMP;
- Présidents CPM;
- Affichage.



*Abombo Abel Eheny*  
LORD MAYOR

Les travaux objet du présent appel d'offres sont financés par le Budget d'Investissement Publics du Cameroun de l'exercice 2020 sur les ligne d'imputation budgétaires N° 54 40 64 16 38 2221

**8. Cautionnement provisoire**

Chaque soumissionnaire doit joindre à ses pièces administratives, une caution de soumission établie par une banque de premier ordre agréée par le Ministère chargé des finances et dont la liste figure dans la pièce 12 du DAO, d'un montant de **Un million (1 000 000) FCFA** et valable pendant trente (30) jours à compter de la date originale de validité des offres.

**9. Consultation du Dossier d'Appel d'Offres**

Le Dossier d'Appel d'Offres peut être consulté et obtenu aux heures ouvrables à la Mairie de Ndop, Service de Passation des Marchés (Secrétariat Privé) Tél. : **675447413**, dès publication du présent avis.

**10. Acquisition du Dossier d'Appel d'Offres**

Le dossier peut être obtenu aux heures ouvrables à la Mairie de Ndop, Service de Passation des Marchés Publics Tél. : **675447413**, dès publication du présent avis, contre présentation d'une quittance de versement de la somme non remboursable de **Soixante-quatre mille ( 64 000 ) Francs** à la Trésorerie de la municipalité de Ndop.

**11. Remise des offres**

Chaque offre rédigée en français ou en anglais en sept (07) exemplaires dont un (01) original et six (06) copies marquées comme telles, devra parvenir contre récépissé à la Mairie de Ndop, Service de Passation des Marchés Public Tél. : **675447413** au plus tard le **30 Janvier 2020 à 10 h 00**, heure locale et devra porter la mention suivante :

**«AVIS D'APPEL D'OFFRES NATIONAL OUVERT N° 02/ AONO /CN/CIPMCN/2020 DU 8 JANVIER DANS LA COMMUNE DE NDOP DANS LE DEPARTEMENT DE NGOKETUNJIA, REGION DU NORD OUEST  
»**

**«A N'OUVRIR QU'EN SEANCE DE DEPOUILLEMENT»**

**12. Recevabilité des offres**

Sous peine de rejet, les pièces du dossier administratif requises doivent être produites en originaux ou en copies certifiées conformes par le service émetteur ou une autorité administrative (Préfet, Sous-préfet, ...), conformément aux stipulations du Règlement Particulier de l'Appel d'Offres.

Elles doivent dater de moins de trois (03) mois précédant la date originale de dépôt des offres ou avoir été établies postérieurement à la date de signature de l'Avis d'Appel d'Offres.

Toute offre incomplète conformément aux prescriptions du Dossier d'Appel d'Offres sera déclarée irrecevable. Notamment l'absence de la caution de soumission délivrée par une banque de premier ordre agréée par le Ministère chargé des Finances.

**13. Ouverture des plis**

L'ouverture des plis se fera en un temps. L'ouverture des pièces administratives et des offres techniques et financières aura lieu **30 Janvier 2020 à 11h00**, heure locale, dans la salle de conférence de la Mairie de Ndop, par la Commission interne de Passation de Marchés de la commune de Ndop siégeant en présence des soumissionnaires ou de leurs représentants dûment mandatés et ayant une parfaite connaissance du dossier.

**14. Critères d'évaluation**

*Les offres seront évaluées selon les principaux critères suivants :*

**A - Critères éliminatoires**

*Il s'agit notamment:*

- 1- Fausses déclarations ou pièces falsifiées ;
- 2- Absence ou insuffisance de la caution provisoire de soumission ;
- 3- Offres financière incomplète,
- 4- L'omission d'une quantité dans l'offre financière ;

REPUBLIQUE DU CAMEROUN  
Paix – Travail – Patrie  
-----  
MINISTERE DE LA DECENTRALISATIO  
ET DU DEVELOPPEMENT LOCAL  
-----  
REGION DU NORD OUEST  
-----  
DEPARTEMENT DE NGOKETUNJIA  
-----  
ARRONDISSEMENT DE NDOP  
-----  
COMMUNE DE NDOP  
-----  
COMMISSION INTERNE DE  
PASSATION DES MARCHE



REPUBLIC OF CAMEROON  
Peace – Work – Fatherland  
-----  
MINISTRY OF DECENTRALIZATION AND  
LOCAL DEVELOPMENT  
-----  
NORTH WEST REGION  
-----  
NGOKETUNJIA DIVISION  
-----  
NDOP SUB DIVISION  
-----  
NDOP COUNCIL  
-----  
NDOP COUNCIL INTERNAL  
TENDERS' BAORD

### AVIS D'APPEL D'OFFRES

AVIS D'APPEL D'OFFRES NATIONAL OUVERT N° 02/ AONO /CN/CIPMCN/2020 DU 8 JANVIER 2020 POUR LES TRAVAUX DE CONSTRUCTION D'UN CENTRE DE SANTE INTEGRE A MBEBAH DANS LA COMMUNE DE NDOP DANS LE DEPARTEMENT DE NGOKETUNJIA, REGION DU NORD OUEST

Financement : BUDGET D'INVESTISSEMENT PUBLIC (BIP) - EXERCICE 2020

**1. Objet de l'Appel d'Offre**

Dans le cadre de l'exercice budgétaire 2020, le Maire de Ndop, Autorité Contractante lance, par procédure d'urgence un Appel d'Offres National Ouvert pour les travaux de construction d'un Centre de Sante Intégré à MBEBAH du Département de Ngoketunja, Région du Nord-Ouest.

**2. Consistance des travaux**

Les travaux comprennent notamment :

- Travaux préparatoires
- Terrassement
- Fondations
- Maçonneries en élévations
- Charpente-couverture
- Menuiserie métallique
- Menuiserie bois
- Plomberie sanitaire
- Electricité
- Peinture et Revêtement
- VRD

**3. Délais d'exécution**

Le délai maximum prévu le Maître d'Ouvrage Délégué pour la réalisation des travaux objet du présent appel d'offres est de Cinq (05) Mois.

**4. Allotissement**

Les Les travaux sont en un (01) lot ci-après définis :  
Construction d'un Centre de Sante Intégré à MBEBAH

**5. Coût prévisionnel**

Le coût prévisionnel de l'opération à l'issue des études préalables est de Cinquante millions (50 000 000) FCFA.

**6. Participation et origine**

La participation à cette consultation est ouverte aux entreprises de droit camerounais.

**7. Financement**

**B. Essential criteria**

- 1- General presentation of the tender files;
- 2- Financial capacity;
- 3- References of the company in similar achievements;
- 4- Quality of the personnel;
- 5- Technical organization of the works;
- 6- Logistics;
- 7- Attestation and report of site visit;
- 8- Special Technical Clauses initialed in all the pages;
- 9- Special Administrative Clauses completed and initialed in all the pages.

**15. Award**

This evaluation will be done in a purely positive way (yes) or negative (no) with an acceptable minimum of 20/25 of the essential criteria taken in account.

The contract will be awarded to the bidder who would have proposed the offer with the lowest amount, in conformity with the regulations of the Tender Documents and having satisfied to 100% of the eliminatory criteria and at least 20/25 of the essential criteria.

**16. Validity of bids**

Bidders will remain committed to their offers for sixty (60) days from the deadline set for the submission of tenders.

**17. Complementary information**


Complementary technical information may be obtained during working hours from the Ndop Council, Service of Award of Public Contracts Telephone N°675447413

Done at Ndop on 08 JAN 2020

The Lord Mayor Ndop council

**Copies:**

- MINMAP
- ARMP
- Chairpersons of TB
- Notice Boards



*Mbombo Abel Ekeny*  
LORD MAYOR

## **7. Financing**

Works which form the subject of this invitation to tender shall be financed by the 2020 Public Investment Budget of the Ministry of Public Health, budget head No. **54 40 64 16 38 2221**.

## **8. Bid bond**

Each bidder must include in his administrative documents, a bid bond issued by a first-rate banking establishment approved by the Ministry in charge of finance and whose list is found in document No. 12 of the Tender File, of an amount of **One million (1 000 000) Francs CFA**, and valid for thirty (30) days beyond the date of validity of bids

## **9. Consultation of Tender File:**

The file may be consulted during working hours at the Ndop Council, Mayor's Private Secretariat Telephone N°675447413, as soon as this notice is published.

## **10. Acquisition of tender file:**

The file may be obtained from the Ndop Council Mayor Private Secretariat Telephone N°675447413 as soon as this notice is published against payment of the sum of **Sixty four thousand (64 000 CFA) Francs CFA**, payable at the Ndop Council Treasury, representing the cost of purchasing the tender file.

## **11. Submission of bids:**

Each offer drafted in English or French in 07 (seven) copies including 01 (one) original and 06 (six) copies marked as such, should reach the Ndop council service of award not later than 30<sup>th</sup> January 2020 at 10:00 AM local time and should carry the inscription:

**OPEN NATIONAL INVITATION TO TENDER N° 02/ONIT /NC/NCITB/2020 OF 8<sup>th</sup> JANUARY 2020 FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRE IN MBEBAH BAMESSING IN NGOKETUNJIA DIVISION OF THE NORTH WEST REGION.**

*"To be opened only during the bid-opening session"*

## **12. Admissibility of bids**

Under penalty of being rejected, only originals or true copies certified by the issuing service or administrative authorities (Senior Divisional Officer, Divisional Officers) must imperatively be produced in accordance with the Special Regulations of the invitation to tender.

They must obligatorily be not older than three (3) months preceding the date of submission of bids or may be established after the signature of the tender notice

Any bid not in compliance with the prescriptions of the Tender File shall be declared inadmissible. This refers especially to the absence of a bid bond issued by a first-rate bank approved by the Minister in charge of Finance.

## **13. Opening of bids:**

The bids shall be opened in a single phase. The opening of the administrative documents, the Technical and Financial offers will take place on the 30<sup>th</sup> January 2020 at 11:00 AM local time, in the Ndop Council Hall, by the Ndop Council Internal Tenders Board. Only bidders may attend or be represented by duly mandated persons of their choice.

## **14. Evaluation criteria**

The bids shall be evaluated according to the main criteria as follows:

### **A. Eliminatory criteria**

1. -False declaration or falsified documents;
2. -Absence or insufficient bid bond;;
3. -Incomplete financial file;
4. -Omission of a unit price in the financial bid;
5. -Score less than 20/25.
6. Absence or non-conformity of a document in the administrative file

REPUBLIQUE DU CAMEROUN  
Paix – Travail – Patrie  
-----  
MINISTRE DE LA DECENTRALISATION  
ET DU DEVELOPPEMENT LOCAL  
-----  
REGION DU NORD OUEST  
-----  
DEPARTEMENT DE NGOKETUNJIA  
-----  
ARRONDISSEMENT DE NDOP  
-----  
COMMUNE DE NDOP  
-----  
COMMISSION INTERNE DE  
PASSATION DES MARCHES



REPUBLIC OF CAMEROON  
Peace – Work – Fatherland  
-----  
MINISTRY OF DECENTRALIZATION AND  
LOCAL DEVELOPMENT  
-----  
NORTH WEST REGION  
-----  
NGOKETUNJIA DIVISION  
-----  
NDOP SUB DIVISION  
-----  
NDOP COUNCIL  
-----  
NDOP COUNCIL INTERNAL  
TENDERS' BOARD

## TENDER NOTICE

OPEN NATIONAL INVITATION TO TENDER N° 02/ONIT /NC/NCITB/2020 OF 8<sup>th</sup> JANUARY 2020  
FOR FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRE IN MBEBAH BAMESSING IN  
NGOKETUNJIA DIVISION OF THE NORTH WEST REGION.

Financing: MINSANTE Public Investment Budget of 2020

### 1. Subject of the invitation to tender:

Within the framework of 2020 public Investment Budget, the Lord Mayor of Ndop Council, Contracting Authority, hereby launches by the emergency procedure an Open National Invitation to Tender for the Construction of an Integrated Health Centre in **MBEBAH BAMESSING** in Ngoketunjia Division in the North West Region.

### 2. Nature of work:

Work to be done consists of

- Preparatory works
- Earth works
- Foundation
- Masonry elevation
- Carpentry-roof works
- Metallic works
- Wood works
- Sanitary/plumbing works
- Electricity
- Tiling/painting
- VDR drainage

### 3. Execution deadline

The maximum deadline provided by the Delegated Contracting Authority for the execution of the works forming the subject of this invitation to tender is **Five (05) Months**

### 4. Lots

The works is in a single lot as follows:

Construction of Integrated Health Centre MBEBAH Ndop Sub Division

### 5. Estimated cost

The estimated cost after preliminary studies is 50 000 000 (Fifty million) FCFA

### 6. Participation and origin

Participation to this invitation to tender is open to Cameroonian enterprises that are in compliance with the fiscal laws.

**Document No. 1**  
**Tender Notice**

## Table of contents

<b>A. General</b>	
Article 1: Scope of the tender.....	
Article 2: Financing.....	
Article 3: Fraud and corruption.....	
Article 4: Candidates admitted to compete.....	
Article 5: Building materials, materials, supplies, equipment and authorised services...	
Article 6: Qualification of the bidder.....	
Article 7: Visit of site of works.....	
<b>B. Tender File</b> .....	
Article 8: Content of Tender File.....	
Article 9: Clarifications on Tender File and complaints .....	
Article 10: Modification of the Tender File.....	
<b>C. Preparation of Bids</b>	
Article 11: Tender fees.....	
Article 12: Language of bid.....	
Article 13: Constituent documents of the bid.....	
Article 14: Amount of bid.....	
Article 15: Currency of bid and payment.....	
Article 16: Validity of bids.....	
Article 17: Bid bond.....	
Article 18: Varying proposals by bidders.....	
Article 19: Preparatory meeting to the establishment of bids.....	
Article 20: Form and signature of bids.....	
<b>D. Submission of bids</b> .....	
Article 21: Sealing and marking of bids.....	
Article 22: Date and time-limit for submission of bids.....	
Article 23: Out of time-limit bids.....	
Article 24: Modification, substitution and withdrawal of bids.....	
<b>E. Opening and evaluation of bids</b> .....	
Article 25: Opening of bids.....	
Article 26: Confidential nature of the procedure.....	
Article 27: Clarifications on the bid and contact with Contracting Authority.....	
Article 28: Determination of their compliance.....	
Article 29: Qualification of the bidder.....	
Article 30: Correction of errors.....	
Article 31: Conversion into a single currency.....	
Article 32: Evaluation of financial bids.....	
Article 33: National preference.....	
<b>F. Award of the contract</b> .....	
Article 34: Award.....	
Article 35: Right of the Contracting Authority to declare an invitation to tender unsuccessful or to cancel a procedure.....	
Article 36: Notification of the award of the contract.....	
Article 37: Signature of the contract.....	
Article 38: Final bond.....	

## GENERAL RULES OF THE INVITATION TO TENDER

### A. General

#### Article 1: Scope of the tender

1.1 The Contracting Authority as defined in the Special Regulations of the invitation to tender hereby launches an invitation to tender for the construction of the works described in the Tender File and briefly described in the Special Regulations.

1.2 The bidder retained or the preferred bidder must complete the works within the time-limit indicated in the Special Regulations and which time-limit runs from the date of notification of the Administrative Order.

1.2 In this Tender File, the term "day" means a calendar day.

#### Article 2: Financing

The source of financing of the works forming the subject of this invitation to tender shall be specified in the Special Regulations.

#### Article 3: Fraud and corruption

3.1 The Contracting Authority requires of bidders and contractors the strict respect of rules of professional ethics during the award and execution of public contracts. By virtue of this principle:

a) The following definitions shall be admitted:

- i) Shall be guilty of "corruption" whoever offers, gives, requests or accepts any advantage in view of influencing the action of a public official during the award or execution of a contract;
- ii) Is involved in "fraudulent manoeuvres" whoever deforms or distorts facts in order to influence the award or execution of a contract;
- iii) "Collusive practices" shall mean any form of agreement between two or among several bidders (whether the Contracting Authority is aware or not) aimed at artificially maintaining the prices of bids at levels not corresponding to those resulting from competition;
- iv) "Coercive practices" shall mean any form of harm against persons or their property or threats against them in order to influence their action during the award or execution of a contract.

b) Any proposed award shall be rejected if it is proved that the proposed preferred bidder is directly or through an intermediary, guilty of corruption or is involved in fraudulent manoeuvres, collusive or coercive practices for the award of this contract.

3.2 The Minister Delegate at the Presidency in charge of public contracts may, as a precaution, take a decision of exclusion from bidding for a period not exceeding two (2) years against any bidder found guilty of influence peddling, of conflicts of interest, insider trading, fraud, corruption or production of non-genuine documents in the bid, without prejudice to criminal proceedings that may be brought against him

#### **Article 4: Candidates allowed to compete**

4.1 If the invitation to tender is restricted, consultation is addressed to all candidates retained after a pre-qualification procedure.

4.2 Generally, the invitation to tender is addressed to all entrepreneurs, subject to the following provisions:

- (a) a bidder (including all members of a group of enterprises and all sub-contractors to the bidder) must be from an eligible country, in accordance with the funding agreement.
- (b) a bidder (including all members of a group of enterprises and all sub-contractors to the bidder) must not be in a situation of conflict of interest, subject to disqualification. A bidder shall be judged to be in a situation of conflict of interest if he:
  - i) is or was associated in the past with an enterprise (or a subsidiary of this enterprise) which provided consultancy services for the conception, preparation of specifications and other documents used within the scope of contracts awarded for this invitation to tender; or
  - ii) presents more than one bid within the context of invitation to tender, except authorised variants according to article 17, where need be; meanwhile, this does not prevent the participation of sub-contractors in more than one bid.
  - iii) The Contracting Authority or Project Owner has financial interests in the capital in a way as to compromise the transparency of the procedures of award of public contracts.
- (c) The bidder must not have been excluded from bidding for public contracts.
- (d) A Cameroonian public enterprise may participate in the consultation if it can demonstrate that it is: (i) legally and financially autonomous, (ii) managed according to commercial laws and (iii) not under the direct supervisory authority of the Contracting Authority or Project Owner.

#### **Article 5: Building materials, materials, supplies, equipment and authorised services**

5.1 Building materials, the contractor's materials, supplies, equipment and services forming the subject of this contract must originate from countries meeting the criteria of origin defined in the Special Regulations of the invitation to tender and all expenditure done within the context of the contract shall be limited to the said building materials, materials, supplies, equipment and services.

5.2 Within the meaning of this 5.1 above, the term "originate" shall designate the place where the goods are extracted, cultivated, produced, manufactured and from where the services originate.

#### **Article 6: Qualification of bidder**

6.1 As an integral part of their bid, bidders must:

- (a) submit a power of attorney making the signatory of the bid bound by the bid in a situation where it is owned by a group of persons; and
- (b) provide all information (complete or update information included in their request for pre-qualification which may have changed in the case where the candidates took part in pre-

qualification), requested of bidders in the Special Regulations of the invitation to tender, in order to establish their qualification to execute the contract.

Where necessary, bidders should provide information relating to the following points:

- (i) The production of certified balance sheets and recent turnovers;
- (ii) Access to a line of credit or availability of other financial resources;
- (iii) Orders acquired and contracts awarded;
- (iv) Pending litigations;
- (v) Availability of indispensable equipment.

6.2 Bids presented by two or more associated undertakings (joint-contracting) must satisfy the following conditions:

- (a) The bid must include all the information listed in article 6(1) above. The Special Regulations must indicate the information to be furnished by the group and that to be furnished by each member of the group;
- (b) The bid and the contract must be signed in a way that is binding on all members of the group;
- (c) The nature of the group (joint or several) must be specified in the Special Regulations and justified with the production of a joint venture agreement in due form;
- (d) The member of the group designated as the representative will represent all the undertakings vis à vis the Project Owner and Contracting Authority with regard to the execution of the Contract;
- (e) In case of joint co-contracting, the co-contractors shall share the sums which are paid by the Project Owner into a single account. On the other hand, each undertaking is paid into its own account by the Project Owner where it is joint co-contracting.

6.3 Bidders must equally present sufficiently detailed proposals to demonstrate that they comply with the technical specifications and execution time-limits set in the Special Regulations of the invitation to tender.

6.4 Bidders requesting to benefit from the margin of preference must furnish all the necessary information to prove that they satisfy the eligibility criteria set in article 33 of the General Regulations of the invitation to tender.

#### **Article 7: Visit of works site**

7.1 The bidder is advised to visit and inspect the site and its environs and obtain by himself and under his own responsibility, all the information which may be necessary for the preparation of the bid and the execution of the works. The related cost of the visit of the site shall be borne by the bidder.

7.2 The Project Owner shall authorise the bidder and his employees or agents to enter the premises and the land for the said visit but only on the express condition that the bidder, his employees and agents free the Project Owner, his employees and agents of any responsibility that may ensue and indemnify them if necessary and that they shall remain responsible for any deadly or corporal accident, loss or material damages, costs and fees incurred from this visit.

7.3 The Project Owner may organise a visit of the site of the works during the preparatory meeting to establishing the bids mentioned in article 19 of the General Regulations of the invitation to tender.

#### **B. Tender File**

## **Article 8: Content of Tender File**

8.1 The Tender File describes the works forming the subject of the contract, sets the consultation procedure of contractors and specifies the terms of the contract. Besides the addendum (addenda) published in accordance with article 10 of the General Regulations of the invitation to tender, it includes the following documents:

- Document No. 1. The tender notice;
- Document No. 2. The General Regulations of the invitation to tender;
- Document No. 3. The Special Regulations of the invitation to tender;
- Document No. 4. The Special Administrative Conditions;
- Document No. 5. The Special Technical Conditions;
- Document No. 6. The schedule of unit prices;
- Document No. 7. The bill of quantities and estimates;
- Document No. 8. The sub details of unit prices;
- Document No. 9. Model documents of the contract:
  - a. The execution schedule;
  - b. Model of forms presenting the equipment, personnel and references;
  - c. Model bidding letter;
  - d. Model bid bond;
  - e. Model final bond;
  - f. Model of bond of start-off advance;
  - g. Model of guarantee in replacement of the retention fund;
  - h. Model contract;
- Document No. 10. Models to be used by bidders;
  - a. Model contract;
- Document No. 11. Justifications of preliminary studies; to be filled by the Project Owner or Delegated Project Owner;
- Document No. 12. List of first grade banking establishments or financial institutions approved by the Minister in charge of Finance authorised to issue bonds for public contracts to be inserted by the Contracting Authority.

8.2 The bidder must examine all the regulations, forms, conditions and specifications contained in the Tender File. It is up to him to furnish all the information requested and prepare a bid in compliance with all aspects of the said file.

## **Article 9: Clarifications on the Tender File and complaints**

9.1 Any bidder who wants to obtain clarifications on the Tender File may request them from the Contracting Authority in writing or by electronic mail (fax or e-mail) at the Contracting Authority's address indicated in the Special Regulations of the invitation to tender and send a copy to the Project Owner. The Contracting Authority replies in writing to any request for clarification received at least fourteen (14) days prior to the deadline for the submission of bids.

A copy of the Contracting Authority's response, indicating the question posed but not mentioning the author, is addressed to all bidders who bought the Tender File.

9.2 Between the publication of the tender notice including the pre-qualification phase of candidates and the opening of bids, any bidder who feels aggrieved in the public contracts award procedure may lodge a complaint to the Minister in charge of Public Contracts.

9.3 A copy of the complaint should be addressed to the Contracting Authority and to the body in charge of the regulation of public contracts and the chairperson of the Tenders Board.

9.4 The Contracting Authority has five (5) days to react. A copy of the reaction shall be forwarded to MINMAP and the body in charge of the regulation of public contracts.

#### **Article 10: Amendment of the Tender File**

10.1 The Contracting Authority may at any moment, prior to the deadline for the submission of bids and for any reason, be it at his initiative or in reply to a request for clarification formulated by a bidder, amend the Tender File by publishing an addendum.

10.2 Any published addendum shall be an integral part of the Tender File, in accordance with article 8.1 of the General Regulations of the invitation to tender and must be communicated in writing or made known by a traceable means to all bidders who bought the Tender File.

10.3 In order to give bidders sufficient time to take account of the addendum in the preparation of their bids, the Contracting Authority may postpone as is necessary, the deadline for the submission of bids, in accordance with provisions of article 22 of the General Regulations of the invitation to tender.

### **C Preparation of bids:**

#### **Article 11: Tender costs**

The candidate shall bear the costs related to the preparation and presentation of his bid and the Contracting Authority and the Project Owner shall in no case be responsible for these costs nor pay for them whatever the evolution or outcome of the invitation to tender procedure.

#### **Article 12: Language of bid**

The bid as well as any correspondence and any document exchanged between the bidder and the Contracting Authority shall be written in English or French. Complementary documents and the forms provided by the bidder may be written in another language on condition that a precise translation into either English or French of the passages concerning the bid is included; in which case for reasons of interpretation, the translation shall be considered to be authentic.

#### **Article 13: Constituent documents of the bid**

13.1 The bid presented by the bidder shall include the documents detailed in the Special Regulations of the invitation to tender, duly filled and put together in three volumes:

##### **a. Volume 1: Administrative file**

It includes:

- i) all documents attesting that the bidder:
  - has subscribed to all declarations provided for by the laws and regulations in force;
  - paid all taxes, duties, contributions, fees or deductions of whatever nature;
  - is not winding up or bankrupt;
  - is not the subject of an exclusion order or forfeiture provided for by the law in force;
- ii) The bid bond established in accordance with the provisions of article 17 of the General Regulations of the invitation to tender;
- iii) the written confirmation empowering the signatory of the bid to commit the bidder, in accordance with the provisions of article 6(1) the General Regulations of invitation to tender.

**b. Volume 2: Technical bid**

**b.1 Information on qualifications**

The Special Regulations list the documents to be furnished by bidders to justify the qualification criteria mentioned in article 6(1) of the Special Regulations of the invitation to tender.

**b.2 Methodology**

The Special Conditions of the invitation to tender specify the constituent elements of the technical bid of the bidders especially: a methodological statement on an analysis of the works and specifying the organisation and programme which the bidder intends to put in place or use to execute the works (installations, schedule, Quality Assurance Plan (QAP), sub-contracting, attestation of visit of the site, where necessary, etc).

**b.3 Proof of acceptance of conditions of the contract**

The bidder shall submit duly initialled copies of the administrative and technical documents relating to the contract, namely:

1. The Special Administrative Conditions (SAC);
2. The Special Technical Conditions (STC).

**b.4 Commentaries (optional)**

A commentary on the technical choices of the project and possible proposals.

**c. Volume 3: Financial bid**

The Special Regulations specify the elements that will help in justifying the cost of the works, namely:

1. The signed and dated original bid prepared according to the attached model, stamped at the prevailing rate;
2. The duly filled Unit Price Schedule;
3. The duly filled detailed estimates;
4. The sub-details of prices and/or breakdown of all-in prices;
5. The projected schedule of payments, where need be.

In this regard, the bidders will use the documents and models provided in the Tender File, subject to the provisions of article 17(2) of the General Regulations of the invitation to tender concerning the other possible forms of guarantees.

- 13.2 If in accordance with the provisions of the Special Regulations of the invitation to tender, the bidders present bids for several lots of the same invitation to tender, they could indicate rebates offered in case of award of more than one lot.

**Article 14: Bid price**

- 14.1 Except otherwise stated in the Tender File, the amount of the contract shall cover all the works described in article 1.1 of the General Regulations of the invitation to tender, on the basis of the price schedule and the detailed bill of quantities and estimates presented by the bidder

- 14.2 The bidder shall fill the unit prices and totals of all items on the schedule and bill of quantities and estimates.

14.3 Subject to contrary provisions provided for in the Special Regulations and in the Special Administrative Conditions, all dues, taxes and fees payable by the bidder on grounds of the contract or on any other ground, thirty (30) days prior to the submission of the bids, shall be included in the prices and in the total amount of the bid presented by the bidder.

14.4 If a price revision/updating clause is provided for in the contract, the date of establishment of the initial price, as well as the price revision/updating conditions for the said price must be specified. This is with the understanding that any contract of duration less than one (1) year shall not be subject to price revision.

14.5 All unit prices must be justified by sub-details established in accordance with the structure proposed in document 8 of the Tender File.

#### **Article 15: Currency of bid and payment**

15.1 In case of international invitations to tender, the currencies of the bid shall follow the provisions of either Option A or Option B below, the applicable option being that retained in the Special Regulations of the invitation to tender.

**15.2 Option A:** The amount of the bid shall be entirely made in the national currency.

The amount of the bid, unit prices of the price schedule and the prices of the bill of quantities and estimates are completely made in CFA francs in the following manner:

- a) Prices shall be entirely drawn in the national currency. The bidder who intends to commit expenditures in other currencies for the execution of the works shall indicate in the annex to the bid the percentage(s) of the amount of the bid necessary to cover the needs in foreign currencies, without exceeding the maximum of the three currencies of member countries of the funding institution of the contract.
- b) The exchange rates used by the bidder to convert his bid into the national currency shall be specified by the bidder in an annex to the bid in compliance with the specifications of the Special Regulations. These rates shall be applied for any payment within the framework of the contract so that the retained bidder does not bear any change in the exchange rate.

**15.3 Option B:** The amount of the bid shall be directly made in the national and foreign currency at the rates fixed in the Special Regulations.

The bidder shall draw the unit prices of the price schedule and the prices of the bill of quantities and estimates in the following manner:

- (a) The prices of inputs necessary for the works which the bidder intends to procure in the Contracting Authority's country shall be in currency of the Contracting Authority's country specified in the Special Regulations and called "national currency";
- (a) The prices of inputs necessary for works which bidder intends to procure out of the Contracting Authority's country shall be in the currency of the country of origin of the bidder or of the currency of an eligible member country widely used in international trade.

15.4 The Contracting Authority may request the bidders to explain the needs in national and foreign currencies and to justify that the amounts included in the unit and total prices and indicated in annex to the bids are reasonable; to this end, a detailed statement of their needs in foreign currencies shall be furnished by the bidder.

15.5 During the execution of the works, most of the foreign currency to be paid as part of contract may be revised by mutual agreement between the Contracting Authority and the entrepreneur in a way as to take account of any modification in the foreign currency needs within the context of the contract.

#### **Article 16: Validity of bids**

16.1 Bids must remain valid during the period stated in the Special Regulations from the date of submission of the bids fixed by the Contracting Authority, in application of article 22 of the Special Regulations. A bid valid for a shorter period shall be rejected by the Contracting Authority or Delegated Contracting Authority as not being in compliance.

16.2 Under exceptional circumstances, the Contracting Authority may seek the approval of bidders to extend the validity time-limit. The request and the responses that will be given shall be in writing (or by fax). The validity of the bid bond provided for in article 17 of the General Regulations shall equally be extended for a corresponding duration. A bidder may refuse to extend the validity of his bid without losing his bid bond. A bidder who consents to an extension shall not be asked to modify his bid nor shall he be authorised to do so.

16.3 Where the contract does not include a price revision clause and that the period of validity of bids is extended by more than sixty (60) days, the amounts payable to the bidder retained shall be updated by application of the related formula featuring in the request for extension that the Contracting Authority addressed to bidders.

The updating period shall run from the date of overrun of sixty (60) days to the date of notification of the contract or the Administrative Order for start of execution of works by the retained bidder, as specified in the Special Administrative Conditions. The effect of updating shall not be taken into account for purposes of evaluation of bids.

#### **Article 17: Bid bond**

17.1 In application of article 13 of the General Regulations, the bidder shall furnish a bid bond of the amount specified in the Special Regulations and which bid bond shall be a full part of his bid.

17.2 The bid bond must conform to the model presented in the Tender File; other models may be authorised subject to the prior approval of the Contracting Authority. The bid bond will remain valid for thirty (30) days beyond the original date set for the validity of bids or any other validity time-limit requested by the Contracting Authority and accepted by the bidder, in accordance with the provisions of article 16 (2) of the General Regulations.

17.3 Any bid without an acceptable bid bond shall be rejected by the Tenders Board as not in conformity. The bid bond of associated enterprises must be established in the name of the group submitting the bid and mention each member of the associated grouping.

17.4 The bid bonds of bidders who are not retained shall be returned within fifteen (15) days after publication of the award result.

17.5 The bid bond of the successful bidder shall be released as soon as the latter would have signed the contract and furnished the required final bond.

17.6 The bid bond may be seized:

(a) if the bidder withdraws his bid during the period of validity;

(b) if the retained bidder:

- i) fails in his obligation to register the contract in application of article 38 of the General Regulations;
- ii) fails in his obligation to furnish the required final bond in application of article 38 of the General Regulations;
- iii) refuses to receive notification of the Administrative Order to commence execution.

### **Article 18: Varying proposals of bidders**

18.1 Where the works can be executed within variable deadlines, the Special Regulations shall specify these deadlines and shall indicate the method retained for the evaluation of the completion deadline proposed by the bidder within the specified deadlines. Bids that propose deadlines beyond those specified shall be considered as not being in conformity.

18.2 Except in the case mentioned in article 18(3) below, bidders wishing to offer technical variants must first assess the basic solution of the Contracting Authority as described in the Tender File and furnish in addition all the information which the Contracting Authority needs for a complete evaluation of the proposed variant, including the plans, calculations, technical specifications, sub-details of prices and proposed construction methods and all other useful information. If necessary, the Contracting Authority will examine only the technical variants of the bidder whose bid is in compliance with the basic solution has been evaluated as the lowest bid.

18.3 When according to the Special Regulations the bidders are authorised to directly submit the technical variants for certain parts of the works, these parts of the works must be described in the technical specifications. Such variants shall be evaluated on their own merit in accordance with the provisions of article 31(2) (g) of the General Regulations.

### **Article 19: Preparatory meeting to the establishment of bids**

19.1 Except otherwise stipulated in the Special Regulations, a bidder may be invited to take part in a preparatory meeting which will hold at the date and place indicated in the Special Regulations.

19.2 The subject of the preparatory meeting shall be to furnish clarifications and answer any questions which may be raised at this stage.

19.3 As much as possible, the bidder is requested to submit any question in a way as to reach the Contracting Authority at least one week before the meeting. The Contracting Authority may not reply to questions received too late. In this case, the questions and answers shall be transmitted according to the methods set in article 19(4) below.

19.4 The minutes of the meeting, including the text of the questions asked and the replies given, including questions prepared after the meeting, shall be forwarded immediately to everyone who bought the Tender File. Any modification of documents of the Tender File listed in article 8 of the General Regulations which may prove to be necessary at the end of the preparatory meeting shall be done by the Contracting Authority by publishing an addendum in accordance with the provisions of article 10 of the General Regulations and not through the minutes of the preparatory meeting.

19.5 The fact that a bidder does not attend a preparatory meeting for the establishment of bids shall not be a reason for disqualification.

### **Article 20: Form and signature of bid**

20.1 The bidder shall prepare an original of the constituent documents described in article 13 of the General Regulations in a volume clearly indicated "ORIGINAL". In addition, the bidder shall submit the number required in the General Regulations, bearing "COPY". In case of discrepancy, the original shall be considered as authentic.

20.2 The original and copies of the bid must be typed or written in indelible ink (photocopies shall be accepted in the case of copies) and shall be signed by the person(s) duly empowered to sign on behalf of the bidder, in accordance with article 6(1a) or 6(2c) of the General Regulations, as the case may be. All the pages of the bid containing alterations or changes must be initialled by the signatory (ies) of the bid.

- 20.3 The bid shall bear no modification, suppression or alteration unless such corrections are initialed by the signatory(ies) of the bid.

#### **D. SUBMISSION OF BIDS**

##### **Article 21: Sealing and marking of bids**

21.1 The bidder shall seal the original and each copy of the bid in separate envelopes (internal envelopes) by marking on these envelopes "**ORIGINAL**" and "**COPY**", as the case may be. The envelopes shall then be placed in another envelope which will equally be sealed but which will not give any indication regarding the identity of the bidder.

21.2 The external and internal envelopes:

a) should be addressed to the Contracting Authority at the address indicated in the Special Regulations;

b) should bear the name and identification number of the project as indicated in the Special Regulations and bear the inscription "**TO BE OPENED ONLY DURING THE BID-OPENING SESSION**" as specified in the Special Regulations.

21.3 The internal envelopes should equally carry the name and address of the bidder in a way as to enable the Contracting Authority return the sealed bid if it is late in accordance with article 23 and 24 of the General Regulations.

21.4 If the external envelope is not sealed and marked as indicated in paragraphs 21(1) and 21(2) above, the Contracting Authority shall not be responsible if the bid is misplaced or opened prematurely.

##### **Article 22: Date and time-limit for submission of bids**

22.1 The bids must be received by the Contracting Authority at the address specified in article 21(2) of the Special Regulations not later than the date and time stated in the Special Regulations.

22.2 The Contracting Authority may, at his discretion, postpone the deadline set for the submission of the bids by publishing an addendum in accordance with the provisions of article 10 of the General Regulations. In this case, all the rights and obligations of the Contracting Authority and bidders previously governed by the initial date will henceforth be governed by the new date.

##### **Article 23: Late bids**

Any bid received by the Contracting Authority beyond the deadline for the submission of bids in accordance with article 22 of the General Regulations shall be declared late and consequently rejected.

##### **Article 24: Modification, substitution and withdrawal of bids**

24.1 A bidder may modify or withdraw his bid after submitting it, on condition that the written notification of the modification or withdrawal is received by the Contracting Authority prior to the end of the time-limit prescribed for the submission of the bids. The said notification must be signed by an authorised representative in application of article 20(2) of the General Regulations. The modification or the corresponding replacement bid must be attached to the written notification. As the case may be, the envelopes must bear the inscription "**WITHDRAWAL**", and "**REPLACEMENT BID**" or "**MODIFICATION**".

- 24.2 Notification of modification, replacement or withdrawal of the bid by the bidder should be prepared, sealed, marked and forwarded in accordance with the provisions of article 21 of the General Regulations. Withdrawal may equally be notified by telex but should in this case be confirmed by a duly signed written notification whose date, post mark being authentic, shall not be posterior to the time-limit set for the submission of bids.
- 24.3 In application of article 24(1), bids being requested to be withdrawn by bidders shall be returned to them unopened.
- 24.4 No bid may be withdrawn during the interval between the submission of bids and the expiry of the validity of bids specified by the model tender. The withdrawal of a bid by a bidder during this interval may lead to the confiscation of the bid bond in accordance with the provisions of article 17(6) of the General Regulations.

#### **E. Opening of envelopes and evaluation of bids**

##### **Article 25: Opening of envelopes and petitions**

- 25.1 The competent Tenders Board shall open the envelopes in single or double phases and in the presence of the representatives of bidders who wish to attend at the date, time and address specified in the Special Regulations. Representatives of bidders shall sign a register attesting to their presence.
- 25.2 Firstly, envelopes marked "**withdrawal**" shall be opened and the contents announced to the hearing of everyone, while the envelope containing the corresponding bid shall be returned to the bidder unopened. Withdrawal shall be allowed only if the corresponding notification contains a valid empowerment of the signatory to request this withdrawal and if this notification is read to the hearing of everyone. Then the envelopes marked "**Replacement bid**" are opened and announced to the hearing of everyone and the new corresponding bid substituted for the preceding one which will be sent to the bidder concerned unopened. The replacement of the bid shall only be allowed if the corresponding notification contains a valid empowerment of the signatory requesting the replacement and read to the hearing of everyone. Lastly, the envelopes marked "**modification**" shall be opened and their contents read to the hearing of everyone with the corresponding bid. The modification of the bid shall only be allowed if the corresponding notification contains a valid empowerment of the signatory requesting the modification and read to the hearing of everyone. Only bids which were opened and announced to the hearing of everyone during the opening of bids shall then be evaluated.
- 25.3 All envelopes shall be opened successively and the name of the bidder announced aloud as well as the possible modification mentioned, the price offered, including any rebates [*in case of opening of financial bids*] and any variant, where necessary, the existence of a guarantee of the bid if it is required and any other details which the Contracting Authority deems useful to be mentioned. Only rebates and variants of bids announced to the hearing of everyone during the opening of bids shall be submitted for evaluation.
- 25.4 Bids (and modifications received in accordance with the provisions of article 24 of the General Regulations) which were not opened and read to the hearing of everyone during the bid-opening session for whatever reason, shall not be submitted for evaluation.
- 25.5 Bid-opening minutes are recorded on the spot mentioning the admissibility of bids, their administrative regularity, prices, rebates and time-limits as well as the composition of the Evaluation sub-committee. A copy of the said minutes to which is attached the attendance sheet is handed over to all the participants at the end of the session.

25.6 At the end of each bid-opening session, the chairperson of the Tenders Board immediately hands over to the focal point designated by the body in charge of regulation of public contract an initialled copy of the bids presented by bidders.

25.7 In case of petition as provided for by the Public Contracts Code, it should be addressed to the Minister Delegate in charge of Public Contracts with copies to the body in charge of the regulation of public contracts, the head of structure to which is attached the Tenders Board concerned.

It must reach within a maximum deadline of three (3) working days after the opening of bids in the form of a letter to which is obligatorily attached a sheet of the petition form duly signed by the petitioner and possibly by the chairperson of the Tenders Board.

The Independent Observer attaches to his report the sheet that was handed to him, including any related commentaries or observations.

#### **Article 26: Confidential nature of the procedure**

26.1 No information relating to the examination, clarification, evaluation and comparison of bids and verification of the qualification of the bidders and the recommendation for the award shall be given to bidders or to any person not concerned with the said procedure as long as the preferred bidder has not been made public, subject to the disqualification of the bid of the bidder and suspension of the authors from all activities in the domain of public contracts.

26.2 Any attempt by a bidder to influence the Tenders Board or the Evaluation sub-committee of bids or the Contracting Authority in its award decision may lead to the rejection of his bid.

26.3 Notwithstanding the provisions of paragraph 26.2 above, between the opening of bids and the award of the contract, if a bidder wishes to enter into contact with the Contracting Authority for reasons having to do with his bid, he may do so in writing.

#### **Article 27: Clarifications on the bids and contact with the Contracting Authority**

27.1 To ease the examination, evaluation and comparison of bids, the Tenders Board may, if it so desires, request any bidder to give clarifications on his bid. This request for clarification and the response thereto are formulated in writing but no change on the amount or content of the bid is sought, offered or authorised, except it is necessary to confirm the correction of calculation errors discovered by the Evaluation Sub-committee during the evaluation in accordance with the provisions of article 30 of the General Regulations.

27.2 Subject to the provisions of paragraph 1 above, bidders shall not contact members of the Tenders Board and the Evaluation Sub-committee for questions related to their bids, between the opening of envelopes and the award of the contract.

#### **Article 28: Determination of compliance of bids**

28.1 The Evaluation sub-committee shall carry out a detailed examination of bids to determine if they are complete, if the required guarantees are furnished, if the documents were correctly signed and if generally the bids are in proper order.

28.2 The Evaluation sub-committee shall determine if the bid is essentially in compliance with the conditions fixed in the Tender File based on the content without recourse to external elements of proof.

28.3A bid that complies with the Tender File shall essentially be a bid that respects all the terms, conditions and specifications of the Tender File, without substantial divergence or reservation. A substantial divergence or reservation is that:

- i) which substantially limits the scope, quality or realisation of the works;
- ii) which substantially limits, contrary to the Tender File, the rights of the Contracting Authority or his obligations in relation to the contract;
- iii) Whose correction would unjustly affect the competitiveness of the other bidders who presented bids that essentially complied with the Tender File.

28.4 If a bid is essentially not in compliance, it shall be rejected by the competent Tenders Board and shall not subsequently be rendered in compliance.

28.5 The Contracting Authority reserves the right to accept or reject any modification, divergence or reservation. Modifications, divergences, variants and other factors which are beyond the requirements of the Tender File shall not be considered during the evaluation of bids.

#### **Article 29: Qualification of the bidder**

The Evaluation sub-committee shall ensure that the successful bidder retained for having submitted a bid substantially in compliance with the provisions of the Tender File, fulfils the qualification criteria stipulated in article 6 of the Special Regulations. It is essential to avoid any arbitrariness in determining qualification.

#### **Article 30: Correction of errors**

30.1 The Evaluation sub-committee shall verify bids considered essentially in compliance with the Tender File to correct the possible calculation errors. The Evaluation sub-committee shall correct the errors in the following manner:

- (a) where there is an incoherence between the unit price and the total obtained by multiplying the unit price by the quantity, the unit price being authentic, the total price shall be corrected, unless the Evaluation sub-committee judges that it is a gross error of decimal point in the unit price in which case the total price as presented shall be authentic and the unit price corrected.
- (b) if the total obtained by addition or subtraction of the totals is not exact, the sub totals shall be considered authentic and the total corrected.
- (c) where there is a difference between the price indicated in letters and in figures, the amount in letters shall be considered authentic, unless the amount is linked to an arithmetical error confirmed by the sub-detail of the said price, in which case the amount in figures shall prevail subject to paragraphs (a) and (b) above.

30.2 The amount featuring in the bid shall be corrected by the Evaluation sub-committee, in accordance with the error correction procedure above and with confirmation by the bidder, the said amount shall be deemed to commit him.

30.3 If the bidder who presented the bid evaluated as the lowest refuses the correction thus carried out, his bid shall be rejected and the bid bond may be seized.

#### **Article 31: Conversion into a single currency**

31.1 To facilitate the evaluation and comparison of bids, the Evaluation sub-committee shall convert the prices of bids expressed in various currencies into those in which the bid is payable in CFA francs.

31.2 The conversion shall be done using the selling rate fixed by the Bank of Central African States (BEAC) under the conditions defined by the Special Regulations.

#### **Article 32: Evaluation and comparison of financial bids**

32.1 Only bids considered as being in compliance, as per the provisions of article 28 of the General Regulations, shall be evaluated and compared by the Evaluation sub-committee.

32.2 By evaluating the bids, the Evaluation Sub-committee shall determine for each bid the evaluated amount of the bid by rectifying the amount as follows:

- a) By correcting any possible error in accordance with the provisions of article 30.2 of the General Regulations;
- b) By excluding projected sums and where necessary provisions for unforeseen occurrences featuring in the bill of quantities and estimates but by adding the amount of works done under State supervision where they are costed in a competitive manner as specified in the Special Regulations.
- c) By converting into a single currency the amount resulting from the rectifications (a) and (b) above, in accordance with the provisions of article 31(2) of the General Regulations;
- d) By appropriately adjusting any other modification, divergence or quantifiable reservation on technical or financial basis.
- e) By taking into consideration the various execution time-limits proposed by the bidders, if they are authorised by the Special Regulations;
- f) If need be, in accordance with the provisions of article 13(2) of the General Regulations and the Special Regulations by applying the rebates offered by the bidder for the award of more than one lot, if this invitation to tender is launched simultaneously for several lots.
- g) If need be, in accordance with the provisions of article 18(3) of the Special Regulations and the Technical Specifications, the proposed technical variants, if they are permitted, shall be evaluated on their own merit and independently of the fact that the bidder offered or not a price for the technical solution specified by the Contracting Authority in the Special Regulations.

32.3 The estimated effect of price revision formulae featuring in the GAC and SAC applied during the period of execution of the contract shall not be considered during the evaluation of bids.

32.4 If the bid judged the lowest bid is considered abnormally low or strongly unbalanced in relation to the estimates of the Project Owner for the works to be executed in this contract, the Tenders Board may, from the sub-details of prices furnished by the bidder for any element or all the elements of the bill of quantities and estimates, verify if these prices are compatible with the construction methods and proposed calendar. In the case where the justifications presented by the bidder are not satisfactory, the Contracting Authority may reject the bid after the technical opinion of the Public Contracts Regulatory Agency.

#### **Article 33: Preference granted national bidders**

National contractors shall benefit from a margin of national preference during the evaluation of bids as provided for in the Public Contracts Code.

#### **Article 34: Award**

- 34.1 The Contracting Authority shall award the contract to the bidder whose bid was judged essentially in compliance with the Tender File and who has the required technical and financial capacities to execute the contract satisfactorily and whose bid was evaluated as the lowest by including, where necessary, proposed rebates
- 34.2 If, according to article 13(2) of the General Regulations, the invitation to tender comprises several lots, the lowest bid shall be determined by evaluating this contract with other lots to be awarded concurrently, by taking into account the rebates offered by the bidders in the case of more than one lot.
- 34.3 Any award of contract shall be made to the bidder fulfilling the technical and financial capacities required resulting from the evaluation criteria and presenting the bid evaluated as the lowest.

**Article 35: The right by the Contracting Authority to declare an invitation to tender unsuccessful or cancel a procedure**

The Contracting Authority reserves the right to cancel a procedure of invitation to tender after the authorisation of the Minister Delegate at the Presidency in charge of Public Contracts where the bids have been opened or to declare an invitation to tender unsuccessful after the advice of the competent Tenders Board, without any claims being entertained.

**Article 36: Notification of award of the contract**

Before the expiry of the validity of the bids set in the Special Regulations, the Contracting Authority shall notify the preferred bidder by telecopy confirmed by registered mail or by any other means that his bid was retained. This letter will indicate the amount the Project Owner will pay the contractor to execute the works and the execution time-limit.

**Article 37: Publication of results of award and petitions**

37.1 The Contracting Authority shall communicate to any bidder or administration concerned, upon request addressed to it within a maximum deadline of five (5) days after publication of the award results, the Independent Observer's report as well as the minutes of the award session of the related contract to which shall be attached the evaluation report of the bids.

37.2 The Contracting Authority is bound to communicate the reasons for the rejection of bids of the bidders concerned who so request.

37.3 After publication of the award results, bids that are not withdrawn within fifteen (15) days shall be destroyed, without any claims for compensation being entertained. Only the copy destined for the body in charge of regulation shall be kept.

37.4 In case of petition, it should be addressed to the Public Contracts Authority, with copies to the body in charge of the regulation of public contracts, the Contracting Authority and the chairperson of the Tenders Board concerned.

It must take place within a maximum deadline of five (5) working days after the publication of the results.

**Article 38: Signing of the contract**

38.1 After publication of the results, the draft contract subscribed by the successful bidder is submitted to the Tenders Board for examination and where applicable, to the Minister in charge of Public Contracts for prior endorsement.

38.2 The Contracting Authority has a deadline of seven (7) days to sign the contract from the date of reception of the draft contract examined by the competent Tenders Board and subscribed by

the successful bidder and where applicable, the endorsement of the Minister in charge of Public Contracts.

38.3 The contract must be notified to the successful bidder within five (5) days of its date of signature.

**Article 39: Final Bond**

39.1 Within twenty (20) days of the notification by the Contracting Authority, the contractor shall furnish the Project Owner with a final bond, to guarantee the complete execution of the works.

39.2 The bond whose rate varies between 2 and 5 percent of the amount of the contract inclusive of all taxes, may be replaced by a guarantee from a banking establishment approved according to the instruments in force with the Project Owner as beneficiary or by a joint or several guarantee.

39.3 Small and medium-sized enterprises (SME) constituted of national capital and managed by nationals may, in lieu of the guarantee, provide a statutory lien or a bond issued by a banking establishment or first rate financial institution approved in accordance with the instruments in force.

39.4 Failure to produce the final bond within the prescribed time limit shall likely cause the termination of the contract under the terms laid down in the General Administrative Conditions.

**DOCUMENT No. 3: SPECIAL REGULATIONS OF THE  
INVITATION TO TENDER**

## Special regulations of the invitation to tender

References of the General regulations	General
1.1	<p><b>Definition of works:</b>  <b>Construction of an Integrated Health Centre in MBEBAH in Ngoketunjia Division in the North West Region.</b></p> <p>Name and address of the Contracting Authority: , The Lord Mayor of Ndop , Delegated Contracting Authority</p> <p>Reference of Invitation to tender: N° 2/ONIT /NC/NCITB/2020 OF 8<sup>th</sup> January 2020</p>
1.2	Execution deadline: 5 five months
2.1	<p><b>Source of financing</b>  Works which form the subject of this invitation to tender shall be financed by the 2020 Public Investment Budget of the Ministry of Basic Education, budget head- No. <b>54 40 64 16 38 2221</b></p>
4.1	List of pre-qualified candidates, not applicable
5.1	<p>Origin of building materials, equipment, materials, supplies and equipment:  The materials will generally be from natural sources in Cameroon.</p>

### **6.1 Evaluation criteria**

The bids shall be evaluated according to the main criteria as follows:

#### **C. Eliminary criteria**

1. -False declaration or falsified documents;
2. Absence or insufficient bid bond;
3. -Incomplete financial file;
4. -Omission of a unit price in the financial bid;
5. -score less than **20/25** of essential criteria.
6. Absence or non-conformity of a document in the administrative file

#### **D. Essential criteria**

- 1- General presentation of the tender files;
- 2- Financial capacity;
- 3- References of the company in similar achievements;
- 4- Quality of the personnel;
- 5- Technical organization of the works;
- 6- Logistics;
- 7- Attestation and report of site visit;
- 8- Special Technical Clauses initialed in all the pages;
- 9- Special Administrative Clauses completed and initialed in all the pages.

The criteria relating to the qualification of candidates could be indicative on the following:

The essential criteria are subjected to minima whose detail is given in the Special Tender Regulation (RPAO).

This evaluation will be done in a purely positive way (yes) or negative (no) with an acceptable minimum from at least 80% of the essential criteria taken in account.

The contract will be awarded to the bidder who would have proposed the offer with the lowest amount, in conformity with the regulations of the Tender Documents and having satisfied to 100% of the eliminatory criteria and at least 80% of the essential criteria.

**ARTICLE 6 : Language of the bids:**

The offer like any correspondence and all documents concerning the tender, exchanged between the tenderer and the Project Owner will be written in French or English. The complementary documents and the printed papers form provided by the Bidder can be written in another language on condition of being accompanied by a precise translation in French or English; in which case and for purposes of interpretation of the offer, the translation will be taken.

**PRESENTATION OF THE TENDER.**

The bids prepared in English or French and in seven (07) copies with one (01) original and six (06) copies marked thus, shall be presented in three (03) volumes as follows:

- A) Administrative Documents
- B) Technical Documents
- C) Financial Documents

**5.1 External envelope.**

Each bidder shall seal these three (03) envelopes (A, B and C) in one common envelope on which shall be written:

**<<OPEN NATIONAL INVITATION TO TENDER N° 02/ONIT /NC/NCITB/2020 OF 8<sup>th</sup> JANUARY 2020 FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRE IN MBEBAH BAMESSING IN NGOKETUNJIA DIVISION OF THE NORTH WEST REGION IN NGOKETUNJIA DIVISION OF THE NORTH WEST REGION.>>**

**"TO BE OPENED ONLY DURING THE BID-OPENING SESSION"**

N.B: The external envelope should not carry any mark or sign that can lead to the identification of the bidder.

**8.2 Internal envelopes**

Three (03) internal envelopes must be sealed in an external envelope.

The first internal envelope shall be labeled;

**<<ENVELOPE A: ADMINISTRATIVE DOCUMENTS>>** and shall contain the administrative documents of the enterprise. These documents shall be original or copies certified by competent authorities not more than three months.

**ADMINISTRATIVE DOCUMENTS.**

DOCUMENT N°	DESCRIPTION
A.1	Certified Copy of the Business Registration, not more than three months old.
A.2	Declaration of intention to tender stamped with the tariff in force (written by the bidder).
A.3	Certificate of non-bankruptcy established by the Court of 1st instance or the Chamber of Commerce, Industry and Trade of the place of residence of the bidder, not more than three (03) months.
A.4	Attestation of bank account of the bidder, issued by a first rate-bank approved by the Ministry in charge of Finance or by a foreign bank of the first order not more than three months.
A.5	Purchase receipt of tender file issued by public treasury
A.6	A bid bond of 1 000 000 FCFA (one million FCFA) as the case may be issued by a first rate-bank approved by the Ministry in charge of Finance in conformity with COBAC conditions
A.7	An attestation of non-exclusion from Public Contracts issued by the Public contract Regulatory Board (ARMP)
A.8	An Attestation of the National Social Insurance Fund stating that the bidder has met all his obligations vis a vis the Fund; the attestation should be less than three months old.
A.9	A valid Certificate of imposition certified by the chief of center for taxation
A.10	Business License (photocopy certified by the chief of center of Taxes, not more than three months).
A.11	Certified Copy of a valid taxpayers card, delivered by the chief of center of Taxes.
A.12	A Clearance Certificate signed by the chief of Centre of Taxes that the bidder has met all the statutory declarations in issues of taxes in the current financial year; this certificate should be less than three months old.

The absence or the nonconformity of any one of these documents will result to the elimination of the offer.

The second Internal Envelope shall be labeled <<ENVELOPE B: TECHNICAL DOCUMENT>> and shall contain the following:

<b>B.1</b>	<b>General presentation of the tender files</b>		
B.1.1	- Document spirally bound - Table of content page		
B.1.2	- Colour sheets separation - Presentation of documents in the order given in this tender		
<b>B.2</b>	<b>LIST OF REFERENCES OF THE ENTERPRISE IN THE SIMILAR JOBS</b>		
B.2.1	List of references of the enterprise in similar jobs justified by signed contracts (first and last pages) and minutes of reception or attestation of clearances of works executed. (minutes of final reception for up to 2018 projects) Minimum acceptable: 02 Contracts realized in the domain of building construction over the past 06 years		
	1 <sup>st</sup> Reference		
	2 <sup>nd</sup> reference		
<b>B.3</b>	<b>QUALIFICATION AND EXPERIENCE OF SUPERVISORY STAFF FOR EACH LOT</b>		
B.3.1	<b>01 works supervisor (at least HND or equivalent certificate)</b>		
	Qualification of the works supervisor: (Senior Technician certificate in Civil Engineering (BAC +2) Professional experience of the project engineer $\geq$ 03 years (signed CV)		
	<ul style="list-style-type: none"> <li>➤ A certified copy of the technical diploma,</li> <li>➤ Certified copy of ID card</li> </ul>		
	<ul style="list-style-type: none"> <li>➤ An Attestation of presentation of original of the technical diploma</li> <li>➤ CV signed and dated by the candidate,</li> </ul>		
B.3.2	<b>01 Site foreman (Civil Engineering Senior Technician)</b>		
	Qualification of the Site foreman: (Technician certificate in Civil Engineering (BAC F4 or equivalent certificate) Professional experience of the Site foreman $\geq$ 03 years (signed CV) A certified copy of		
	<ul style="list-style-type: none"> <li>➤ A certified copy of the technical diploma,</li> <li>➤ Certified copy of ID card</li> </ul>		
	<ul style="list-style-type: none"> <li>➤ An Attestation of presentation of original of the technical diploma</li> <li>➤ CV signed and dated by the candidate,</li> </ul>		
B.3.3	<b>Other personnel</b>		
	List of support staff		
<b>B.4</b>	<b>TECHNICAL PROPOSALS</b>		
B.4.2	Organizational chart of the project (Specify names of the personnel handling the various functions)		
B.4.3	Logical sequence for the execution of the task		
B.4.5	Quality control method		
B.4.7	Environmental protection measures		
B.4.8	Security and safety at the site		
B.4.9	Duration of execution in respect with the Tender file		
<b>B.5</b>	<b>LOGISTICS (Equipment put aside for this project)</b>		
B.5.1	Proof of ownership or rental of a pick-up or other vans		
B.5.2	Proof of ownership or rental of a dump truck		

B.5.3	Proof of ownership or rental of a concrete vibrator		
B.5.4	Proof of ownership or rental of a Hand compactor		
B.5.5	Masonry Kit : Wheelbarrows, masonry clamps, masonry harmer 300g, shovel, dig axe, building level, masonry bucket , trowels, etc.		
	Carpentry Kit : carpentry clamps, saws, hammers, etc.		
<b>B.6</b>	<b>FINANCIAL CAPACITY</b>		
B.6.1	An attestation of financial capacity (solvency) of the enterprise issued by a 1st class bank located in any area in Cameroon and approved by the Ministry of Finance and respect COBAC conditions. 25%		
B.7	Attestation of site visit signed and dated by the director of the Company		
B.8	Comprehensive report of site visit signed by the company administrator and justified by photos		
B.9	Special Technical Clauses initialed in all the pages and last page signed and dated		
B.10	Special Administrative Clauses completed and initialed in all the pages and last page signed and dated		

#### ENVELOPE C- FINANCIAL FILE

No.	DESIGNATION.
C1	A submission letter, signed, dated and stamped.(see ANNEX 3)
C2	Completed and signed frame work of unit prices.
C3	Signed Bills of quantities and cost estimates indicating the total amount without taxes (HT) and with taxes (TTC)
C4	Sub details of unit prices

- The bidders will use for this purpose the documents and models envisaged in the Tender Documents, subject to the provisions of Article 19.2 of the RGAO concerning the other possible forms of bid bond.
- The various parts of the same file must be separated with colour guides in the original as in the copies, so as to facilitate its examination

#### Supply price

##### **ARTICLE 8: Currency of payment**

This National Invitation to tender is awarded on total and contractual price, inclusive of all taxes, firm and non revisable for the whole of the works and the equipment defined in the present Invitation to tender.

The corresponding amount will be calculated inclusive of all taxes and the prices will be obligatorily expressed in francs CFA.

The unit Schedule price expressed out in figures and letters and in seven (07) copies will be joined to the offer. In the event of error between the prices in figures and letters, the latter will precede and be used as a basis of calculation of the amount of the offer.

The establishment of the prices will be done on the basis of economic condition in force in the Republic of Cameroon at the handover date of the offers.

##### **ARTICLE 9:Transport and delivery**

The materials for work must be protected during transportation through packaging whether by air, railway or road according as the case may be. The conditions of storage must be of tropical type.

**ARTICLE 10: Guarantee and retention guarantee**

**10.1 Provisional guarantee**

The amount of the provisional guarantee or guarantee of tender is fixed at 1 000 000 FCFA (one million FCFA) The time of validity of this guarantee is sixty (60) days as from the date of depositing of the offers.

**10.2 Final Bond**

The final Bond is fixed at two percent (2%) of the initial amount of the services envisaged in the country.

It could be replaced by a guarantee personal and interdependent of a banking house approved by the Ministry of Finance following COBAC conditions.

It will have to be made up in the twenty (20) days following the notification of the signature of the contract in a bank approved by the Minister in charge of Finance.

**10.3 Guarantee Retention**

Guarantee Retention of ten percent (10%) will be operated on amount including all taxes of the contract. The corresponding sum will be paid or the released guarantee, with the final reception of work.

**ARTICLE 11: Period of validity of the offers**

The bidder will remain committed to his offer for sixty (60) days as from the handover date of the offers.

If at the end of this period, the contract were not notified to him, the bidder will be able, either to cancel his offer, or to ask for a new negotiation of the unit prices.

**ARTICLE 12: A number of copies of the offer which must be filled and sent**

The tender, as all the parts accompanying it will have to be given in seven (07) copies, including one (01) original and six (06) copies. The bidder will present his dossier inside a sealed outer jacket being marked:

**<<OPEN NATIONAL INVITATION TO TENDER N° 02/ONIT /NC/NCITB/2020 OF ..... 2020 FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRE IN MBEBAH BAMESSING IN NGOKETUNJIA DIVISION OF THE NORTH WEST REGION IN NGOKETUNJIA DIVISION OF THE NORTH WEST REGION.>>**

**TO BE OPENED ONLY DURING THE OPENING SESSION»**

**ARTICLE 13: Date and latest time of deposit of offers**

The offers will have to arrive under closed fold and seal latest ... January 2020 at 10:AM, by mail registered with acknowledgement of delivery or by deposit against receipt to the following address:

**NDOP COUNCIL  
SERVICE OF PUBLIC CONTRACTS  
TEL.: 67447413**

Beyond this time no offer will be received or accepted.

**ARTICLE 14: Opening of the tenders**

The opening of the folds will be carried out in the conference room of the Ndop council on 30<sup>th</sup> January 2020 as from 11:00 AM, by the Ndop council internal Tender Board sitting in the presence of the duly elected bidders or their representatives and having a good knowledge of the file.

**AWARD OF THE CONTRACT**

**ARTICLE 15: Award of the contract**

The Tenders Board will propose to the Contracting Authority to award the contract to the bidder who will have presented the offer with the lowest offer, essentially conforming to the regulations of the Tender File, having satisfied to **100% of all the eliminatory criteria and at least 20/25 of the essential criteria** taken into account.

The decision carrying attribution of the contract will be published by way of press release or any other means of publication of use in the Administration.

If the contract passed on the basis of technical alternative suggested by the bidder, the contracting authority reserves the right to introduce all the provisions there allowing him to guarantee itself against the real overrun costs of the alternative compared to his estimate of origin. In the absence of these last precise details, any additional charge due to an alternative will be inadmissible.

To this end, it is specified that a bidder cannot claim to be compensated, if action is not taken action on his offer.

The contracting authority reserves the right not to take action on an Invitation to tender, if it did not obtain a proposal which appears acceptable to him.

**ARTICLE 16: COMMENCEMENT OF WORK:**

Before the commencement of works the contractor must be installed on the site by the following:

- ❖ The authorizing officer.....(president)
- ❖ Control engineer.....(Secretary)
- ❖ The Divisional Delegate of MINMAP or his representative.....(obsever)
- ❖ The Divisional Delegate of MINEPAT.....(member)

**DOCUMENT No. 4: SPECIAL ADMINISTRATIVE CONDITIONS  
(SAC)**

## Table of contents

### Chapter I: General

- Article 1 - Subject of the contract
- Article 2 - Award procedure
- Article 3 - Definitions and duties (article 2 of GAC supplemented)
- Article 4 - Language, applicable law and regulations
- Article 5 - Constituent documents of the contract (article 4 of GAC)
- Article 6 - General applicable instruments
- Article 7 - Communication (GAC articles 6 and 10 supplemented)
- Article 8 - Administrative Orders (article 8 of GAC supplemented)
- Article 9 - Contracts with conditional phases (article 15 of GAC)
- Article 10 - Contractor's personnel (article 15 of GAC supplemented)

### Chapter II: Financial conditions

- Article 11 - Guarantees and bonds (articles 29 and 41 of GAC supplemented)
- Article 12 - Amount of contract (articles 18 and 19 supplemented)
- Article 13 - Place and method of payment
- Article 14 - Price variation (article 20 of GAC)
- Article 15 - Price revision formulas
- Article 16 - Price updating formulas (article 21 of GAC)
- Article 17 - Work under State supervision (article 22 of GAC supplemented)
- Article 18 - Evaluation of works (article 23 supplemented)
- Article 19 - Evaluation of supplies (article 24 of GAC) supplemented)
- Article 20 - Advances (article 28 of GAC)
- Article 21 - Payments for the works (articles 26, 27 and 30 of GAC supplemented)
- Article 22 - Interests on overdue payments (article 31 of GAC supplemented)
- Article 23 - Penalties for delay (article 32 of GAC supplemented)
- Article 24 - Payment in case of a group of enterprises (article 33 of GAC)
- Article 25 - Final detailed account (article 35 of GAC)
- Article 26 - General detailed account (article 35 of GAC)
- Article 27 - Tax and customs schedule (article 36 of GAC)
- Article 28 - Stamp duty and registration (article 37 of GAC)

### Chapter III: Execution of the works

- Article 29 - Nature of works
- Article 30 - Obligations of the Project Owner (GAC supplemented)
- Article 31 - Execution deadline of contract (article 38 of GAC)
- Article 32 - Roles and responsibilities of the contractor (article 40 of GAC)
- Article 33 - Making available documents and site (article 42 of GAC)
- Article 34 - Insurance of structures and civil responsibility (article 45 of GAC)
- Article 35 - Documents to be furnished by the contractor (article 49 supplemented)
- Article 36 - Organisation and security of sites (article 50 of GAC)
- Article 37 - Implantation of structures (article 52 of GAC)
- Article 38 - Sub-contracting (article 54 of GAC)
- Article 39 - Site laboratory and trials (article 55 of GAC)
- Article 40 - Site logbook (article 56 of GAC supplemented)
- Article 41 - Use of explosives (article 60 of GAC)

### Chapter IV: Acceptance

- Article 42 - Provisional acceptance (article 67 of GAC)
- Article 43 - Documents to be furnished after execution (article 68 of GAC)
- Article 44 - Guarantee time-limit (article 70 of GAC)
- Article 45 - Final acceptance (article 72 of GAC)

### Chapter V: Miscellaneous provisions

- Article 45 - Termination of the contract (article 74 of GAC)
- Article 46 - Force majeure (article 75 of GAC)
- Article 47 - Differences and disputes (article 79 of GAC)
- Article 48 - Drafting and dissemination of this contract
- Article 49 and last: Entry into force of the contract

## Chapter I: General

### Article 1: Subject of contract

The subject of this contract shall be the Construction of an integrated health centre in MBEBAH in Ndop council Area in Ngoketunjia Division in the North West Region.

### Article 2: Contract award procedure

This contract shall be awarded by Open National Invitation To Tender N°02/ NC/NCITB/2020 OF 8<sup>th</sup> January, 2020

### Article 3: Definitions and duties (article 2 of GAC supplemented)

#### 3.1 General definitions (cf. Code)

- The Contracting Authority shall be the **Lord mayor of Ndop Council**  
He awards the contract, ensures the preservation of originals of said contract documents and the transmission of copies to Ministry in charge of Public Contracts and to the body in charge of regulation.
- The Contract Engineer shall be the **Divisional Delegate of Public Works for Ngoketunjia** hereinafter referred to as the Engineer and shall sign the "Attachment"
- The Project Owner is the **Lord mayor of Ndop Council**. He represents the beneficiary administration of the works.  
He ensures respect of the administrative, technical and financial conditions and contractual deadlines.
- The Project Manager shall be the **District Medical officer**  
He ensures the interest of the project owner at the definition, preparation, execution and acceptance stages
- The **control brigade of MINMAP** shall carry out regular unannounced control visits to the site to ensure the respect of this jobbing order.
- The contractor shall be [to be specified].

#### 3.2 Security

This contract may be used as security subject to any form of transfer of the debt.  
In this case:

- The authority in charge of ordering payment shall be *the Lord Mayor of Ndop Council*.
- The authority in charge of the clearance of expenditures shall be *the Municipal Finance controller Ndop council*.
- The body or official in charge of payment shall be *the Municipal treasurer Ndop council treasury*.
- The official competent to furnish information within the context of execution of this contract shall be *the Lord mayor of Ndop Council*.

#### 3.3 Duties of the Control Mission, Project Manager

3.3.1 Missions [to be completed, where need be]

3.3.2 Means put at the disposal of the Control Mission [to be completed where need be].

### Article 4: Language, applicable law and regulation

1.2 The language to be used shall be *English and/or French*.

1.3 The contractor shall be bound to observe the law, regulations and ordinances in force in Cameroon both within his own organization and in the execution of the contract.

If the laws and regulations in force at the date of signature of this contract are amended after the signature of the contract, the possible direct resulting costs shall be taken into account without gain or loss for either party.

**Article 5: Constituent documents of the contract (Article 4 of GAC)**

The constituent contractual documents of this contract are in order of priority: (to be adapted to the nature of the works).

- 1) The tender or commitment letter;
- 2) The bidder's tender and its annexes in all provisions not contrary to the Special Administrative Conditions (GAC) and the Special Technical Conditions (STC) hereunder;
- 3) The Special Administrative Conditions (SAC);
- 4) The Special Technical Conditions (STC);
- 5) The particular elements necessary for the determination of the contract price, such as, in order of priority: the unit price schedule, the statement of all-in prices, detailed estimates, the breakdown of all-in prices and the sub-details of unit prices;
- 6) Plans, calculation notes, trial documents, geotechnical documents [insert and indicate, where need be, names and references];
- 7) The General Administrative Conditions applicable on public works contracts that went into effect by Order No. 033/CAB/PM of 13 February 2007;
- 8) The General Technical Condition(s) applicable on the services forming the subject of the contract [insert and indicate, where need be, names and references].

**Article 6: General instruments in force**

This contract shall be governed by the following general instruments [to be adapted according to the case]:

1. The Mining Code;
2. Instruments governing the various professional bodies;
3. Decree No. 2001/048 of 23 February 2001 relating to the setting up, organization and functioning of the Public Contracts Regulatory Agency
4. Decree No. 2003/651/PM of 16 April 2003 to lay down the procedure for implementing the tax and customs system applicable to public contracts;
5. Decree No. 2018/366 of 20 June 2018 to institute the Public Contracts Code;
6. Decree No. 2012/075 of 8 March 2012 to organise the Ministry in charge of Public Contracts;
7. Circular No. 001/CAB/PR of 19 June 2012 relating to the award and control of execution of Public Contracts;
8. Letter No. 00908/MINTP/DR of 1997 to publish guidelines for the consideration of environmental impact of road maintenance;
9. Circular No. 00008349/C/MINFI of 30<sup>th</sup> December 2019 on the instructions relating to the execution of the finance laws, monitoring and control of the execution of the budget of the state, and other public entities for the 2020 financial year.
10. Unified Technical Documents (DTU) for building works;
11. Applicable standards;
12. Other instruments specific to the domain concerned with the contract.

**Article 7: Communication (Articles 6 and 10 supplemented)**

1.1 All communications within the framework of this contract shall be written and notifications sent to the following address:

- a) In the case where the contractor is the addressee: Sir/Madam.....
  - b) Beyond the time-limit of 15 days fixed in article 6(1) of the GAC to make his domicile known to the Project Owner and Contract Manager, correspondences shall be validly addressed to the [to the specified] council, chief town of the region in which the work was done;
  - c) In the case where the Project Owner is the addressee: Sir/Madam.....
- Contract Manager, Contract Engineer, Project Manager and where need be, within the same deadline:
- In the case where the Contracting Authority is:

Sir/Madam [to be specified] with a copy addressed within the same deadline to the Project Owner, Contract Manager, Contract Engineer and Project Manager, where applicable

- 1.2 The contractor shall address all written notifications or correspondences to the Project Manger with a copy to the Contract Manager.

#### **Article 8: Administrative Orders (Article 8 of GAC)**

- 8.1 The Administrative Order to start execution of works shall be signed and notified to the contractor by the **Delegated Contracting Authority** with a copy to **MINMAP**, the Contract Manager, Contract Engineer, the Paying Body and the Project Manager, where applicable.
- 8.2 Upon proposal by the **Project Owner** and based on the minutes of a site meeting jointly signed by, **Project Owner and Project Engineer**, Administrative Orders with an incidence on the objective, the amount and execution deadline shall be signed by **Delegated Contracting Authority** and notified by the **Project Engineer** to the Contractor with a copy to the **MINMAP**, the **Project Manager** and the Paying Body. The prior endorsement of the Paying Body shall possibly be required before the signature of those that have an incidence on the amount.
- 8.3 Administrative Orders of a technical nature linked to the normal progress of the work and without financial incidence shall be signed directly by the **Delegated Contracting Authority/ Project owner** based on the report of a joint site visit done by **Project Owner and project Engineer** and notified to the Contractor by the **Contract Engineer** or **Project Manager** (where applicable) with a copy to **MINMAP**
- 8.4 Administrative Orders serving as warnings shall be signed by the **Delegated Contracting Authority /Project Owner** and notified to the contractor by the **Contract Engineer** with a copy to **MINMAP** and **Project Manager**.
- 8.5 Administrative Orders for suspension or resumption of work as a result of the weather or any other case of force majeure shall be signed by the **Delegated Contracting Authority** and notified by his services to the contractor with a copy to the **MINMAP, Contract Engineer and Project Manager**.
- 8.6 Administrative Orders prescribing works necessary to remedy disorders which could appear on structures during the guarantee period and not related to normal usage shall be signed by the **Project owner** upon the proposal of the **Contract Engineer** and notified to the contractor by the **Contract Engineer** and a copy sent to **MINMAP**
- 8.7 The contractor has a time-limit of **fifteen (15) days** to issue reservations on any Administrative Order received. Having reservations shall not free the enterprise of executing the Administrative Orders received.

#### **Article 9: Contracts with conditional phases (Article 9 of GAC)**

- 9.1 [Specify if the contract has one or several phases]
- At the end of a phase, the Project Owner shall carry out the acceptance of the works and issue an attestation of proper execution to the contractor. This attestation shall condition the start of the following conditional phase(s).
- 9.2 The time-limit granted for notification of the Administrative Order to start execution of a conditional phase shall be five (5) days.

#### **Article 10: Contractor's equipment and personnel (Article 15 of GAC supplemented)**

- 10.1 Any modification, even partial, made to the technical bid shall only occur after the written approval of the Contract Manager. In case of modification, the contractor shall have himself replaced by a member of staff of equal competence (qualifications and experiences).

10.2 In any case, the list(s) of supervisory staff to be used shall be subject to the approval of the Project Owner in the days following notification of the Administrative Order to start execution. The Project Manager has 5 (five) days to notify his opinion in writing with a copy sent to the Contract Manager. Beyond this time-limit, the staff list shall be considered as approved.

10.3 Any unilateral modification on the supervisory staff made in the technical bid prior to and during the works shall be a reason for termination of the contract as mentioned in article 45 below or the application of penalties [to be specified where need be].

## Chapter II: Financial conditions

### Article 11: Guarantees and bonds (Articles 29 and 41 of GAC)

#### 11.1 Final bond

The final bond shall be set at 2% of the amount of the contract, inclusive of all taxes.

It is constituted and transmitted to the Contract Manager within a maximum deadline of twenty (20) days of the notification of the contract.

The bond shall be returned or the guarantee released within one month following the date of provisional acceptance of the works, following a release issued by the Contracting Authority upon request by the contractor.

#### 11.2 Performance bond

The retention fund shall be set at 10 % of the amount of the contract, inclusive of all taxes.

The return or release of the retention fund or security shall be done within one month after final acceptance by release issued by the Contracting Authority upon request by the contractor.

#### 11.3 Guarantee of start-off advance

20% maximum of the amount of the contract inclusive of all taxes guaranteed at 100%) and conditions for the return of the guarantee

### Article 12: Amount of the contract (Articles 18 and 19 of GAC supplemented)

The amount of this contract as indicated by the attached [detail or estimates] is \_\_\_\_\_ (in figures) \_\_\_\_\_ (in letters) CFA francs Inclusive of All Taxes; that is:

- Amount exclusive of VAT: \_\_\_\_\_ (\_\_\_\_\_) CFA F
- Amount of VAT: \_\_\_\_\_ (\_\_\_\_\_) CFA F.
- Amount of TSR and/or \_\_\_\_\_ CFA F
- Net to be paid = EVAT-TSR and/or AIR

### Article 13: Place and method of payment

The Project Owner shall release the sums due in the following manner:

- a. For payments in CFA francs (amount in figures and letters exclusive of taxes) by credit to account No. \_\_\_\_\_ opened in the name of the contractor in the \_\_\_\_\_ bank.
- b. For payments in foreign currencies (amount in figures and letters exclusive of taxes) by credit to account No. \_\_\_\_\_ opened in the name of the contractor in \_\_\_\_\_ bank.

### Article 14: Price variation (Article 20 of GAC)

12.1 Prices shall be firm.

- a. Payments on account made to the contractor as advances shall not be revisable.
- b. Revision shall be "frozen" upon expiry of the contractual time-limit, except in the case of price reductions.

12.2 Price updating modalities (not applicable)

**Article 15: Price revision formulae (article 21 of GAC)**  
(not applicable)

**Article 16: Price updating formulae (article 21 of the GAC)**  
(not applicable)

**Article 17: Works under State supervision (Article 22 of GAC supplemented)**

17.1 The percentage of works under State supervision shall be [must not exceed 2 %] of the amount of the contract and its additional clauses, where applicable.

17.2 In the case where the contractor were invited to execute works under State supervision, the submitted and duly justified expenditures shall be reimbursed to him under the following conditions:

- The quantities considered shall be the hours used or the quantities of building materials and materials used that was the subject of joint job cost sheets;

- The remunerations and salaries effectively paid to local labour shall be increased by forty percent (40 %) to take account of social benefits;

- The hours put in by the heavy equipment shall be counted at the rate featuring in the sub-detail of prices;

- Building materials and materials shall be reimbursed at cost price duly justified at the place of use, marked up by ten percent for loss, stocking and handling;

- The amount for services thus calculated, including the hours put by heavy equipment shall be marked up by 25 % to take into account the overheads, profits and the contractor's unforeseen.

**Article 18: Evaluation of works (article 23 of the GAC)**

This contract is at [unit price, all-in price or unit and all-in price].

**Article 19: Evaluation of supplies (article 24 of the GAC supplemented)**

19.1 [indicate, where applicable, the modalities for payment of supplies].

19.2 No security shall be requested for payments on account on supplies.

**Article 20: Advances (article 28 of the GAC)**

20.1 The Contracting Authority may grant a start-off advance equal to 20% of the amount of the contract.

20.2 This advance whose value cannot exceed twenty (20) percent of the initial amount inclusive of all taxes shall be guaranteed at one hundred (100) percent by a banking establishment governed by Cameroon law or a first-rate financial institution in accordance with the instruments in force and reimbursed by deduction of the payments on accounts to be paid to the contractor during the execution of the contract according to the modalities laid down in the Special Administrative Conditions.

20.3 The total amount of the advance must be reimbursed not later than when the value in basic price of the works reaches eighty (80) percent of the amount of the contract.

20.4 As the reimbursement advances, the Project Owner shall issue the release of the corresponding part of the guarantee upon the express request by the contractor.

20.5 The possibility of granting start-off advance or advance for supplies must be expressly stipulated in the Tender File.

#### **Article 21: Payment for works (articles 26, 27 and 30 of the GAC supplemented)**

##### **21.1 Establishment of works executed**

Before the 30<sup>th</sup> of each month, the contractor and the Project Manager shall jointly establish a job cost sheet which summarises and fixes the quantities executed and established for each item on the schedule during the month and capable of giving entitlement to payment.

##### **21.2 Monthly detailed account**

No later than the fifth (5<sup>th</sup>) of the month following the month of the services, the contractor shall hand over to the Project Manager two draft provisional monthly detailed accounts in seven copies (one detailed account exclusive of VAT and the other inclusive of taxes), according to the agreed model and establishing the total amount of the sums to which he may lay claim as a result of the execution of the contract since the start of the contract.

Only the detailed account exclusive of VAT shall be paid to the contractor. The detailed account of the amount of the taxes shall be the subject of an entry into the budgets of the Ministry in charge of Finance

Only the amount exclusive of VAT shall be paid to the contractor as follows:

- [100-2.2 and/or - (7.5 or 15%)] paid directly into the account of the contractor;
- 2.2 % paid to the public treasury as AIR due by the contractor.
- 7.5% or 15% paid into the public treasury as TSR due by the contractor.

The Project Manager has a time-limit of seven (7) days to forward to the Contract Manager the detailed accounts he has approved.

The Contract Engineer has a maximum time-limit of twenty-one (21) days to forward the detailed accounts he approved such that they are in his possession not later than the twelfth of the month.

The Contract Manager has a deadline of fourteen (14) days maximum to sign the detailed accounts.

Payments shall be done by \_\_\_\_\_ within a maximum deadline of \_\_\_\_\_ calendar days from the date of submission of the approved detailed accounts.

##### **21.3 Detailed account of start-off account (if applicable).**

#### **Article 22: Interest on overdue payments (Article 31 of the GAC)**

Possible interests on overdue payments are paid by statement of sums due in accordance with article 88 of Decree No. 2004/275 of 24 September 2004 to institute the Public Contracts Code.

#### **Article 23: Penalties (Article 32 of the GAC supplemented)**

##### **A. Penalties for delay**

23.1 The amount set for penalties for delays shall be set as follows:

- a) One two thousandth (1/2000<sup>th</sup>) of the initial contract amount all taxes inclusive per calendar day of delay from the first to the 30<sup>th</sup> day beyond the contractual time-limit;
- b) One onethousandth (1/1000<sup>th</sup>) of the initial amount of the contract inclusive of all taxes per calendar day beyond the 30<sup>th</sup> day.

23.2 The cumulated amounts of penalties for delay shall be limited to ten percent (10 %) of the initial contract inclusive of all taxes.

##### **B. Specific penalties [amount to be indicated]**

23.3 Independently of penalties for overrun of contractual time-limit, the contractor shall be liable for the following special penalties for the non-observation of the provisions of the contract, especially:

- Late submission of final bond;
- Late submission of insurances;
- Late submission of the draft execution schedule if the lateness is caused by the contractor.

**Article 24: Payment in case of a group of enterprises (article 33 of the GAC)**

Not applicable

**Article 25: Final detailed account (article 34 of the GAC)**

25.1 After completion of the works and within a maximum time-limit of fourteen (14) days after the date of Provisional acceptance, the contractor shall establish, based on joint reports, the draft final detailed account of works executed to the contract Engineer. This final detailed account of works executed summarises the total sums to which the contractor may be entitled as a result of the execution of the whole Jobbing Order.

25.1 *The Contract Manager has up to thirty (30) days to notify the corrected and approved draft to the Project Manager.*

25.2 *The contractor has up to thirty (30) days to return the signed final detailed account.*

**Article 26: General and final detailed account (article 35 of the GAC)**

26.1 The Contract Manager or the Project Manager has up to thirty (30) days to establish the general detailed account and forward to the contractor after final acceptance.

At the end of the guarantee period which results in the final acceptance of the works, the Contract Manager draws up the general and final detailed accounts of the contract which he has had signed jointly by the contractor and the Contracting Authority. This detailed account includes:

- the final detailed account,
- the balance
- the summary of monthly payments on account.

The signing of the general and final detailed account without reservation by the contractor definitely binds the two parties, puts an end to the contract, except with regard to interest on overdue payments.

26.2 The contractor has up to thirty (30) days to return the signed final detailed account.

**Article 27: Tax and customs regulations (article 36 of the GAC)**

Decree No. 2003/651/PM of 16 April 2003 lays down the terms and conditions for implementing the tax regulations and customs procedures applicable to public contracts. The taxes applicable to this contract include notably:

- Taxes and dues relating to industrial and commercial profits, including the IAR which is a deduction on company taxes;
- Registration dues in accordance with the Tax Code;
- Dues and taxes attached to the execution of services provided for in the contract;
  - o Duties and taxes of entry into Cameroonian territory (customs duties, VAT, computer tax);
  - o Council dues and taxes;

- Dues and taxes relating to the extraction of building materials and water.

These elements must be included in the costs which the undertaking imputes on its running costs and constitute one of the elements of the sub-details of prices exclusive of taxes.

All taxes inclusive prices means VAT included.

#### **Article 28: Stamp duty and registration of contracts (article 37 of GAC)**

Seven (7) original copies of the contract shall be stamped by and at the cost of the contractor; in accordance with the applicable regulations.

### **Chapter III: Execution of works**

#### **Article 29: Nature of the works (article 46 of GAC)**

The works shall include especially: (position or volume of works)  
(To be specified cf. Special/Technical Conditions)

#### **Article 30: Role and responsibilities of the Project Owner (GAC supplemented)**

30.1 The Project Owner shall be bound to furnish the contractor with information necessary for the execution of his mission and to guarantee, at the cost of the contractor, access to sites of projects.

30.2 The Project Owner shall ensure the contractor of protection against threats, insults, violence, assault and battery, slander or defamation of which he could be victim by reason of or during the exercise of his mission.

#### **Article 31: Execution time-limit of the contract (article 38 of the GAC)**

31.1 The time-limit for the execution of the works forming the subject of this contract shall be **Five (5) Months**.

31.2 This time-limit shall run from the date of notification of the Administrative Order to commence execution of the works.

#### **Article 32: Role and responsibilities of the contractor (article 40 of the CAG)**

The detailed and general plan of progress of the works shall be communicated to the Project owner in five (05) copies at the beginning of each.

#### **Article 33: Provision of documents and site (article 42 of the GAC)**

A reproducible copy of the plans featuring in the Tender File shall be submitted by the *Contract engineer*.

The Project Owner shall make available the site and access ways to the contractor at the appropriate time as the works progress.

#### **Article 34: Insurance of structures and civil liabilities (article 45 of GAC)**

The following insurance policies are required within the scope of this jobbing order in the minimum amounts indicated hereafter within fifteen (15) days of the notification of the contract (*to be adapted*):

- Liability insurance, business manager;
- Comprehensive insurance of the site;
- Insurance covering its ten-year obligation, where applicable.

#### **Article 35: Documents to be furnished by the contractor (Article 49 of the GAC supplemented)**

35.1 Programme of works, Quality Assurance Plan and others

a) Within a minimum deadline of [fifteen (15) days] from the date of notification of the Administrative Order to commence execution, the contractor shall submit in [six (6)] copies for the approval of [Project owner after the endorsement of the Contract Engineer] the execution programme of the works, his supply calendar, his draft Quality Assurance Plan and the Environment Management Plan, where applicable.

This programme shall be exclusively presented according to the furnished models.

Two (2) copies of these documents will be returned to him within a deadline of fifteen (15) days from the date of reception with:

- Either the indication "GOOD FOR EXECUTION";
- Or the indication of their rejection including the reasons for the said rejection.

The contractor has eight (8) days to present a new draft. The Contract Manager or the Project Manager then has a deadline of five (5) days to give his approval or possibly make comments. Delay in approving the draft execution schedule shall stay the execution deadline.

The approval given by the Project owner does not in any way release the contractor of his responsibilities. Meanwhile, works executed before the approval of the programme shall neither be ascertained nor paid for. The updated and approved schedule will become the contractual schedule.

The contractor shall constantly update on site, a schedule that will take account of real progress of the site. Significant modifications may only be made on the contractual programme upon receiving the approval of the Project owner. After approval of the execution schedule by the project owner, the latter shall transmit it within five (5) days to the Contracting Authority without staying its execution. However, if important modifications alter the objective of the contract or the nature of the works, the Contracting Authority shall return the execution schedule accompanied by reservations to be lifted within fifteen (15) days of the date of reception.

b) The Environment Management Plan should bring out notably the choice technical conditions of the site and basic life, conditions of the backfill of the extraction sites and conditions for reinstating the works and installation sites.

c) The contractor shall indicate in this schedule the equipment and methods which he intends to use as well as the personnel he intends to employ.

d) The approval granted by the Project owner shall in no way diminish the responsibility of the contractor with regard to the harmful consequences which their implementation may cause both towards third parties and the respect of clauses of the contract

### 35.2 Execution draft

a) The execution plan documents (calculations and drawings) necessary for the realisation of all the parts of the structure must be submitted for the endorsement of the [Contract Manager or Project Manager] at most fifteen (15) days prior to the date provided for the commencement of execution of the corresponding part of the structure.

b) The [Contract Engineer or Project owner] has a deadline of [five (05) days] to examine and make known his observations. The contractor then has a deadline of [04] four days] to present a new file including the said observations.

35.3. In case of the non observance of the approval deadlines of the above documents by the Administration, these documents shall be deemed to have been approved.

### Article 36: Organisation and safety of sites (article 50 of the GAC)

36.1. Signboards at the beginning and end of each section must be placed within a maximum deadline of fifteen days after the notification of the Administrative Order to commence work.

36.2. The services to inform in case of interruption of traffic or along the deviated itinerary: [To be specified in accordance with article 50(2) of the GAC].

36.3. Indicate the special measures demanded of the contractor, other than those provided for in the GAC, for rules of hygiene and safety and for circulation around or in the site.

**Article 37: Implantation of structures**

The Project Manager shall notify within [five] days following the date of notification of the Administrative Order to commence work, the basic points and levels of the project.

**Article 38: Sub-contracting (article 54 of the GAC)**

There shall be no sub contracting

**Article 39: Site laboratory and trials (article 55 of GAC)**

39.1 Indicate if necessary the modalities for carrying out the trials and geotechnical studies provided for in the Special Technical Conditions.

39.2 The Contract Engineer has a deadline of three days to approve the contractor's personnel and laboratory as soon as the request is made.

**Article 40: Site logbook (article 56 of the GAC supplemented)**

40.1 The Site logbook must be systematically jointly signed by MINMAP and Engineer, where need be and the contractor's representative each day.

40.2 It is a joint document in a single copy. Its pages must be numbered and initialed. No page should be removed. The erased or cancelled parts must be mentioned on the margin for validation.

40.3 Absence of site log book that is duly signed shall be sanctioned with a penalty of 3,000 (three thousand) F CFA per day

**NB the Site logbook must be such that two carbon copies of each page are left behind.**

**Article 41: Use of explosives (article 60 of the GAC)**

Explosives shall not be used during the execution of this job

**Chapter IV: Acceptance**

**Article 42: PROVISIONAL ACCEPTANCE**

**42.1 PRE- ACCEPTANCE OPERATIONS**

Before the acceptance of the works the contractor shall ask in writing to the control Engineer, to organize a technical visit for pre-acceptance. This visit shall include the following operations.

- >Qualitative and quantitative evaluations of the different works that have been executed.
- >Findings and statement of the unexecuted task envisaged in the present jobbing order.
- >Findings relative to the completion of the work
- >Findings on the quantity of works that have been effectively realized

These operations shall be subject to a site report drawn up on the field, signed by the following.

- Control Engineer,
- Contractor.

During this pre-reception, the engineer shall eventually specify the reserves to be lifted and the corresponding works to be effected before the reception. The Engineer shall fix the reception date in collaboration with the chief of service for the contract.

**42.2 Acceptance**

The acceptance commission shall comprise:

- 1- The Authorizing Officer ..... (Chairman)
- 2- The Control Engineer..... (Secretary)
- 3- The DD MINMAP..... (observer)
- 4- The Contractor or his Representative..... (Member)
- 5- The project manager.....( Member)

The commission shall examine the report of the pre-acceptance and shall proceed to the acceptance. An acceptance report (proces - verbal) of the works shall be prepared by the Engineer and signed by all the commission members.

**Article 43: GUARANTEE PERIOD.**

The guarantee period is one (01) year from the date of the provisional reception for the section of new civil Engineering works.

**Article 44: Article 45: Final acceptance (article 72 of the GAC)**

44.1 Final acceptance shall take place within a maximum deadline of [fifteen (15) days] from the date of expiry of the guarantee.

The procedure for final acceptance shall be the same as for provisional acceptance

**Chapter V: Sundry provisions**

**Article 45: Termination of the contract (article 74 of the GAC)**

The contract may be terminated as provided for in Part III Paragraph IV of Decree No. 2004/275 of 24 September 2004 and equally under the conditions laid down in articles 74, 75 and 76 of the GAC especially in one of the following cases:

- Delay of more than fifteen (15) calendar days in the execution of an Administrative Order or unjustified stoppage of more than seven (7) calendar days;
- Delay in work resulting in penalties of more than 10 % of the amount of the works;
- Refusal to repeat poorly executed works;
- Default by the contractor;
- Persistent non payment for services.

**Article 46: Case of force majeure (article 75 of the GAC)**

If the contractor were to raise the issue of force majeure, the thresholds below which claims shall not be admitted are:

- Rainfall: 200 millimetres in 24 hours;
- Wind: 40 metres per second;
- Flood: decennial flood frequency.

**Article 47: Disagreements and disputes (article 79 of the GAC)**

Disagreements and disputes resulting from the execution of this contract may be settled amicably.

Where no amicable solution can be found for a disagreement, it is brought before the competent Cameroonian jurisdiction, subject to the following provisions: *[to be filled, where need be]*.

**Article 48: Production and dissemination of this contract**

Seven copies of this contract shall be produced at the cost of the contractor and furnished to the Contract Manager.

**Article 49 and last: Entry into force of the contract**

This contract shall be final only upon its signature by the Contracting Authority. It shall enter into force as soon as it is notified to the contractor by the Contracting Authority.

**Document No. 5:  
Special Technical Conditions (STC)**

# TECHNICAL SPECIFICATIONS

- I - GENERALITIES
- II- PREPARATORY WORKS-IMPLANTATION
- III- FOUNDATION
- IV - ELEVATION WORKS
- V - ROOF TRUSS AND THE COVERING
- VI - JOINERY AND METAL WORKS
- VII - PLUMBING-SANITARY
- VIII- ELECTRICAL INSTALLATION
- IX - RENDERING (PLASTERING) AND COATING
- X - PAINTING
- XI - OUTSIDE AMENITIES AND LAYOUT PLANNING
- XII - PROTECTION OF THE ENVIRONMENT
- XIII - ORIGIN, QUALITY AND PREPARATION OF MATERIALS

## **1.- GENERALITIES**

This present special technical specifications concern the **CONSTRUCTION OF AN INTEGRATED HEALTH CENTRE IN MBEBAH NGOKETUNJIA DIVISION OF THE NORTH WEST REGION**. It is the duty of the contractor to realise the structure as per the execution plans that shall be approved by the control Engineer provided by the project owner.

Through the Control Engineer, the contractor shall furnish the owner of the project within the shortest possible time with an installation plan showing clearly how he intends to run the work site. A fence in local materials shall enclose the whole work site to avoid trespassing

The contractor shall be responsible for the protection of the structures before final reception. He shall be equally responsible for all tools and materials present at the work site. He shall seek an insurance policy to cover theft and fire incidence.

The contractor shall take all preventive measures against accidents. The owner of the project reserves the right to intervene in case of any emergency without necessary interfering with the responsibilities of the contractor.

The contractor shall verify all dimensions on the plans. For execution, no dimension shall be measured with a scale rule from the plans. The contractor shall check insitu the possibility of translating the dimensions on plans to the structure before work begins. He shall refer to the Control Engineer in case of any doubt. He shall not on his/her own modify anything on the structure and shall inform the Control Engineer of any changes that he considers necessary.

All modifications accepted by the contractor shall be accomplished in a specified duration and at his/her cost without modification of the contract amount. The owner of the project shall have the right to the final choice in case of any modification.

## **2 - PREPARATORY WORKS – SETTING OUT**

These works concern the demolition of any existing structure on the site and the evacuation of the rubbles to the public discharge, the clearing and levelling of the site where necessary.

The setting out will be in respect to the technical plans. The setting out profile boards will be at least 1, 20 m from the outside axes; this is to facilitate trenching and other earthworks, and good circulation. The commencement of excavation will be accepted by the control engineer without checking the conformity of the setting.

The minimal depth of the excavation trenches shall be of 80cm, and depending on the soil bearing capacity. Where there is black vegetable soil or soil with low bearing capacity at the bottom of the trench, the contractor shall continue excavation up to a depth as will be approved by the control engineer. The excavations will be done manually and no concrete or mortar shall be laid on the bottom of the trench without the acceptance of the trench bottom of excavation by the control engineer.

The descriptive notice completes or confirms the indications on the execution plans. In the case of contradictions between the plans and the descriptive notice, the project team shall be contacted for examination, elaboration and conclusion.

These technical specifications have as objective the definition of the consistence of works to be executed in accordance with the plans and according to technical norms for the construction of classroom buildings.

## **3 - FOUNDATION**

Any blinding concrete will be of thickness 5 cm at 150 kg/m<sup>3</sup> of firm consistence and will be laid on the bottom of the excavations where necessary. On it will be laid the footings of the ground half pillars until the level of the finished foundation. The foundation peripheral walls will be of masonry

stones laid on cement mortar and finished with a DPC layer or ground beams of 20 x 20cm in reinforced concrete at a dosage of 300 kg/m<sup>3</sup>.

The foundation will be filled with earth of good quality in successive compacted layers of 20 cm where the fill depth exceeds 30cm. A mass concrete of thickness 8 cm will be laid to cover the whole foundation area at a dosage of 300 kg/m<sup>3</sup>.

#### **4 – ELEVATION WORKS**

The elevation walls will be in agglomerated hollow blocks of 15 x 20 x 40cm with a good crushing resistance. The mixing for block moulding should give at most 32 blocks per bag of cement. They should be kept dry for at least 21 days before laying on the elevation walls. The reinforced concrete pillars of section 15 x 15 and 15 x 30 at 350 kg/m<sup>3</sup> will be cast as one raises the agglomerated hollow blocks walls and this is to permit a good adhesion. The characteristic strength of concrete at 28 days should not be less than 16Mpa. The maximal spacing of the pillars is to be 5,00 m of span or as on plans. The lintels 15 x 20 in reinforced concrete at 350 kg/m<sup>3</sup> will be levelled to + 2,20 m above the level of the finished foundation.

The average height under the ceiling is 3,00m.

A chaming beam of 15 x 20 cm in reinforced concrete at 350 kg/m<sup>3</sup> will be laid above the finished level of the agglomerated hollow blocks walls with fixing plates so as to receive the wooden roof truss.

#### **7: – ROOF TRUSS AND THE COVERING:**

-*Trusses* of hardwood agreed by the control Engineer shall compose of single frame rafters of 5cmx15cm and spaced at 1.50m interval. These rafters will be solidly attached to the wall plate with the help of standby beam iron rods also spaced at 1.50m spacing;

ie: eucalyptus, mahogany, iroko etc,

-*Purlins*- shall consist of 5x8 cm timbers. All structural timber shall be treated with carbonyl. The timber for the roof work will be of good quality, with the straight grain and free of any defect

-*Roofing sheets*: shall be in high rib (Tôle BAC) aluminium sheets of type 5/10mm. The sheets shall be fixed onto the purlins using screw nails equipped with aluminium gaskets and bituminous rubbers caps.

-*Facial board* shall be 40cm wide and of high rib aluminium sheets (tôle bac) of 0.35mm thickness.

-*Ceiling*- will be made of 4mm thick (red plywood on both sides). Fastened noggins of 4cm thick or 5x5 and treated with carbonyl. The spaces for ceiling joist panel will be 60x120cm in size. Eaves shall be equipped with wire mesh ventilation holes and two trap doors will be provided in each of the classrooms. for external ceiling TOLE LISSE shall be used at the Eaves

#### **6 – JOINERY AND METAL WORKS**

**Doors Frame** - All doors will be made of forged iron double metal fitted on metallic frame anchored in the wall with angle 35mm metal of Size; 2.20m x 0.97m. Angle bar 35mm for metallic doors and for window frames and shutters. Moreover, all windows shall have iron or solid metal protectors inside.

#### **7 - PLUMBING - SANITARY**

If there be any sanitary fitting works, it will be executed according to plumbing norms. The dimensions and constructive dispositions will be made by the engineer.

#### **8 – ELECTRICAL INSTALLATION**

The interior facilities (sheaths VGV cables, TH etc...) will be executed according to the norms and the rules concerning electrical installations at the time of the mass concrete or as the agglomerated hollow blocks walls are being raised. Any necessary branching from ENEO network should respect the

regulation in force. Accessories and luminous elements (sockets, switches etc...) will be of good model. The set of facilities will be joined to a general earth hold.

### **9 - RENDERING (PLASTERING) AND COATINGS**

The wall rendering (thickness at least 1,5 cm) will be of cement mortar at 400 kg/m<sup>3</sup>. There will be an under-coat layer and a finish layer floated and foamed to finish. They must be well cut horizontally and vertically using a straight edge.

The floor will be finished in cement sand screed and coated to finish with cement paste trowel to finish. Blackboards (1, 20x5, 00m) will be executed and tinted with the desired blackboard dyes. Each classroom has 02 blackboards with one having a stage.

### **10 - PAINTING**

A layer of impression of quicklime will be applied previously on all the walls as preparatory layer. The interior walls and the ceiling will be painted in pantex 800. The outside walls will be painted in pantex 1300. Colour tinted tubes will be chosen to achieve the desired colour frame needed.

### **11 - OUTSIDE AMENITIES AND LAYOUT PLANNING**

It will be created on all sides of the classroom building mass concrete peripheral gutter of 40x25cm that will facilitate drainage problems and mass concrete (300 kg/m<sup>3</sup>) between this peripheral gutter and the remaining parts to the classroom building to prevent external moisture droppings to the building at the ground level.

### **12 - PROTECTION OF THE ENVIRONMENT**

The entrepreneur will propose to the control engineer, before the beginning of works, the place of his/her yard facilities and will request his/her authorization of installation.

The site must be chosen outside of the sensitive zones, in order to limit the site clearing, the extraction of bushes, the setting out of the building and general circulation.

The site must foresee an adequate drainage of waters on the whole surface. The maintenance areas and of washing should be concreted. These maintenance areas should have a slope toward a cesspool provided for the purpose and toward the inside of the platform in order to avoid the out-flow of the polluting products toward the site and the neighbourhood.

At the end the works, the entrepreneur will do all necessary works to the restoration of the various places of the site. The entrepreneur should fold all his/her material, and equipment. He should demolish all stationary installation, as foundation, support made of concrete or metallic, etc. in order to put back the site in its nearest initial state. No equipment nor materials should be abandoned on the site, nor in the vicinity after the execution of all the works. Left-over materials are to be covered with a layer of earth, and the site has to receive an adequate drainage in order to avoid all erosion as the case may be.

### **13 - ORIGIN, QUALITY AND PREPARATION OF MATERIALS**

The fine and coarse aggregates may either be from the river or quarry crushed and must be approved by the control engineer before any use on the site. The sand (0/5) shall have very fine elements settlement of less than 4%. The gravels (5/15 or 15/25) shall be clean and well graded with very fine elements settlement of less than 2%.

The cement shall be CPA 325 class from CEMENCAM or from an approved factory.

The reinforcement steel for reinforced concrete shall be of type HA FeE400 for the main reinforcement steel rods and round-smooth RL E235 for the stirrup rings.

Any fill material for the foundation and the surroundings structures shall have no particle dimension above 50mm and with plasticity index of less than 35. Fill materials shall also be free from organic elements and shall have a good granularity grading. No black vegetable soil shall be accepted for backfilling:

Stones for masonry works shall be of basalt, gneiss or granite type, be esthetical and should be gotten from the quarry or deposits approved by the control engineer with dimension sizes of not less than 20cm.

### 1) CONCRETE:

- **Ordinary concrete** specifically lean concrete shall be 5cm thick and laid all-round the excavated foundation trenches before the stone/block work is carried out and dosed at 150kg/m<sup>3</sup>.

- **Mass concrete** shall be 8cm thick laid over the entire floors and paved area between walls and gutters at 300kg/m<sup>3</sup>.

NB: The external veranda shall be 5cm below the level of the internal floor with 2% slope.

- **Reinforced concrete** shall be specifically for pillars, beams damp proof course (DPC), lintels and ring beams and their mixture shall be in a proportion of 350kg/m<sup>3</sup>.

NB: All concrete works should be properly cured (i.e. water three times a day for seven days)

#### NOTE: Reinforcement Schedule.

No	STRUCTURE	SIZES	RODS		STIRRUP Spacings	DOSAGE	TYPE
		Nos	φ	Torsφ			
1	Ground beams 20x20	4	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-40
2	Lintel (15x20)	4	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-40
3	Veranda Pillars 15x 30	6	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-40
4	Wall Pillars 15x15	4	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-40
5	Wall plate 15x20	4	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-40

- **Sand:** Will be free from oxide, organic material of animals or plant origin. Sieving shall vary from 0.08 – 2.5mm for mortar and other resisting surfaces like concrete structure shall vary from 0.16 – 5mm. It shall be river sand and nothing else.

- **Coarse Aggregate:** shall consist of natural and homogeneous materials or crushed stones. Tiny layer of grave (dust) shall be removed by sieving, blowing or washing.

- **Water:** To be used for the mixture mortar, concrete and washing of aggregates. Shall be clean and free from impurities; meaning potable water.

- **Cement:** To be used mostly for cement mortar, all concrete mixtures shall satisfy the general conditions laid down by regulation in force. It will be type CPA325 Portland cement and shall not show any trace of uneven mixture. Storage on the building site shall be done on a dry and ventilated floor. Any stock presenting an unsatisfactory pulverulent condition will be discarded and cleared away within four (04) days.

- **Rods:** shall be mild steel reinforcement, Tor or Steel in accordance with the R/C & 3 rules. The steel shall be perfectly clean without any trace of rust, non-adhesive to paint or grease.

- **Shuttering:** hard wood, to bear without any noticeable distortion, the load and pressure of concrete, the effect of vibration and weight of workers involved in setting it up.

### MASONRY:

- **Blocks-** Load bearing wall shall be mounted in compressed cement blocks of (15x20x40) cm for load bearing walls of PC300 Kg/m<sup>3</sup> (at most 32 blocks per bag of cement). Blocks should show an appreciable degree of resistance to violent pressure.

**All blocks shall be cured for at least 28 days before being used.**

- **Plastering:** All plastering shall be applied using a trowel, float, straights edges and sponge. Cement mortar mix in a proportion of 400kg/m<sup>3</sup> will be used to plaster all previously rejoined areas on all masonry and concrete works, and then thinly floated. The final thickness of the plastering shall not be less than three (02cm) centimetres. The external walls shall receive a coat of spatadash before plastering is done on it.

-Screed: a smooth layer of ordinary cement screed 400kg/m<sup>3</sup> (1:2) finish shall be spread on the 8cm concrete floor and the screed shall be 2cm thick.

#### 18 GUTTERS:

To be excavated 40cm wide and 30cm deep at the rain drops and to be provided particularly at the frontage and the two ends of the building as the topography of the terrain is relatively flat. The walls of gutters are to be constructed in concrete and the floor will be rolled and smoothen out with ordinary cement concrete providing a slope of 2% for the flow of water for level surfaces.

Prefabricated slabs of one metre twenty (1.20m) wide each shall be provided at the main entrance of the classrooms at right angles.

Equally ramps cast insitu of one meter twenty (1.20m) wide each shall be provided at the entrance of each classroom for handicaps on wheel chairs or otherwise.

#### 15- Wood – Material

- The wood must be pure and should not have nodes, foreign bodies or fractures due to sawing.
- Type : hard
- Essence : EUCALYPTUS, SIPO, SAPPELLI, IROKO, MAHOUGHANY.
- Seasoning: Wood with a humidity rate of 14% maximum.

**Document No. 5:  
Schedule of unit prices**

**UNIT PRICE SLIP (UPS) FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRES (I.H.C) IN MBEBAH NGOKETUNJIA DIVISION OF THE NORTH WEST REGION**

N° PRIX	DESIGNATION	UNITE	P.UNITAIRE EN CHIFFRE	P.UNITAIRE EN LETTRES
<b>100</b>	<b>TRAVAUX PRELIMINAIRES - TERRASSEMENTS</b>			
101	Installation du chantier	FF		
102	Aménagement et assainissement de la plateforme	FF		
103	Notice d'impact environnemental	FF		
104	Fouilles en puits	m3		
105	Fouilles en rigoles	m3		
106	Remblai des fouilles	m3		
107	Couche de sable sous dallage	m2		
108	Film polyane	m2		
<b>200</b>	<b>FONDATION</b>			
201	Béton de propreté dosé à 150 kg/m3	m3		
202	Béton armé de semelle dosé à 250 kg/m3	m3		
203	agglos pleins de 20x20x40	m2		
204	Longrine en B.A dosé à 350 kg/m3	m3		
<b>300</b>	<b>BETON ARME EN ELEVATION</b>			
301	Dallage du sol et autour du bâtiment dosé à 300 kg/m3	m3		
302	Béton armé pour poteaux et poutres chaîné et linteaux dosé à 350 kg/m3	m3		
303	Appui de fenêtre dosé à 350 kg/m3	m3		
<b>400</b>	<b>MACONNERIE</b>			
401	Murs en agglos creux de 15x20x40	m2		
402	Murs en agglos creux de 10x20x40	m2		
403	Claustras	m2		
<b>500</b>	<b>ENDUITS, CHAPES ET DIVERS</b>			
501	Enduits sur murs extérieurs	m2		
502	Enduits sur murs intérieurs	m2		
503	Remplissage pour surélévation des placards de 10 cm	m2		
504	Chape de 4 cm	m2		
505	Paillasse en béton et divers	ml		
<b>600</b>	<b>FAUX PLAFOND</b>			
601	Plafond en contreplaqué	m2		
602	Plafond en tôle lisse	m2		
603	Couvre joint	ml		
<b>700</b>	<b>REVÊTEMENTS SCELLES</b>			
701	Grès cérame antidérapant de 30x30	m2		
702	Faïence pour pièces humides	m2		
703	Plinthe en grès cérame de 15 cm de hauteur	m2		
<b>800</b>	<b>CHARPENTE - COUVERTURE</b>			

801	Bois de charpente dur traité au xylamon	m3		
802	Planche de rive	ml		
803	Tôle de rive	ml		
804	Tôle de noue	ml		
805	Tôle faitière	ml		
806	Couverture bac alu 5/10e	m2		
807	Gouttière préfabriquée en acier	ml		
808	Descente d'eau en PVC	ml		
<b>900</b>	<b>MENUISERIE BOIS</b>			
901	Porte isoplane 0,7x2,10 : P11	U		
902	Porte isoplane 1,00x2,10 : P12	U		
903	Porte pleine 1,00x2,10 : PP1	U		
904	Fenêtre châssis NACO 10 lames 1,50 m y compris toile moustiquaire (CN)	U		
905	Fenêtre châssis NACO 7 lames 0,60 m y compris toile moustiquaire (CN)	U		
906	Placard de 0,8x3 en CP ép. 0,19 y compris étagères	U		
<b>1000</b>	<b>MENUISERIE METALLIQUE</b>			
1001	Grille antivol pour CN	m2		
<b>1100</b>	<b>PEINTURE - VITRERIE</b>			
1101	Penture sur murs extérieurs 2 couches	m2		
1102	Penture sur murs intérieurs 2 couches	m2		
1103	Peinture sur menuiseries bois	m2		
1104	Peinture sur grilles antivol de châssis CN	m2		
1105	Peinture sur plafond	m2		
1106	Vitrage pour châssis NACO	m2		
<b>1200</b>	<b>ELECTRICITE</b>			
	<b>Circuit de terre - mise à la terre</b>			
1201	Ceinture de terre	ml		
1202	Liaison équipotentielles	Ens.		
	<b>Coffrets et tableaux</b>			
1203	Coffrets et tableaux	FF		
	<b>Distribution - Alimentation - Eclairage - Prises - Equipements</b>			
1204	Interrupteurs simple allumage y compris foureautage et câblage	U		
1205	Interrupteurs va et vient y compris foureautage et câblage	U		
1206	Prises de courant 2P+T 16A y compris foureautage et câblage	U		
	<b>Lustrerie</b>			
1207	Applique sanitaire 2P+T y compris foureautage et câblage	U		
1208	Réglettes y compris foureautage et câblage	U		
1209	Hublots ronds étanches y compris foureautage et câblage	U		
<b>1300</b>	<b>FLUIDES</b>			
	<b>Plomberie sanitaire</b>			

1301	Réseau d'évacuation EU/EV	Ens.		
1302	Réseau enterré	Ens.		
	<b>Appareils sanitaires</b>			
1303	Lavabo blanc	U		
1304	Cuvette WC	U		
1305	Evier	U		
1306	Douche	U		
1307	Robinet d'eau dans la cour	U		
	<b>Assainissement</b>			
1308	Fosse septique pour 40 usagers y compris canalisations et regards de raccordement	Ens.		
1309	Puisard septique pour 40 usagers y compris canalisations et regards de raccordement	Ens.		
13010	Caniveau bétonné tout autour du bâtiment	ml		
13011	Dalettes pour caniveaux	ml		

**Document No. 7:  
Bill of quantities and estimates**

<b>BILL OF QUANTITIES FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRES (I.H.C) IN MBEBAH NGOKETUNJIA DIVISION OF THE NORTH WEST REGION</b>					
<b>N° PRIX</b>	<b>DESIGNATION</b>	<b>UNITE</b>	<b>QUANTITE</b>	<b>P.UNITAIRE</b>	<b>PRIX TOTAL</b>
<b>100</b>	<b>TRAVAUX PRELIMINAIRES - TERRASSEMENTS</b>				
101	Installation du chantier	FF	1		
102	Aménagement et assainissement de la plateforme	FF	1		
103	Notice d'impact environnemental	FF	1		
104	Fouilles en puits	m3	20,27		
105	Fouilles en rigoles	m3	111,29		
106	Remblai des fouilles	m3	241,5		
107	Couche de sable sous dallage	m2	288,24		
108	Film polyane	m2	288,24		
	<b>SOUS TOTAL - 100</b>				
<b>200</b>	<b>FONDATION</b>				
201	Béton de propreté dosé à 150 kg/m3	m3	11,12		
202	Béton armé de semelle dosé à 350 kg/m3	m3	5,02		
203	Agglos pleins de 20x20x40	m2	194,25		
204	Longrine en B.A dosé à 350 kg/m3	m3	12,78		
	<b>SOUS TOTAL - 200</b>				
<b>300</b>	<b>BETON ARME EN ELEVATION</b>				
301	Dallage au sol et autour du bâtiment dosé à 300 kg/m3	m3	34,42		
302	Béton armé pour poteaux et poutres chaînage et linteaux dosé à 350 kg/m3	m3	26,51		
303	Appui de fenêtre dosé à 350 kg/m3	m3	0,64		
	<b>SOUS TOTAL - 300</b>				
<b>400</b>	<b>MACONNERIE</b>				
401	Murs en agglos creux de 15x20x40	m2	600,75		
402	Murs en agglos creux de 10x20x40	m2	58,42		
403	Claustras	m2	51,64		
	<b>SOUS TOTAL - 400</b>				
<b>500</b>	<b>ENDUITS, CHAPES ET DIVERS</b>				
501	Enduits sur murs extérieurs	m2	374,22		
502	Enduits sur murs intérieurs	m2	904,50		
503	Remplissage pour surélévation des placards de 10 cm	m2	4,98		
504	Chape de 3 cm	m2	344,23		
505	Paillassé en béton et divers	ml	3,35		
	<b>SOUS - TOTAL - 500</b>				
<b>600</b>	<b>FAUX PLAFOND</b>				

601	Plafond en contreplaqué	m <sup>2</sup>	344,23		
602	Plafond en tôle lisse	m <sup>2</sup>	71,55		
603	Couvre - joint	ml	501,12		
<b>SOUS - TOTAL - 600</b>					
<b>700</b>	<b>REVÊTEMENTS SCELLES</b>				
701	Grès céramé antidérapant de 5x5	m <sup>2</sup>	344,23		
702	Faïence pour pièces humides	m <sup>2</sup>	105,66		
703	Plinthe en grès céramé de 15 cm de hauteur	m <sup>2</sup>	329,58		
<b>SOUS - TOTAL - 700</b>					
<b>800</b>	<b>CHARPENTE - COUVERTURE</b>				
801	Bois de charpente dur traité au xylamon	m <sup>3</sup>	6		
802	Planche de rive	ml	124,3		
803	Tôle de rive	ml	124,3		
804	Tôle de noue	ml	19,6		
805	Tôle faîtière	ml	89,3		
806	Couverture bac alu 5/10e	m <sup>2</sup>	435,35		
807	Gouttière préfabriquée en acier	ml	99,6		
808	Descente d'eau en PVC	ml	40,8		
<b>SOUS - TOTAL - 800</b>					
<b>900</b>	<b>MENUISERIE BOIS</b>				
901	Porte isoplane 0,7x2,10 : P11	U	12		
902	Porte isoplane 1,00x2,10 : P12	U	9		
903	Porte pleine 1,00x2,10 : PP1	U	4		
904	Fenêtre châssis NACO 10 lames 1,50 m y compris toile moustiquaire (CN)	U	12		
905	Fenêtre châssis NACO 7 lames 0,60 m y compris toile moustiquaire (CN)	U	12		
906	Placard de 0,8x3 en CP ép. 0,19 y compris étagères	U	3		
<b>SOUS - TOTAL - 900</b>					
<b>1000</b>	<b>MENUISERIE METALLIQUE</b>				
1001	Grille antivol pour CN	m <sup>2</sup>	35,04		
<b>SOUS - TOTAL - 1000</b>					
<b>1100</b>	<b>PEINTURE - VITRERIE</b>				
1101	Peinture sur murs extérieurs 2 couches	m <sup>2</sup>	495		
1102	Peinture sur murs intérieurs 2 couches	m <sup>2</sup>	790,84		
1103	Peinture sur menuiseries bois	m <sup>2</sup>	89,88		
1104	Peinture sur grilles antivol de châssis CN	m <sup>2</sup>	27,36		
1105	Peinture sur plafond	m <sup>2</sup>	288,24		
1106	Vitrage pour châssis NACO	m <sup>2</sup>	27,36		
<b>SOUS - TOTAL - 1100</b>					
<b>1200</b>	<b>ELECTRICITE</b>				
	Circuit de terre - mise à la terre				

1201	Ceinture de terre	ml	148,64		
1202	Liaison équipotentielle	Ens.	1		
	<b>Coffrets et tableaux</b>				
1203	Coffrets et tableaux	FF	1		
	<b>Distribution - Alimentation - Éclairage - Prises - Equipements</b>				
1204	Interrupteurs simple allumage y compris fourautage et câblage	U	35		
1205	Interrupteurs va et vient y compris fourautage et câblage	U	30		
1206	Prises de courant 2P+T 16A y compris fourautage et câblage	U	40		
	<b>Lustrerie</b>				
1207	Applique sanitaire 2P+T y compris fourautage et câblage	U	3		
1208	Réglettes y compris fourautage et câblage	U	65		
1209	Hublots ronds étanches y compris fourautage et câblage	U	11		
	<b>SOUS - TOTAL - 1200</b>				
<b>1300</b>	<b>FLUIDES</b>				
	<b>Plomberie sanitaire</b>				
1301	Réseau d'évacuation EU/EV	Ens.	1		
1302	Réseau enterré	Ens.	1		
	<b>Appareils sanitaires</b>				
1303	Lavabo blanc	U	5		
1304	Cuvette WC	U	5		
1305	Évier	U	3		
1306	Douche	U	3		
1307	Buanderie	U	1		
1308	Porte Serviette	U	3		
1309	Porte savon blanc encastré	U	4		
1310	Porte papier hygiénique	U	4		
1311	Paillasse avec évier et bloc placard sous paillasse en contre plaque à vernir Y compris toute surjections	M2	3,18		
1312	Siphon de sol	U	3		
1313	Miroir de 60cmx60cm (fil sagé femme)	U	1		
1314	Robinet d'eau dans la cour	U	2		
	<b>Assainissement</b>				
1315	Fosse septique pour 40 usagers y compris canalisations et regards de raccordement	Ens.	1		
1316	Puisard septique pour 40 usagers y compris canalisations et regards de raccordement	Ens.	2		
1317	Caniveau bétonné tout autour du	ml	125		

	bâtiment			
1318	Dalettes pour caniveaux	ml	9,4	
	<b>SOUS - TOTAL - 1300</b>			
	<b>RECAPITULATIF :</b>			
100	TRAVAUX PRELIMINAIRES			
200	FONDATION			
300	BETON ARME EN ELEVATION			
400	MACONNERIE			
500	ENDUITS, CHAPEE ET DIVERS			
600	FAUX PLAFONDS			
700	REVÊTEMENTS SCELLES			
800	CHARPENTE - COUVERTURE			
900	MENUISERIE BOIS			
1000	MENUISERIE METALLIQUE			
1100	PEINTURE - VITRERIE			
1200	ELECTRICITE			
1300	FLUIDES			
	<b>TOTAL HTVA</b>			
	<b>T.V.A (19,25 %)</b>			
	<b>A.I.R (2.2 % or 5.5%)</b>			
	<b>TOTAL TTC</b>			
	<b>NET à MANDATER</b>			

**Document No. 8:  
Schedule of sub-detail of prices**

DESIGNATION :Studies and site installation					
No	Daily out put	Total quantity	Unit	Duration of activity	
<b>WORKMAN SHIP</b>	Category	No	Daily wage	Days break up	Amount
		TOTAL A			
<b>EQUIPMENT/MACHINES</b>	Type	No	Daily rate	Days break up	Amount
	TOTAL B				
<b>MISCELLANEOUS</b>	Type	Unit	Unit cost	Quantity	Amount
	TOTAL C				
<b>D</b>	<b>DIRECT TOTAL COST</b>			A+B+C	
<b>E</b>	<b>GENERAL SITE EXPENSES</b>			Dx%	
<b>F</b>	<b>GENERAL OFFICE EXPENSES</b>			Dx%	
<b>G</b>	<b>NET COST</b>			D+E+F	
<b>H</b>	<b>RISK + BENEFITS</b>			Gx%	
<b>P</b>	<b>TOTAL COST (HT)</b>			G+H	
<b>V</b>	<b>UNIT COST (HT)</b>			P/Q'TY	

**Document No. 9:  
Model contract**

REPUBLIQUE DU CAMEROUN  
Paix – Travail – Patrie

MINISTRE DE LA DECENTRALISATION  
ET DU DEVELOPPEMENT LOCAL

REGION DU NORD OUEST

DEPARTEMENT DE NGOKETUNJIA

ARRONDISSEMENT DE NDOP

COMMUNE DE NDOP

COMMISSION INTERNE DE  
PASSATION DES MARCHES



REPUBLIC OF CAMEROON  
Peace – Work – Fatherland

MINISTRY OF DECENTRALIZATION AND  
LOCAL DEVELOPMENT

NORTH WEST REGION

NGOKETUNJIA DIVISION

NDOP SUB DIVISION

NDOP COUNCIL

NDOP COUNCIL INTERNAL  
TENDERS' BOARD

JOBGING ORDER No \_\_\_\_\_ JO /NC/NCITB/2020 OF .....2020

**Awarded after OPEN NATIONAL INVITATION TO TENDER N°02/ONIT/  
NC/NCITB/2020 OF 8<sup>th</sup> JANUARY 2020 FOR THE CONSTRUCTION OF AN  
INTEGRATED HEALTH CENTRES (I.H.C) IN MBEBAH NGOKETUNJIA DIVISION**

Project Owner [Indicate name and full address]

**HOLDER** \_\_\_\_\_ : [indicate name and full address of holder]

P.O. Box \_\_\_\_\_, Tel: \_\_\_\_\_ Fax: \_\_\_\_\_

Business Registry No. \_\_\_\_\_ at  
Taxpayer's No. \_\_\_\_\_

**SUBJECT** \_\_\_\_\_ : Execution of \_\_\_\_\_ works;  
Lot No. \_\_\_\_\_; Network \_\_\_\_\_

**PLACE** \_\_\_\_\_ :Region \_\_\_\_\_

**EXECUTION DEADLINE** \_\_\_\_\_ ( \_\_\_\_\_ ) months

**AMOUNT IN CFA F:**

IAT	
EVAT	
VAT	
AIR (Income tax)	
Net to be paid	

**FINANCING** \_\_\_\_\_ : [indicate the source of financing]

**BUDGET HEAD** : [to be completed]

SUBSCRIBED ON: \_\_\_\_\_  
SIGNED ON: \_\_\_\_\_  
NOTIFIED ON: \_\_\_\_\_  
REGISTERED ON: \_\_\_\_\_

Between:

The Government of the Republic of Cameroon, represented by \_\_\_\_\_ hereinafter referred to the "Contracting Authority"

On the one hand,

And

\_\_\_\_\_ (enterprise)

P.O. Box \_\_\_\_\_ Tel: \_\_\_\_\_ Fax: \_\_\_\_\_

Business Registry No. \_\_\_\_\_

Taxpayer's No. \_\_\_\_\_

Represented by M. \_\_\_\_\_, its General Manager, hereinafter referred to as the "Contractor"

On the other hand,

Agree on the following:

### Summary

Part I: Special Administrative Conditions (SAC)

Part II: Special Technical Conditions (STC)

Part III: Schedule of Unit Prices (SUP)

Part IV: Details of Estimates

Page \_\_\_\_\_ and last of Contract No. \_\_\_\_\_ C or JO/CA/TB/0000  
Awarded after invitation to tender [specify references of invitation to tender]

With \_\_\_\_\_

For the execution of \_\_\_\_\_ works

**EXECUTION DEADLINE** \_\_\_\_\_ (\_\_\_\_\_) months

**Amount of contract in CFA F:**

IAT	
EVAT	
VAT (	
AIR (1.1 or 1.65 %)	
Net to be paid	

**Read and accepted by the contractor**

(place of signature) \_\_\_\_\_ (date)

**Signature of Delegated Contracting Authority**

(place of signature) \_\_\_\_\_ (date)

**Registration**

**Document No. 10:  
Forms and models to be used by bidders**

## Table of models

Annex No. 1: Model tender

Annex No. 2: Model bid bond

Model No. 3: Model final bond

Model No. 4: Model of start-off advance bond

Model No. 5: Model retention fund

Annex No. 6: Evaluation grid

Annex No. 7: Attestation of site visit

Annex No 8: Site Visit Report

## Annex No. 1: Model tender

I, the undersigned \_\_\_\_\_ [indicate the name and capacity of signatory]

Representing the \_\_\_\_\_ company or enterprise or group with head office at \_\_\_\_\_  
registered in the trade register of \_\_\_\_\_ under the number No \_\_\_\_\_

Having taken cognisance of all the documents featured or mentioned in the Tender File including the addendum (addenda): the invitation to tender [recall the subject of the invitation to tender]

- After having personally taken account of the situation of the site and evaluated from my point of view and under my responsibility, the nature and difficulty of the works to be carried out;
- Hereby submit, bearing my signature, the schedule of unit prices as well as the quotations in accordance with the structure featuring in the Tender File.
- Submit and commit myself to execute the works in accordance with the Tender File, in return for the prices which I myself establish for each type of structure which prices reveal the amount of the tender for lot No. \_\_\_\_\_ at \_\_\_\_\_ [in figures and words] CFA francs exclusive of VAT and at \_\_\_\_\_ CFA francs Inclusive of all Taxes. [In figures and words].
- I pledge to execute the works within a deadline of .....months.
- I pledge to maintain my bid for [indicate duration of validity, in principle 90days for national invitations to tender 120 days for international invitations to tender] from the deadline of submission of bids.
- Rebates and the modalities of application the said rebates shall be the following (in case of the possibility of award of several lots).

The Project Owner shall pay the sums due for this contract by crediting account No..... opened  
in.....Bank.....Branch

Prior to the signing of the contract, this tender accepted by you shall constitute an agreement between us.

Done at..... on.....

Signature of.....

in the capacity of.....duly authorised to sign the bids on behalf of.....

## ANNEX No. 2: MODEL BID BOND

Addressed to [indicate the Contracting Authority and his address] "Contracting Authority"

Whereas the undertaking \_\_\_\_\_ hereinafter referred to as the "bidder" has submitted his bid on \_\_\_\_\_ for [recall the subject of the invitation to tender], hereinafter referred to as "the bid" and to which must be attached a bid bond equivalent to [indicate the amount] CFA francs.

We \_\_\_\_\_ [name and address of the bank], represented by \_\_\_\_\_ [names of signatories], hereinafter referred to as "the bank" hereby guarantee payment to the Contracting Authority of the maximum sum of [indicate the amount] CFA francs, that the bank pledges to pay in full to the Contracting Authority, binding itself, its successors and assignees.

The conditions of this commitment are as follows:

If the bidder retires his bid during the validity period provided for in the Tender File;

Or

If the bidder, having been notified of the award of the contract by the Contracting Authority during the validity period:

- Fails or refuses to sign the contract, even though required to do so;
- Fails or refuses to furnish the final bond for the contract (final bond) as provided for by the contract;

We pledge to pay to the [Contracting Authority] an amount up to the maximum of the sum referred to above upon reception of the his first written request, without the Contracting Authority having to justify his request, given, however, that in his request the Contracting Authority shall note that he is due the amount he is claiming because one or the other or both of the above condition(s) has (have) been fulfilled and he shall specify which condition(s) took effect.

This bond shall enter into force from the date of signature and from the date set by the Contracting Authority for the submission of bids. It shall remain valid up till the thirtieth day inclusive following the end of the deadline for the validity of bids. Any request by the Contracting Authority to cause it to take effect should reach the bank by registered mail with an acknowledgement of receipt before the end of this period of validity.

This bond shall, for purposes of its interpretation and execution, be subject to Cameroon law. Cameroon courts shall be the only jurisdictions competent to rule on this commitment and its consequences.

Signed and authenticated by the bank at \_\_\_\_\_, on \_\_\_\_\_

[Bank's signature]

Annex No. 3: Model final bond

Bank:

Reference of the bond: No. \_\_\_\_\_

Addressed to [indicate the Project Owner and his address] Cameroon, hereinafter referred to as the "Project Owner"

Whereas [name and address of Contractor], hereafter referred to as "the Contractor", has committed himself, in execution of the contract referred to as "the contract", to carry out [indicate the nature of the works].

Whereas it is stated in the contract that the Contractor shall entrust to the Project Owner a final bond of an amount equal to [indicate the percentage between 2 and 5%] of the amount of the corresponding portion of the contract, as guarantee of the execution of his full obligations in accordance with the terms of the contract,

Whereas we have agreed to issue the Contractor this guarantee,

We, \_\_\_\_\_ [name and address of bank] represented by \_\_\_\_\_ [name of signatories],

hereinafter referred to as "the bank", commit ourselves to pay the Project Owner, within a maximum deadline of eight (8) weeks, upon the simple written request declaring that the Contractor has not satisfied his contractual commitments within the meaning of the contract, without being able to defer the payment nor raise any contests for whatever reason, any sum up to the sum of \_\_\_\_\_ [in figures and words].

We agree that no change or addendum or any other amendment to the contract shall free us of any obligation incumbent on us by virtue of this final bond and we hereby incline to any notification, addendum or change.

This final bond shall enter into force upon signature and notification of the contract. It shall be released within a deadline of [indicate the deadline] from the date of the provisional acceptance of the works.

After this date, the bond shall be baseless and should be returned to us without the express request on our part.

Any request for payment made by the Project Owner by virtue of this guarantee should be done by registered mail with acknowledgement of receipt to reach the bank during the period of validity of this commitment.

This bond shall, for purposes of its interpretation, be subject to Cameroon law. Cameroon courts shall be the only jurisdictions competent to rule on this commitment and its consequences.

Signed and authenticated by the bank at \_\_\_\_\_ on \_\_\_\_\_

[Signature of the bank]

**ANNEX No. 4: Model of start-off advance bond**

Bank: reference, address \_\_\_\_\_

We, the undersigned, (bank, address) hereby declare by the present to guarantee on behalf of \_\_\_\_\_ [the holder] to the benefit of the Project Owner [address of the Project Owner] (the beneficiary).

The payment, without contest and upon receipt of the first written request by the beneficiary, declaring that \_\_\_\_\_ [the holder] has not fulfilled his obligations relating to the reimbursement of the start-off advance according to the terms of contract No. \_\_\_\_\_ of \_\_\_\_\_ relating to \_\_\_\_\_ works [indicate the subject of the works, the references of the invitation to tender and the lot, if possible] of the total sum corresponding to the advance of [twenty (20) %] of the amount inclusive of all taxes of contract No. \_\_\_\_\_, payable upon notification of the corresponding Administrative Order that is, \_\_\_\_\_ CFA francs.

This bond shall enter into force and shall take effect upon reception of the respective parts of this advance into the accounts of \_\_\_\_\_ [the holder] opened in the \_\_\_\_\_ bank under No. \_\_\_\_\_.

This bond shall remain in force up till the reimbursement of the advance in accordance with the SAC. However, the amount of the bond shall be proportionately reduced on the progressive reimbursement of the advance.

The applicable law and jurisdiction shall be those of the Republic of Cameroon.

Signed and authenticated by the bank at \_\_\_\_\_ on \_\_\_\_\_

[Signature of the bank]

**ANNEX No. 5: Model of performance bond (Retention fund)**

Bank: \_\_\_\_\_  
Reference of the bond; No \_\_\_\_\_

Addressed to *[Indicate the Project Owner]*  
*[Address of Contracting Authority]*

Hereinafter referred to as "the Project Owner"

Whereas \_\_\_\_\_ *name and address of Supplier*] hereinafter referred to "the contractor", pledged, in execution of the contract, to carry out the works of *[indicate the subject of the works]*

Whereas it is stipulated in the contract that the retention fund fixed at *[percentage below 10 % to be specified]* of the amount of the contract may be replaced by a joint guarantee,

Whereas we have agreed to provide the Contractor with this guarantee,

We, \_\_\_\_\_ *[name and address of the bank],*

Represented by \_\_\_\_\_ *[names of signatories]* and hereinafter referred to as "the bank"

Hence, we hereby affirm that on behalf of the Contractor, we guarantee and are responsible to the Project Owner for a maximum amount of \_\_\_\_\_  
*[in figures and letters]* corresponding to *[percentage below 10 % to be specified]* of the contract price.

And we pledge to pay to the Project Owner within a maximum deadline of eight (8) weeks upon his simple written request declaring that the contractor has not fulfilled his contractual obligations or is indebted to the Project Owner within the meaning of the contract, amended where need be, by its additional clauses, without being able to defer the payment nor raise any contest for whatever reason, any sum(s) within the limits of the amount equal to *[percentage below 10 % to be specified]* of the total amount of the works featuring in the final detailed account, without the Project Owner having to prove or give the reasons nor the motive for the amount of the sum indicated above.

We hereby agree that no change or addendum or any other amendment shall release us of any obligation incumbent on us by virtue of this bond and we hereby incline by the present to the notification of any amendment, addendum or change.

This bond shall enter into force upon signature. It shall be released within thirty (30) days from the date of the final acceptance of the works and upon release issued by the Project Owner.

Any request for payment made by the Project Owner by virtue of this bond should be done by registered mail with acknowledgement of receipt to reach the bank during the period of validity of this commitment.

This bond shall, for purposes of its interpretation and execution, be subject to Cameroon law. Cameroon courts shall be the only jurisdictions competent to rule on this pledge and its consequences.

Signed and authenticated by the bank at \_\_\_\_\_ on \_\_\_\_\_

*[Signature of the bank]*

**ANNEX 6: EVALUATION GRID**  
**NºTENDER Nº02/ONIT / NC/NCITB/2020 of 8<sup>th</sup> JANUARY 2020**

**FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRES (I.H.C) IN MBEBAH IN  
 NGOKETUNJIA DIVISION OF THE NORTH WEST REGION**

**ADMINISTRATIVE DOCUMENTS.**

<b>NO</b>	<b>DESCRIPTION</b>	<b>YES</b>	<b>NO</b>
A.1	Certified Copy of the Business Registration, not more than three months old.		
A.2	Declaration of intention to tender stamped with the tariff in force.		
A.3	Certificate of non-bankruptcy established by the Court of 1st instance or the Chamber Commerce, Industry and Trade of the place of residence of the bidder, not more than three (03) months.		
A.4	Attestation of bank account of the bidder, issued by a first rate-bank approved by the Ministry in charge of Finance or by a foreign bank the first order not more than three months.		
A.5	Purchase receipt of tender file issued by public treasury		
A.6	A bid bond issued by a first rate-bank approved by the Ministry in charge of Finance in conformity with COBAC conditions		
A.7	An attestation of non-exclusion from Public Contracts issued by the Public contract Regulatory Board (ARMP)		
A.8	An Attestation signed by the National Social Insurance Fund stating that the bidder has met all his obligations vis a vis the Fund; the attestation should be less than three months old.		
A.9	A valid Certificate of imposition certified by the chief of tax centre		
A.10	Business License (photocopy certified by the chief of tax centre, not more than three months).		
A.11	Certified Copy of a valid taxpayers card, delivered by the chief of tax centre		
A.12	A Clearance Certificate signed by the chief of tax centre stating that the bidder has met all the statutory declarations in issues of taxes in the current financial year; this certificate should be less than three months old.		

EVALUATION GRID OF TECHNICAL BID		YES	NO
N°	EVALUATION CRITERIA AND SUB-CRITERIA	YES	NO
<b>B) ESSENTIAL CRITERIA</b>			
<b>B.1</b>	<b>General presentation of the tender files</b>		
B.1.1	-Document spirally bound -Table of content page		
B.1.2	-Colour sheets separation - Presentation of documents in the order given in this tender		
<b>B.2</b>	<b>LIST OF REFERENCES OF THE ENTERPRISE IN THE SIMILAR JOBS</b>		
B.2.1	List of references of the enterprise in similar jobs justified by signed contracts (first and last pages) and minutes of reception or attestation of clearances of works executed. (minutes of final reception for up to 2018 projects) Minimum acceptable: 02 Contracts realized in the domain of building construction over the past 05 years		
	1st Reference		
	2nd reference		
<b>B.3</b>	<b>QUALIFICATION AND EXPERIENCE OF SUPERVISORY STAFF FOR EACH LOT</b>		
<b>B.3.1</b>	<b>01 works supervisor (at least HND or equivalent certificate)</b>		
	Qualification of the works supervisor: (Senior Technician certificate in Civil Engineering (BAC +2) Professional experience of the project engineer $\geq$ 03 years (signed CV)		
	<ul style="list-style-type: none"> <li>➤ A certified copy of the technical diploma,</li> <li>➤ Certified copy of ID card</li> </ul>		
	<ul style="list-style-type: none"> <li>➤ An Attestation of presentation of original of the technical diploma</li> <li>➤ CV signed and dated by the candidate,</li> </ul>		
<b>B.3.2</b>	<b>01 Site foreman(Civil Engineering Senior Technician)</b>		
	Qualification of the Site foreman: (Technician certificate in Civil Engineering (BAC F4 or equivalent certificate) Professional experience of the Site foreman $\geq$ 03 years (signed CV) A certified copy of		
	<ul style="list-style-type: none"> <li>➤ A certified copy of the technical diploma,</li> <li>➤ Certified copy of ID card</li> </ul>		
	<ul style="list-style-type: none"> <li>➤ An Attestation of presentation of original of the technical diploma</li> <li>➤ CV signed and dated by the candidate,</li> </ul>		
<b>B.3.3</b>	<b>Other personnel</b>		
	List of support staff		
<b>B.4</b>	<b>TECHNICAL PROPOSALS</b>		
B.4.2	Organizational chart of the project (Specify names of the personnel handling the various functions)		
B.4.3	Logical sequence for the execution of the task		
B.4.5	Quality control method		
B.4.7	Environmental protection measures		
B.4.8	Security and safety at the site		

B.4.9	Duration of execution in respect with the Tender file		
B.5	<b>LOGISTICS (Equipment put aside for this project)</b>		
B.5.1	Proof of ownership or rental of a pick-up or other vans		
B.5.2	Proof of ownership or rental of a dump truck		
B.5.3	Proof of ownership or rental of a concrete vibrator		
B.5.4	Proof of ownership or rental of a Hand compactor		
B.5.5	Masonry Kit : Wheelbarrows, masonry clamps, masonry harmer 300g, shovel, dig axe, building level, masonry bucket , trowels, etc.		
	Carpentry Kit : carpentry clamps, saws, hammers, etc.		
B.6	<b>FINANCIAL CAPACITY</b>		
B.6.1	An attestation of financial capacity (solvency) of the enterprise issued by a 1st class bank located in any area in Cameroon and approved by the Ministry of Finance and respect COBAC conditions. 100%		
B.7	Attestation of site visit signed by the company		
B.8	Comprehensive report of site visit signed by the company administrator and justified by photos		
B.9	Special Technical Clauses initialed in all the pages and last page signed and dated		
B.10	Special Administrative Clauses completed and initialed in all the pages and last page signed and dated		

This evaluation will be done in a purely positive way (yes) or negative (no) with an acceptable minimum from at least 80% of the essential criteria taken in account.

The contract will be awarded to the bidder who would have proposed the offer with the lowest amount, in conformity with the regulations of the Tender Documents and having satisfied to 100% of the eliminatory criteria and at least 20/25 of the essential criteria.

#### **A. Eliminatory criteria**

- 1- False declaration or falsified documents;
- 2- Absence or insufficient bid bond;
- 3- Incomplete financial file;
- 4- Omission of a unit price in the financial bid;
- 5- Score less than 20/25.
- 6- Absence or non-conformity of a document in the administrative file

#### **B. Essential criteria**

- 1- General presentation of the tender files;
- 2- Financial capacity;
- 3- References of the company in similar achievements;
- 4- Quality of the personnel;
- 5- Technical organization of the works;
- 6- Logistics;
- 7- Attestation and report of site visit;
- 8- Special Technical Clauses initialed in all the pages;
- 9- Special Administrative Clauses completed and initialed in all the pages.

#### **11. Main qualification criteria**

The criteria relating to the qualification of candidates could be indicative on the following:

The essential criteria are subjected to minima whose detail is given in the Special Tender Regulation (RPAO).

This evaluation will be done in a purely positive way (yes) or negative (no) with an acceptable minimum from at least 20/25 of the essential criteria taken in account.

The contract will be awarded to the bidder who would have proposed the offer with the lowest amount, in conformity with the regulations of the Tender Documents and having satisfied to 100% of the eliminatory criteria and at least 20/25 of the essential criteria.

**ANNEX 7: MODELE ATTESTATION OF SITE VISIT**

I, the undersigned Mr./Mrs./Miss .....[Surname and Name of Director]The Director of ..... [Name of company] confirm that

Mr./Mrs./Miss ..... (Surname and Name)

Engineer of the Company:..... (Name of Enterprise),

has actually visited the site which is going to receive the structure relative to tender OPEN NATIONAL INVITATION TO TENDER N°02/ONIT/ NC/NCITB/2020OF 8<sup>th</sup> January 2020 FOR THE CONSTRUCTION OF AN INTEGRATED HEALTH CENTRES (I.H.C) IN MBEBAH IN NGOKETUNJIA DIVISION OF THE NORTH WEST REGION.....

The interested person declares:

- To have carried out a thorough study of the site taking into consideration all the constraints relative to the execution of the job with respect to norms.
- To establish his unit price schedules taking into account the difficulties of the site relative to the execution of the works and shall in no condition claim the Delegated Contracting Authority for any increase of unit price.

In Testimony Whereof, this present **ATTESTATION OF SITE VISIT** is established and issued to serve the purpose it deserves.

Date .....  
Stamp of enterprise

Signature and Names of the Engineer

**ANNEX 8: SITE VISIT REPORT**

Name of Project.....

Name of Enterprise .....

1. CONTEXT OF THE PROJECT
2. GEOGRAPHICAL SITUATION
3. STATE OF THE SITE
4. PHOTOGRAPHS OF THE SITE (access to the site, existing structures of the school, Sign post of the school, Photos of the Engineer of the enterprise in front of the school building etc.)

Date.....

Name of Enterprise: .....

Stamp and signature of enterprise

# Document No. 11: Preliminary studies

*[To be systematically filled by the Project Owner based on the nature of services to be executed and according to the specifications of Point 5.a of Circular No. 003/CAB/PM of 18 April 2008 relating to the respect of rules governing the award, execution and control of public contracts]*

## **Note on preliminary studies**

In accordance with the Public Contracts Code, the Project Owner or Delegated Project Owner must, prior to commencing the procedure to award contracts or refer to the competent Tenders Board, ensure that draft tender files are prepared based on preliminary studies.

These studies must be required during the examination of the Tender File (TF) by the Tenders Board.

The Project Owner is bound to fill the questionnaire in annex 1 accompanied by justifications of the said studies.

## Annex No. 7: Justification of preliminary studies

1. Attach the preliminary studies.

2. Indicate

2.1. The date studies were carried out;

2.2. The name of the public or private Project Manager

2.3. References of the contract, if Private Manager carried it out;

2.4. If maintenance works

1.4.1 Description of the studies;

1.4.2 Attach the outline of the itinerary bringing out readings of degradations as well as the approved programming documents.

1.5 Rehabilitation or new works

1.5.1 Are quantities in the quotations the same as those of the studies?

1.5.2 Description of studies: Draft Preliminary Study, Detailed Preliminary Study;

1.5.3 Attach the said studies.

N.B. For services of less scope, the Project Owner may furnish a justification of calculation of quantities of the tender file.

- *The chairperson of the Tenders Board may, before taking a decision, seek expert advice on the quality of the studies.*

**Document No. 12:  
List of banking establishments and  
financial bodies authorised to issue  
bonds for public contracts**

## **I- BANKS**


1. Afriland First Bank
2. Banque Atlantique
3. Banque Gabonaise pour le Financement International (BGFI BANK)
4. Banque International du Cameroun pour l'Epargne et le Crédit (BICEC)
5. CITI Bank
6. Commercial Bank of Cameroon (CBC)
7. Ecobank
8. National Financial Credit Bank
9. Société Camerounaise de Banque au Cameroun
10. Société Générale de Banque au Cameroun
11. Standard Chartered Bank Cameroon
12. Union Bank of Cameroon
13. United Bank for Africa.

## **II- Insurance companies**

14. Chanas Insurance;
15. Activa Insurance
16. Zenithe insurance SA BP Douala


Document No. 13

PLANS



PLAN DE DISTRIBUTION

ECH 0M 1M 2M




PLAN DE FONDATION

ECH. 0M 1M 2M









PLAN DE TOITURE

ECH. 0M 1M 2M






FAÇADE PRINCIPALE




FAÇADE ARRIÈRE

ECH 0M 1M 2M




FAÇADE LATÉRALE GAUCHE




FAÇADE LATÉRALE DROITE

ECH. 0M 1M 2M



COUPE TRANSVERSALE PARTIE CENTRALE



COUPE TRANSVERSALE SUR AILES

ECH 0M 1M 2M