REPUBLIC OF CAMEROON Peace — Work — Fatherland

MINISTRY OF DECENTRALIZATION AND

LOCAL DEVELOPMENT

NORTH WEST REGION

**BOYO DIVISION** 

NJINIKOM COUNCIL INTERNAL TENDERS BOARD P.O BOX 01, NJINIKOM TEL: 677669400/677323293/670294650

REPUBLIQUE DU CAMEROUN Paix-Travail-Patrie

MINISTERE DE LA DECENTRALISATION ET DU DEVELOPPEMENT LOCAL

**REGION DU NORD-OUEST** 

DEPARTEMENT DE BOYO

COMMISSION INTERNE DE PASSATION DES MARCHES PUBLICS DE LA COMMUNE DE NJINIKOM

B.P 01, NJINIKOM TEL: 677669400/677323293/670294650

# OPEN NATIONAL INVITATION TO TENDER **TENDER FILE**

LOT 01

N° 11/ONIT/MINDDEVEL/NC/NCITB/PIB/2024/6/2/2024 FOR THE RURAL ELECTRIFICATION OF TWAFUNDONG VILLAGE IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION

PROJECT OWNER: THE LORD MAYOR NJINIKOM COUNCIL FINANCING: MINEE - PUBLIC INVESTMENT BUDGET - 2024

BUDGET HEAD	58 32 137 01 641644 464211 851
AUTH.	IZ05180
PROJECT COST	22,000,000 FCFA
BID BON	440,000 FCFA
TENDER FEE	50,000 FCFA
FINANCIAL YEAR	2024
DURATION	03 MONTHS

**LOT 02** 

N° 12/ONIT/MINDDEVEL/NC/NCITB/PIB/2024/6/2/2024 FOR THE RURAL ELECTRIFICATION OF MUGHEFF DOWN VILLAGE IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION

58 32 137 01 641644 464211 851
IZ05179
20,000,000 FCFA
400,000 FCFA
45,000 FCFA
2024
03 MONTHS

# TABLE OF CONTENTS

Document No. 1: Tender Notice
Document No. 2: General Regulations of the Invitation to Tender
Document No. 3: Special Regulations of the Invitation to Tender
Document No. 4: Special Administrative Conditions
Document No. 5: Special Technical Conditions
Document No. 6: Schedule of unit prices
Document No. 7: Bill of quantities and estimates
Document No. 8: The sub-detail of prices
Document No. 9: Model Contract
Document No. 10: Model documents to be used by bidders
Document No. 11: Justifications of preliminary studies
Document No. 12: List of banking establishments and financial bodies authorized  To issue bonds for Public Contracts

# Document N°. 1 TENDER NOTICE

REPUBLIC OF CAMEROON Peace - Work - Fatherland

MINISTRY OF DECENTRALIZATION AND LOCAL DEVELOPMENT

NORTH WEST REGION

**BOYO DIVISION** 

NJINIKOM COUNCIL INTERNAL TENDERS BOARD P.O BOX 01, NJINIKOM TEL: 677669400/677323293/670294650



REPUBLIQUE DU CAMEROUN Paix-Travail-Patrie

MINISTERE DE LA DECENTRALISATION ET DU DEVELOPPEMENT LOCAL

**REGION DU NORD-OUEST** 

DEPARTEMENT DE BOYO

COMMISSION INTERNE DE PASSATION DES MARCHES PUBLICS DE LA COMMUNE DE NJINIKOM B.P 01, NJINIKOM TEL: 677669400/677323293/670294650

TENDER NOTICE

OPENED NATIONAL INVITATION TO TENDER ONIT/ NJINIKOM COUNCIL/NCITB/2024 OF 16 / 2024 FOR THE RURAL ELECTRIFICATION OF MUGHEFF DOWN / TWAFUNDONG VILLAGES IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION.

Financing: Public Investment Budget - (BIP) 2024

Subject of the Invitation to Tender:

Within the framework of 2023 Public Investment Budget, The MAYOR NJINIKOM COUNCIL, Contracting Authority, hereby launches an Open National Invitation to tender for the Rural Electrification of MUGHEFF DOWN AND TWAFUNDONG VILLAGES in Njinikom Municipality, Boyo Division of the North West Region.

# A - Nature of work: MUGHEFF DOWN

Work to be done consists of

- ✓ Construction of an MV/LV single phase line in 1x34.4mm² Almelec & 4x25 Mm² Aluminum
- Construction of an LV single phase line in 4x25 Mm<sup>2</sup> Aluminum Twisted Cables
- ✓ Installation of one control connections with 2x16 mm² Aluminum cable;
- ✓ Supply and Installation of one (01) transformer phase H61-25KVA 17.32KV/B2
- Production and validation of environmental impact notice
- ✓ The Sundry expenses will consist of:
  - Clearing and pruning 7m width on each side of the network.
  - > Transportation of wooden poles, materials and workers.

# B - Nature of work: TWAFUNDONG

Work to be done consists of

- ✓ Construction of an MV/LV single phase line in 1x34.4mm² Almelec & 4x25 Mm² Aluminum ✓ Construction of an LV single phase line in 4x25 Mm² Aluminum Twisted Cables
- ✓ Installation of one control connections with 2x16 mm² Aluminum cable;
- ✓ Supply and Installation of one (01) transformer phase H61-25KVA 17.32KV/B2 Production and validation of environmental impact notice
- ✓ The Sundry expenses will consist of:
  - Clearing and pruning 7m width on each side of the network.
  - > Transportation of wooden poles, materials and workers.

### **Execution deadline**

The maximum deadline provided by the Contracting Authority for the execution of the works forming the subject of this Invitation to Tender is Ninety (90) days

4 | MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECTS 2024

The work is as follows:

### **LOT 01**

### N° 11/ONIT/MINDDEVEL/NC/NCITB/PIB/2024 \_\_/\_/2024 FOR THE RURAL ELECTRIFICATION OF TWAFUNDONG VILLAGE IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION

TOO TOO	22,000,000 FCFA	
PROJECT COST	440,000 FCFA	_
BID BON	50,000 FCFA	
TENDER FEE	2024	
FINANCIAL YEAR	03 MONTHS	
DURATION		

### **LOT 02**

### N° 12/ONIT/MINDDEVEL/NC/NCITB/PIB/2024 \_\_/\_/2024 FOR THE RURAL ELECTRIFICATION OF MUGHEFF DOWN VILLAGE IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION

TOT COST	20,000,000 FCFA	
PROJECT COST	400,000 FCFA	
BID BON	45,000 FCFA	
TENDER FEE	2024	
FINANCIAL YEAR	03 MONTHS	
DURATION	00 morning	

### **Estimated cost**

The estimated cost after preliminary studies is 20.000.000 FCFA, for Mugheff and 22,000,000 FCFA for Twafundong

Participation to this Invitation to Tender is opened to Cameroonian enterprises that are in compliance with the Cameroon laws.

Works which form the subject of this Invitation to tender shall be financed by the 2024 Public **Financing** Investment Budget

Each bidder must include in his administrative documents, a bid bond issued by a first-rate banking **Bid bonds** establishment approved by the Ministry in charge of Finance and whose list is found in document N°. 12 of the Tender File, of an amount of 400 000 CFA for Mugheff and 440 000 FCFA for Twafundong and valid for thirty (30) days beyond the date of validity of bids

The file may be consulted during working hours at the NJINIKOM COUNCIL, Contract Award Consultation of Tender File: Service, as soon as this notice is published.

The file may be obtained from the NJINIKOM COUNCIL at the Secretariat of the Mayor, Acquisition of Tender File: 10. as soon as this notice is published against the payment of the sum of 45 000 CFA francs for Mugheff and 50 000 FCFA for Twafundong, payable at the Njinikom Council Treasury, representing the cost of

### 11. Submission of bids:

Each offer drafted in English or French in 07 (seven) copies including 01 (one) original and 06 (six) copies marked as such, should reach the NJINIKOM COUNCIL, Contract Award Service not later than 2/13/2024 at 10:00 local time and should carry the inscription:

## << OPEN NATIONAL INVITATION TO TENDER Nº///2/ONIT/ NJINIKOM COUNCIL/NCITB/2024 OF 6/2/2024 FOR THE RURAL ELECTRIFICATION OF MUGHEFF DOWN / TWAFUNDONG VILLAGES IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION.

"To be open only during the bid-opening session"

Admissibility of bids

Under penalty of being rejected, only originals or certified true copies signed by the issuing service or administrative authorities (Senior Divisional Officer, Divisional Officers) must imperatively be produced in accordance with the Special Regulations of the Invitation to Tender.

They must obligatorily not be older than three (3) months preceding the date of submission of bids or may be established after the signature of the tender notice

Any bid not in compliance with the prescriptions of the Tender File shall be rejected. This refers especially to the absence of a bid bond issued by a first-rate bank approved by the Minister in charge of Finance. .

Opening of bids:

The bids shall be open in a single phase. The opening of the administrative documents, the Technical and Financial offers will take place on the 2/13/2024 at 11: 00AM local time, in the conference hall of the NJINIKOM Council, by its competent Members. Only bidders may attend or be represented by duly mandated persons of their choice and having a good knowledge of their files. **Evaluation** criteria

The bids shall be evaluated according to the main criteria as follows

### Eliminatory criteria

Absence or non-conformity of an element in the administrative file;

Deadline for delivery higher than prescribed;

False declaration or falsified documents;

Absence or insufficient bid bond;

A bid with the external envelope carrying a sign or mark leading to the identification of the bidder;

Change of quantity or unit;

Non respect of 37/43 (85%) of essential criteria;

Non completion of any project in the previous years in the North West Region and suspended by

### Essential criteria

General presentation of the Tender Files;

Financial capacity;

References of the company in similar achievements;

Quality of the personnel;

Technical organization of the works;

Safety measures on the site;

6 | MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECTS 2024

Logistics;

Attestation and report of site visit;

Special Technical Clauses initialed in all the pages;

Special Administrative Clauses completed and initialed in all the pages.

This evaluation will be done in a binary way (yes) or (no) with an acceptable minimum of 37/43 (85%) of 15. Award the essential criteria taken in account.

The Contract will be awarded to the bidder who would have proposed the offer with the lowest amount, in conformity with the regulations of the Tender Documents and having satisfied to 100% of the eliminatory criteria and at least 37/43 (85%) of the essential criteria.

Bidders will remain committed to their offers for sixty (60) days from the deadline set for the submission of 16. Validity of bids tenders.

Complementary technical information may be obtained during working hours from NJINIKOM Council at Complementary information the Mayor's Secretariat.

Done at NJINIKOM on OUThe Lord Mayor Njinikom Council REPUBLIC OF CAMEROON Peace - Work - Fatherland

MINISTRY OF DECENTRALIZATION AND LOCAL DEVELOPMENT

NORTH WEST REGION

**BOYO DIVISION** 

NJINIKOM COUNCIL INTERNAL **TENDERS BOARD** P.O BOX 01, NJINIKOM TEL: 677669400/677323293/670294650



REPUBLIQUE DU CAMEROUN Paix-Travail-Patrie

MINISTERE DE LA DECENTRALISATION ET DU DEVELOPPEMENT LOCAL

**REGION DU NORD-OUEST** 

DEPARTEMENT DE BOYO

COMMISSION INTERNE DE PASSATION DES MARCHES PUBLICS DE LA COMMUNE DE NJINIKOM B.P 01, NJINIKOM

TEL: 677669400/677323293/670294650

# AVIS D'APPEL D'OFFRES

AVIS D'APPEL D'OFFRES NATIONAL OUVERT Nº ///AONO/COMMUNE DE NJINIKOM/CIPMN/2024 DU 1/2 2024 POUR L'ELECTRIFICATION RURALES DES VILLAGES MUGHEFF DOWN ET TWAFUNDONG DANS L'ARRONDISSEMENT DE NJINIKOM, DEPARTEMENT DU BOYO.

Financement : Budget d'Investissement Public 2024

Objet de l'Appel d'Offre

Dans le cadre de l'exercice budgétaire 2024, le Maire de la Commune de NJINIKOM, Autorité Contractante lance un Appel d'Offres National Restreint pour les travaux d'électrification des villages MUGHEFF DOWN ET TWAFUNDONG dans l'Arrondissement de NJINIKOM, Département du

# A- Consistence des travaux (MUGHEFF)

Les travaux comprennent notamment :

- Construction d'une ligne MT/BT 34,4mm2 et 4 x 25mm2 torsadee
- Construction d'une ligne BT 1 x 25mm2 cable en Aluminium
- Installation d'une postes témoins avec du câble 2x16 mm² Aluminium torsadé;
- Fourniture et installation d'un poste de transfo H61-25KVA 17.32KV/B2
- Production et validation de la Notice d'Impact Environnemental;
- Les prestations diverse comprennent :
  - Abattage et élagage de 7m sur chaque cote du réseau.
  - Transport des poteaux bois, matériels and ouvriers.

# B- Consistance des travaux (TWAFUNDONG)

Les travaux comprennent notamment:

- Construction d'une ligne MT/BT 34,4mm2 et 4 x 25mm2 torsadee sur une distance de 900m Construction d'une ligne BT, 1 x 25mm2 cable en Aluminium
- Installation d'une postes témoins avec du câble 2x16 mm² Aluminium torsadé;
- Fourniture et installation d'un poste de transfo H61-25KVA 17.32KV/B2
- Production et validation de la Notice d'Impact Environnemental;
- Les prestations diverse comprennent :
  - Abattage et élagage de 7m sur chaque cote du réseau.
  - Transport des poteaux bois, matériels and ouvriers.

Délais d'exécution

Le délai maximum prévu le Maître d'Ouvrage pour la réalisation des travaux objet du présent appel d'offres est de quatre-vingt dix (90) jours.

### Allotissement

Le travail est ci-après défini :

### LOT 01

N° 11/ONIT/MINDDEVEL/NC/NCITB/PIB/2024 \_\_/\_/2024 FOR THE RURAL ELECTRIFICATION OF TWAFUNDONG VILLAGE IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION

T202 COST	22,000,000 FCFA	
PROJECT COST	440,000 FCFA	
BID BON	50,000 FCFA	
TENDER FEE	2024	
FINANCIAL YEAR DURATION	03 MONTHS	

### **LOT 02**

N° 12/ONIT/MINDDEVEL/NC/NCITB/PIB/2024 \_\_/\_/2024 FOR THE RURAL ELECTRIFICATION OF MUGHEFF DOWN VILLAGE IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION

	20,000,000 FCFA	
PROJECT COST	400,000 FCFA	
BID BON	45,000 FCFA	
TENDER FEE	2024	
FINANCIAL YEAR DURATION	03 MONTHS	

Le coût prévisionnel de l'opération à l'issue des études préalables est de Vingt Million Francs CFA Coût prévisionnel (20.000.000 FCFA) pour Mugheff et Vingt-deux millions (22,000,000 FCFA) pour TWAFUNDONG.

Participation et origine La participation à cette consultation est ouverte aux entreprises de droit camerounais.

Les travaux objet du présent appel d'offres sont financés par le Budget d'Investissement Publics MINEE du Cameroun de l'exercice 2024

Chaque soumissionnaire doit joindre à ses pièces administratives, une caution de soumission établie Cautionnement provisoire par une banque de premier ordre agréée par le Ministère chargé des finances et dont la liste figure dans la pièce 12 du DAO, d'un montant de of 2 000 000 FCFA pour MUGHEFF et 2,200,000 FCFA pour TWAFUNDONG et valable pendant trente (30) jours au-delà de la date originale de validité des offres.

Le Dossier d'Appel d'Offres peut être consulté et obtenu aux heures ouvrables à la Délégation Consultation du Dossier d'Appel d'Offres Départementale des Marches Publics du Boyo, Service de Passation des Marchés Publics dès Publication du présent avis.

# Acquisition du Dossier d'Appel d'Offres

Le dossier peut être obtenu aux heures ouvrables à la Marie de NJINIKOM, Service d'Agent Communal de Développement (ACD) dès Publication du présent avis, contre présentation d'une quittance de versement au Trésor de la Commune de Njinikom de la somme non remboursable de F CFA 45 000 pour Mugheff Down et FCFA 50,000 pour TWAFUNDONG.

### Remise des offres

Chaque offre rédigée en français ou en anglais en sept (07) exemplaires dont un (01) original et six (06) copies marquées comme telles, devra parvenir contre récépissé à la Délégation Départementale des Marchés Publics du Boyo, Service de Passation des Marchés Publics au plus tard le 1/2/2023 à 10 h 00, heure locale et devra porter la mention suivante :

«AVIS D'APPEL D'OFFRES NATIONAL OUVERT N° 1/2/AONO/ COMMUNE DE NJINIKOM/CIPMN /2024 DU 1/6 / 2024 POUR L'ELECTRIFICATION RURALES des villages MUGHEFF DOWN et TWAFUNDONG dans l'Arrondissement de NJINIKOM, DEPARTEMENT DU BOYO» «A N'OUVRIR QU'EN SEANCE DE DEPOUILLEMENT»

### Recevabilité des offres

Sous peine de rejet, les pièces du dossier administratif requises doivent être produites en originaux ou en copies certifiées conformes par le service émetteur ou une autorité administrative (Préfet, Souspréfet,...), conformément aux stipulations du Règlement Particulier de l'Appel d'Offres.

Elles doivent dater de moins de trois (03) mois précédant la date originale de dépôt des offres ou avoir été établies postérieurement à la date de signature de l'Avis d'Appel d'Offres.

Toute offre incomplète conformément aux prescriptions du Dossier d'Appel d'Offres sera déclarée irrecevable. Notamment l'absence de la caution de soumission délivrée par une banque de premier ordre

Ouverture des plis

L'ouverture des plis se fera en un temps. L'ouverture des pièces administratives et des offres techniques et financières aura lieu le 2/13/2024 à 10h00, heure locale, dans la salle de conférence de la Commun de NJINIKOM, par la Commission de Passation de Marchés siégeant en présence des soumissionnaires ou de leurs représentants dûment mandatés et ayant une parfaite connaissance du dossier.

### Critères d'évaluation

Les offres seront évaluées selon les principaux critères suivants :

### A - Critères éliminatoires

Il s'agit notamment:

Absence ou non-conformité d'une pièce administrative ;

Délai d'exécution supérieur à celui prescrit (supérieur à trois mois);

Fausses déclarations ou pièces falsifiées;

Absence ou insuffisance de la caution provisoire de soumission;

Offres dont l'enveloppe extérieure porte des mentions permettant de reconnaître le Soumissionnaire;

Le changement d'une unité ou d'une quantité dans l'offre financière ;

Le non-respect de 37/43 (85%) des critères essentiels ;

Non achèvement d'un projet pendant les années antérieures sur l'étendue du Territoire National et B - Critères essentiels

Les critères relatifs à la qualification des candidats porteront à titre indicatif sur : Présentation générale de l'offre ; Capacité financière ; Références de l'entreprise dans les réalisations similaires ; Qualité du personnel; Organisation technique des travaux; Sécurité au chantier : Moyens logistiques; Attestation et rapport de visite du site; Cahier des Clauses Techniques Particulières paraphé à chaque page ; Cahier des Clauses Administratives Particulières complété et paraphé à chaque page. Les critères essentiels sont soumis à des minima dont le détail est donné dans le Règlement Particulier de l'Appel d'Offres (RPAO). Cette évaluation se fera de manière purement positive (oui) ou négative (non) avec un minimum acceptable Attribution d'au moins 37/43 (85%) de l'ensemble des critères essentiels pris en compte. Le marché sera attribué au soumissionnaire qui aura proposé l'offre la moins disante, conforme pour l'essentiel aux prescriptions du Dossier d'Appel d'Offres, ayant satisfait à 100% des critères éliminatoires et au moins 37/43 (85%) des critères essentiels. Les soumissionnaires restent engagés par leur offre pendant 60 jours à partir de la date limite fixée pour la Durée de validité des offres remise des offres. Les renseignements complémentaires d'ordre technique peuvent être obtenus auprès de la Marie de Renseignements complémentaires Fait à NJINIKOM, le\_\_\_\_16 FEV 2024 Njinikom. Le Maire de la Commune de NJINIKOM (Autorité Contractante) Copie: DDMINEE DU BOYO DDMINDDEVEL BOYO ARMP; Maître d'Ouvrage П Présidents CPM; Affichage. П Chrono/archive 

# Document N°. 2 GENERAL REGULATIONS OF THE INVITATION TO TENDER

## Table of contents

General Article 1: Scope of the tender
Article 1: Scope of the tender
Article 1: Scope of the tender
Article 3: Fraud and corruption
Article 3: Fraud and corruption
Article 5: Building materials, materials, supplies, equipment and demonstration
Article 5: Building materials, materials, supplies, equipment and Article 6: Qualification of the bidder
Article 6: Qualification of the bidder
Atticle 7. visit
Tender File.
Tender File
Article 8: Content of Tender File
Article 9: Clarifications on Tender File and complaints
Afficie 10. Median
Preparation of Bids
Preparation of Bids Article 11: Tender fees
Article 11: Tender fees  Article 12: Language of bid
Article 12: Language of bid
Article 13: Constituent documents of the bld
Article 14: Amount of bid
Article 15: Currency of bid and payment
Article 17: Bid bond
Article 17: Bid bond
Article 19: Preparatory meeting to the establishment of olds
Article 19: Preparatory meeting to the establishment of olds
Thurst =
Submission of bids
Submission of bids
Article 21: Sealing and marking of bids
Article 22: Date and time-limit for submission of bids
Article 23: Out of time-limit bids
TH
Opening and evaluation of bids
Article 25: Opening of olds
Article 26: Confidential nature of the protect with Contracting Authority
Article 27: Clarifications on the bid and condet
Article 28: Determination of their companies.
Article 29: Qualification of the bidder
Article 30: Correction of errors
Article 31: Conversion into a single currency
Article 31: Conversion into a single currency
Article 33: National preference
Award of the Contract
Award of the Contract.  Article 34: Award
Article 34: Award
cancel a procedure
cancel a procedure
Article 36: Notification of the award of the Contract
Article 37: Signature of the Contract
Article 38: Final bond
13   MUGHEFF DOWN / TWAFUNDONG ROKAT

# GENERAL RULES OF THE INVITATION TO TENDER

### General

Article 1: Scope of the tender

1.1. The Contracting Authority, The Mayor for NJINIKOM Council hereby launches an OPEN National Invitation to Tender N° \_\_\_/ONIT/ NJINIKOM COUNCIL/NCITB/2024 OF \_/\_/2024 for the rural electrification of MUGHEFF DOWN / TWAFUNDONG VILLAGES IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION.

The bidder retained or the preferred bidder must complete the works within the time-limit indicated in the Special Regulations which runs from the date of notification of the Administrative Order.

In this Tender File, the term "day" means a calendar day.

Article 2: Financing

The source of financing of the works forming the subject of this Invitation to Tender shall be specified in the Special Regulations.

Article 3: Fraud and corruption

The Contracting Authority requires of bidders and Contractors the strict respect of rules of professional ethics during the award and execution of Public Contracts. By virtue of this principle:

The following definitions shall be admitted:

Shall be guilty of "corruption" whoever offers, gives, requests or accepts any advantage in view of influencing the action of a Public official during the award or execution of a Contract;

Is involved in "fraudulent manoeuvres" whoever deforms or distorts facts in order to influence the award or execution of a Contract;

"Collusive practices" shall mean any form of agreement between two or among several bidders (whether the Contracting Authority is aware or not) aimed at artificially maintaining the prices of bids at levels not corresponding to those resulting from competition;

"Coercive practices" shall mean any form of harm against persons or their property or threats against them in order to influence their action during the award or execution of a Contract.

Any proposed award shall be rejected if it is proved that the proposed preferred bidder is directly or through an intermediary, guilty of corruption or is involved in fraudulent manoeuvres, collusive or coercive practices for the award of this Contract.

3.2 The Minister Delegate at the Presidency in charge of Public Contracts may, as a precaution, take a decision of exclusion from bidding for a period not exceeding two (2) years against any bidder found guilty of influence peddling, of conflicts of interest, insider trading, fraud, corruption or production of non-genuine documents in the bid, without prejudice to criminal proceedings that may be brought against him

Article 4: Candidates allowed to compete

4.1 If the Invitation to Tender is open, consultation is addressed to all candidates retained after a prequalification procedure.

4.2 Generally, the Invitation to Tender is addressed to all entrepreneurs, subject to the following provisions:

A bidder (including all members of a group of enterprises and all sub-Contractors to the bidder) must be from an eligible country, in accordance with the funding agreement.

A bidder (including all members of a group of enterprises and all sub-Contractors to the bidder) must not be in a situation of conflict of interest, subject to disqualification. A bidder shall be judged to be in a situation of conflict of interest if he:

Is or was associated in the past with an enterprise (or a subsidiary of this enterprise) which provided consultancy services for the conception, preparation of specifications and other documents used within the scope of Contracts awarded for this Invitation to Tender; or

Presents more than one bid within the context of Invitation to Tender, except authorized variants according to article 17, where need be; meanwhile, this does not prevent the participation of sub-Contractors in more than one bid.

The Contracting Authority or Project Owner has financial interests in the capital in a way as to compromise the transparency of the procedures of award of Public Contracts.

- (c) The bidder must not have been excluded from bidding for Public Contracts.
- (d) A Cameroonian Public enterprise may participate in the consultation if it can demonstrate that it is (i) legally and financially autonomous, (ii) managed according to commercial laws and (iii) not under the direct supervisory authority of the Contracting Authority or Project Owner.

5: Building materials, materials, supplies, equipment and authorized services

- 5.1 Building materials, the Contractor's materials, supplies, equipment and services forming the subject of this Contract must originate from countries meeting the criteria of origin defined in the Special Regulations of the Invitation to Tender and all expenditure done within the context of the Contract shall be limited to the said building materials, materials, supplies, equipment and services.
- 5.2 Within the meaning of this 5.1 above, the term "originate" shall designate the place where the goods are extracted, cultivated, produced, manufactured and from where the services originate.

## Article 6: Qualification of bidder

6.1 As an integral part of their bid, bidders must:

submit a power of attorney making the signatory of the bid bound by the bid; and

(b) provide all information (complete or update information included in their request for prequalification which may have changed in the case where the candidates took part in prequalification) requested of bidders in the Special Regulations of the Invitation to Tender, in order to establish their qualification to execute the Contract.

Where necessary, bidders should provide information relating to the following points:

- (i) The production of certified balance sheets and recent turnovers;
- (ii) Access to a line of credit or availability of other financial resources;

(iii) Orders acquired and Contracts awarded;

(iv) Pending litigations;

- (v) Availability of indispensable equipment.
- Bids presented by two or more associated undertakings (joint-Contracting) must satisfy the

The bid must include all the information listed in article 6(1) above. The Special Regulations must indicate the information to be furnished by the group and that to be furnished by each

The bid and the Contract must be signed in a way that is binding on all members of the group; The nature of the group (joint or several) must be specified in the Special Regulations and justified

with the production of a joint venture agreement in due form;

The member of the group designated as the representative will represent all the undertakings vis à vis the Project Owner and Contracting Authority with regard to the execution of the Contract;

In case of joint co-Contracting, the co-Contractors shall share the sums which are paid by the Project Owner into a single account. On the other hand, each undertaking is paid into its own account by the Project Owner where it is joint co-Contracting.

- 6.3 Bidders must equally present sufficiently detailed proposals to demonstrate that they comply with the technical specifications and execution time-limits set in the Special Regulations of the Invitation
- 6.4 Bidders requesting to benefit from the margin of preference must furnish all the necessary information to prove that they satisfy the eligibility criteria set in article 33 of the General Regulations

### Article 7: Visit of works site

- 7.1 The bidder is advised to visit and inspect the site and its environs and obtain by himself and under his own responsibility, all the information which may be necessary for the preparation of the bid and the execution of the works. The related cost of the visit of the site shall be borne by the bidder.
- 7.2 The Project Owner shall authorize the bidder and his employees or agents to enter the premises and the land for the said visit but only on the express condition that the bidder, his employees and agents free the Project Owner, his employees and agents of any responsibility that may ensue and indemnify them if necessary and that they shall remain responsible for any deadly or corporal accident, loss or material damages, costs and fees incurred from this visit.
- 7.3 The Project Owner may organize a visit of the site of the works during the preparatory meeting to establishing the bids mentioned in article 19 of the General Regulations of the Invitation to Tender.

### B. Tender File

# Article 8: Content of Tender File

8.1 The Tender File describes the works forming the subject of the Contract, sets the consultation procedure of Contractors and specifies the terms of the Contract. Besides the addendum (addenda) published in accordance with article 10 of the General Regulations of the Invitation to Tender, it

Document No. 1. The Tender Notice;

Document No. 2. The General Regulations of the Invitation to Tender;

Document No. 3. The Special Regulations of the Invitation to Tender;

Document No. 4. The Special Administrative Conditions;

Document No. 5. The Special Technical Conditions;

Document No. 6. The schedule of unit prices;

Document No. 7. The bill of quantities and estimates;

Document No. 8. The sub details of unit prices;

Document No. 9. Model documents of the Contract:

The execution schedule;

Model of forms presenting the equipment, personnel and references;

Model bidding letter;

Model bid bond;

Model final bond:

Model of bond of start-off advance;

Model of guarantee in replacement of the retention fund;

Model Contract;

Document No. 10. Models to be used by bidders;

Document No. 11. Justifications of preliminary studies; to be filled by the Project Owner or delegated

Document No. 12. List of first grade banking establishments or financial institutions approved by the Minister in charge of Finance authorized to issue bonds for Public Contracts to be inserted by the Contracting Authority.

8.2 The bidder must examine all the regulations, forms, conditions and specifications contained in the Tender File. It is up to him to furnish all the information requested and prepare a bid in compliance with all aspects of the said file.

Article 9: Clarifications on the Tender File and complaints

9.1 Any bidder who wants to obtain clarifications on the Tender File may request them from the Contracting Authority in writing or by electronic mail (fax or e-mail) at the Contracting Authority's address indicated in the Special Regulations of the Invitation to Tender and send a copy to the Project Owner. The Contracting Authority replies in writing to any request for clarification received at least fourteen (14) days prior to the deadline for the submission of bids.

A copy of the Contracting Authority's response, indicating the question posed but not mentioning the author, is addressed to all bidders who bought the Tender File.

- 9.2 Between the Publication of the tender notice including the pre-qualification phase of candidates and the opening of bids, any bidder who feels aggrieved in the Public Contracts award procedure may lodge a complaint to the Minister in charge of Public Contracts.
- 9.3 A copy of the complaint should be addressed to the Contracting Authority and to the body in charge of the Regulation of Public Contracts and the chairperson of the Tenders Board.
- 9.4 The Contracting Authority has five (5) days to react. A copy of the reaction shall be forwarded to MINMAP and the body in charge of the regulation of Public Contracts.

10.1 The Contracting Authority may at any moment, prior to the deadline for the submission of bids and Article 10: Amendment of the Tender File for any reason, be it at his initiative or in reply to a request for clarification formulated by a bidder, amend the Tender File by publishing an addendum.

10.2 Any published addendum shall be an integral part of the Tender File, in accordance with article 8.1 of the General Regulations of the Invitation to Tender and must be communicated in writing or made known by a traceable means to all bidders who bought the Tender File.

In order to give bidders sufficient time to take account of the addendum in the preparation of their bids, the Contracting Authority may postpone as is necessary, the deadline for the submission of bids, in accordance with provisions of article 22 of the General Regulations of the Invitation to

### C Preparation of bids

### Article 11: Tender costs

The candidate shall bear the costs related to the preparation and presentation of his bid and the Contracting Authority and the Project Owner shall in no case be responsible for these costs nor pay for them whatever the evolution or outcome of the Invitation to Tender procedure. Article 12: Language of bid

The bid as well as any correspondence and any document exchanged between the bidder and the Contracting Authority shall be written in English or French. Complementary documents and the forms provided by the bidder may be written in another language on condition that a precise translation into either English or French of the passages concerning the bid is included; in which case for reasons of interpretation, the translation shall be considered to be authentic.

# Article 13: Constituent documents of the bid

13.1 The bid presented by the bidder shall include the documents detailed in the Special Regulations of the Invitation to Tender, duly filled and put together in three volumes:

## Volume 1: Administrative file

### It includes:

all documents attesting that the bidder:

- has subscribed to all declarations provided for by the laws and regulations in force;
- paid all taxes, duties, contributions, fees or deductions of whatever nature;
- · is not winding up or bankrupt;
- · is not the subject of an exclusion order or forfeiture provided for by the law in force;
- The bid bond established in accordance with the provisions of article 17 of the General ii) Regulations of the Invitation to Tender;
- the written confirmation empowering the signatory of the bid to commit the bidder, in accordance with the provisions of article 6(1) the General Regulations of Invitation to Tender.

## Volume 2: Technical bid

# b.1 Information on qualifications

The Special Regulations list the documents to be furnished by bidders to justify the qualification criteria mentioned in article 6(1) of the Special Regulations of the Invitation to Tender.

### b.2 Methodology

The Special Conditions of the Invitation to Tender specifies the constituent elements of the technical bid of the bidders especially: a methodological statement on an analysis of the works and specifying the organization and programme which the bidder intends to put in place or use to execute the works (installations, schedule, Quality Assurance Plan (QAP), sub-Contracting, attestation of visit of the site, where necessary, etc).

b.3 Proof of acceptance of conditions of the Contract

The bidder shall submit duly initialed copies of the administrative and technical documents relating to the Contract, namely:

The Special Administrative Conditions (SAC);

The Special Technical Conditions (STC).

b.4 Commentaries (optional)

A commentary on the technical choices of the project and possible proposals.

### Volume 3: Financial bid

The Special Regulations specify the elements that will help in justifying the cost of the works, namely:

The signed and dated original bid prepared according to the attached model, stamped at the prevailing rate;

The duly filled Unit Price schedule;

The duly filled detailed estimates;

The sub-details of prices and/or breakdown of all-in prices;

The projected schedule of payments, where need be.

In this regard, the bidders will use the documents and models provided in the Tender File, subject to the provisions of article 17(2) of the General Regulations of the Invitation to Tender concerning the other possible forms of guarantees.

If in accordance with the provisions of the Special Regulations of the Invitation to Tender, the bidders present bids for several lots of the same Invitation to Tender, they could indicate rebates offered in case of award of more than one lot.

- Except otherwise stated in the Tender File, the amount of the Contract shall cover all the works Article 14: Bid price described in article 1.1 of the General Regulations of the Invitation to Tender, on the basis of the 14.1 price schedule and the detailed bill of quantities and estimates presented by the bidder.
  - 14.2 The bidder shall fill the unit prices and totals of all items on the schedule and bill of quantities and estimates.
    - Subject to contrary provisions provided for in the Special Regulations and in the Special Administrative Conditions, all dues, taxes and fees payable by the bidder on grounds of the 14.3 Contract or on any other ground, thirty (30) days prior to the submission of the bids, shall be included in the prices and in the total amount of the bid presented by the bidder.
    - 14.4 If a price revision/updating clause is provided for in the Contract, the date of establishment of the initial price, as well as the price revision/updating conditions for the said price must be specified. This is with the understanding that any Contract of duration less than one (1) year shall not be subject to price revision.
    - 14.5 All unit prices must be justified by sub-details established in accordance with the structure proposed in document 8 of the Tender File.

# Article 15: Currency of bid and payment

15.1 In case of international invitations to tender, the currencies of the bid shall follow the provisions of either Option A or Option B - FCFA, the applicable option being that retained in the Special Regulations of the Invitation to Tender.

15.2 Option A: The amount of the bid shall be entirely made in the national currency. The amount of the bid, unit prices of the price schedule and the prices of the bill of quantities and estimates are completely made in CFA francs in the following manner:

Prices shall be entirely drawn in the national currency. The bidder who intends to commit expenditures in other currencies for the execution of the works shall indicate in the annex to the bid the percentage(s) of the amount of the bid necessary to cover the needs in foreign currencies, without exceeding the maximum of the three currencies of member countries of the funding institution of the Contract.

The exchange rates used by the bidder to convert his bid into the national currency shall be specified by the bidder in an annex to the bid in compliance with the specifications of the Special Regulations. These rates shall be applied for any payment within the framework of the Contract so that the retained bidder does not bear any change in the exchange rate.

15.3 Option B: The amount of the bid shall be directly made in the national and foreign currency at the rates fixed in the Special Regulations.

The bidder shall draw the unit prices of the price schedule and the prices of the bill of quantities and estimates in the following manner:

The prices of inputs necessary for the works which the bidder intends to procure in the Contracting Authority's country shall be in currency of the Contracting Authority's country specified in the Special Regulations and called "national currency";

The prices of inputs necessary for works which bidder intends to procure out of the Contracting Authority's country shall be in the currency of the country of origin of the bidder or of the currency of an eligible member country widely used in international trade.

- 15.4 The Contracting Authority may request the bidders to explain the needs in national and foreign currencies and to justify that the amounts included in the unit and total prices and indicated in annex to the bids are reasonable; to this end, a detailed statement of their needs in foreign currencies shall be furnished by the bidder.
- 15.5 During the execution of the works, most of the foreign currency to be paid as part of Contract may be revised by mutual agreement between the Contracting Authority and the entrepreneur in a Contract.

# Article 16: Validity of bids

- 16.1 Bids must remain valid during the period stated in the Special Regulations from the date of submission of the bids fixed by the Contracting Authority, in application of article 22 of the Special Regulations. A not being in compliance.
- 16.2 Under exceptional circumstances, the Contracting Authority may seek the approval of bidders to extend the validity time-limit. The request and the responses that will be given shall be in writing (or by fax). The validity of the bid bond provided for in article 17 of the General Regulations shall equally be extended for a corresponding duration. A bidder may refuse to extend the validity of his bid without

losing his bid bond. A bidder who consents to an extension shall not be asked to modify his bid nor shall he be authorized to do so.

16.3 Where the Contract does not include a price revision clause and that the period of validity of bids is extended by more than sixty (60) days, the amounts payable to the bidder retained shall be updated by application of the related formula featuring in the request for extension that the Contracting Authority

The updating period shall run from the date of overrun of sixty (60) days to the date of notification of the Contract or the Administrative Order for start of execution of works by the retained bidder, as specified in the Special Administrative Conditions. The effect of updating shall not be taken into account for purposes of evaluation of bids.

- In application of article 13 of the General Regulations, the bidder shall furnish a bid bond of the Article 17: Bid bond amount specified in the Special Regulations and which bid bond shall be a full part of his bid. 17.1
- 17.2 The bid bond must conform to the model presented in the Tender File; other models may be authorized subject to the prior approval of the Contracting Authority. The bid bond will remain valid for thirty (30) days beyond the original date set for the validity of bids or any other validity time-limit requested by the Contracting Authority and accepted by the bidder, in accordance with the provisions of article 16 (2) of the General Regulations.
- 17.3 Any bid without an acceptable bid bond shall be rejected by the Tenders Board as not in conformity. The bid bond of associated enterprises must be established in the name of the group submitting the bid and mention each member of the associated grouping.
- The bid bonds of bidders who are not retained shall be returned within fifteen (15) days after 17.4 Publication of the award result.
- The bid bond of the successful bidder shall be released as soon as the latter would have signed the 17.5 Contract and furnished the required final bond.
- 17.6 The bid bond may be seized:

if the bidder withdraws his bid during the period of validity;

- (b) if the retained bidder: i) fails in his obligation to register the Contract in application of article 38 of the General Regulations;

fails in his obligation to furnish the required final bond in application of article 38 of the General Regulations;

refuses to receive notification of the Administrative Order to commence execution.

- 18.1 Where the works can be executed within variable deadlines, the Special Regulations shall specify Article 18: Varying proposals of bidders these deadlines and shall indicate the method retained for the evaluation of the completion deadline proposed by the bidder within the specified deadlines. Bids that propose deadlines beyond those specified shall be considered as not being in conformity.
  - 18.2 Except in the case mentioned in article 18(3), bidders wishing to offer technical variants must first assess the basic solution of the Contracting Authority as described in the Tender File and furnish in addition

all the information which the Contracting Authority needs for a complete evaluation of the proposed variant, including the plans, calculations, technical specifications, sub-details of prices and proposed construction methods and all other useful information. If necessary, the Contracting Authority will examine only the technical variants of the bidder whose bid is in compliance with the basic solution has been evaluated as the lowest bid.

18.3 When according to the Special Regulations the bidders are authorized to directly submit the technical variants for certain parts of the works, these parts of the works must be described in the technical specifications. Such variants shall be evaluated on their own merit in accordance with the provisions of

# Article 19: Preparatory meeting to the establishment of bids

- Except otherwise stipulated in the Special Regulations, a bidder may be invited to take part in a preparatory meeting which will hold at the date and place indicated in the Special Regulations.
- 19.2 The subject of the preparatory meeting shall be to furnish clarifications and answer any questions which
- As much as possible, the bidder is requested to submit any question in a way as to reach the 19.3 Contracting Authority at least one week before the meeting The Contracting Authority may not reply to questions received too late. In this case, the questions and answers shall be transmitted according to the methods set in article 19(4) NJINIKOM.
- The minutes of the meeting, including the text of the questions asked and the replies given, including 19.4 questions prepared after the meeting, shall be forwarded immediately to everyone who bought the Tender File. Any modification of documents of the Tender File listed in article 8 of the General Regulations which may prove to be necessary at the end of the preparatory meeting shall be done by the Contracting Authority by publishing an addendum in accordance with the provisions of article 10 of the General Regulations and not through the minutes of the preparatory meeting.
- 19.5 The fact that a bidder does not attend a preparatory meeting for the establishment of bids shall not be a

# Article 20: Form and signature of bid

- 20.1 The bidder shall prepare an original of the constituent documents described in article 13 of the General Regulations in a volume clearly indicated "ORIGINAL". In addition, the bidder shall submit the number required in the General Regulations, bearing "COPY". In case of discrepancy, the original
- 20.2 The original and copies of the bid must be typed or written in indelible ink (photocopies shall be accepted in the case of copies) and shall be signed by the person(s) duly empowered to sign on behalf of the bidder, in accordance with article 6(1a) or 6(2c) of the General Regulations, as the case may be. All the pages of the bid containing alterations or changes must be initialed by the signatory (ies) of the
- 20.3 The bid shall be bear no modification, suppression or alteration unless such corrections are initialed by

# D. SUBMISSION OF BIDS

# Article 21: Sealing and marking of bids

- 21.1 The bidder shall seal the original and each copy of the bid in separate envelopes (internal envelopes) by marking on these envelopes "ORIGINAL" and "COPY", as the case may be. The envelopes shall then be placed in another envelope which will equally be sealed but which will not give any indication regarding the identity of the bidder.
- 21.2 The external and internal envelopes:
- a) should be addressed to the Contracting Authority at the address indicated in the Special Regulations:
  - b) should bear the name and identification number of the project as indicated in the Special
  - "TO BE OPENED ONLY DURING THE BID-OPENING SESSION" as specified in the Special Regulations and bear the inscription. Regulations.
- 21.3 The internal envelopes should equally carry the name and address of the bidder in a way as to enable the Contracting Authority return the sealed bid if it is late in accordance with article 23 and 24 of the General Regulations.
- 21.4 If the external envelope is not sealed and marked as indicated in paragraphs 21(1) and 21(2) above, the Contracting Authority shall not be responsible if the bid is misplaced or open prematurely.

- 22.1 The bids must be received by the Contracting Authority at the address specified in article 21(2) of the Special Regulations not later than the date and time stated in the Special Regulations.
- 22.2 The Contracting Authority may, at his discretion, postpone the deadline set for the submission of the bids by publishing an addendum in accordance with the provisions of article 10 of the General Regulations. In this case, all the rights and obligations of the Contracting Authority and bidders previously governed by the initial date will henceforth be governed by the new date.

### Article 23: Late bids

Any bid received by the Contracting Authority beyond the deadline for the submission of bids in accordance with article 22 of the General Regulations shall be declared late and consequently rejected.

# Article 24: Modification, substitution and withdrawal of bids

- 24.1 A bidder may modify or withdraw his bid after submitting it, on condition that the written notification of the modification or withdrawal is received by the Contracting Authority prior to the end of the timelimit prescribed for the submission of the bids. The said notification must be signed by an authorized representative in application of article 20(2) of the General Regulations. The modification or the corresponding replacement bid must be attached to the written notification. As the case may be, the envelopes must bear the inscription "WITHDRAWAL", and "REPLACEMENT BID" or "MODIFICATION".
- 24.2 Notification of modification, replacement or withdrawal of the bid by the bidder should be prepared, sealed, marked and forwarded in accordance with the provisions of article 21 of the General Regulations. Withdrawal may equally be notified by telex but should in this case be confirmed by a duly signed written notification whose date, post mark being authentic, shall not be posterior to the time-limit set for the submission of bids.
- 24.3 In application of article 24(1), bids being requested to be withdrawn by bidders shall be returned to them unopen.

24.4 No bid may be withdrawn during the interval between the submission of bids and the expiry of the validity of bids specified by the model tender. The withdrawal of a bid by a bidder during this interval may lead to the confiscation of the bid bond in accordance with the provisions of article 17(6) of the General Regulations.

# E. Opening of envelopes and evaluation of bids

Article 25: Opening of envelopes and petitions

- 25.1 The NJINIKOM Council Internal Tenders Board shall open the envelopes in single or double phases and in the presence of the representatives of bidders who wish to attend at the date, time and address specified in the Special Regulations. Representatives of bidders shall sign a register attesting to their
- 25.2 Firstly, envelopes marked "withdrawal" shall be open and the contents announced to the hearing of everyone, while the envelope containing the corresponding bid shall be returned to the bidder un open. Withdrawal shall be allowed only if the corresponding notification contains a valid empowerment of the signatory to request this withdrawal and if this notification is read to the hearing of everyone. Then the envelopes marked "Replacement bid" are open and announced to the hearing of everyone and the new corresponding bid substituted for the preceding one which will be sent to the bidder concerned unopen. The replacement of the bid shall only be allowed if the corresponding notification contains a valid empowerment of the signatory requesting the replacement and read to the hearing of everyone. Lastly, the envelopes marked "modification" shall be open and their contents read to the hearing of everyone with the corresponding bid. The modification of the bid shall only be allowed if the corresponding notification contains a valid empowerment of the signatory requesting the modification and read to the hearing of everyone. Only bids which were open and announced to the hearing of everyone during the opening of bids shall then be evaluated.
- 25.3 All envelopes shall be open successively and the name of the bidder announced aloud as well as the possible modification mentioned, the price offered, including any rebates [in case of opening of financial bids] and any variant, where necessary, the existence of a guarantee of the bid if it is required and any other details which the Contracting Authority deems useful to be mentioned. Only rebates and variants of bids announced to the hearing of everyone during the opening of bids shall be submitted for
- 25.4 Bids (and modifications received in accordance with the provisions of article 24 of the General Regulations) which were not open and read to the hearing of everyone during the bid- opening session for whatever reason, shall not be submitted for evaluation.
- 25.5 Bid- opening minutes are recorded on the spot mentioning the admissibility of bids, their administrative regularity, prices, rebates and time-limits as well as the composition of the Evaluation sub-committee. A copy of the said minutes to which is attached the attendance sheet is handed over to all the participants at the end of the session.
- 25.6 At the end of each bid- opening session, the chairperson of the Tenders Board immediately hands over to the focal point designated by the body in charge of regulation of Public Contract an initialed copy of
- 25.7 In case of petition as provided for by the Public Contracts Code, it should be addressed to the Minister Delegate in charge of Public Contracts with a copies to the body in charge of the regulation of Public Contracts, the head of structure to which is attached the Tenders Board concerned.

It must reach within a maximum deadline of three (3) working days after the opening of bids in the form of a letter to which is obligatorily attached a sheet of the petition form duly signed by the petitioner and possibly by the chairperson of the Tenders Board.

The Independent Observer attaches to his report the sheet that was handed to him, including any related commentaries or observations.

- 26.1 No information relating to the examination, clarification, evaluation and comparison of bids and verification of the qualification of the bidders and the recommendation for the award shall be given to bidders or to any person not concerned with the said procedure as long as the preferred bidder has not been made Public, subject to the disqualification of the bid of the bidder and suspension of the authors from all activities in the domain of Public Contracts.
- 26.2 Any attempt by a bidder to influence the Tenders Board or the Evaluation sub-committee of bids or the Contracting Authority in its award decision may lead to the rejection of his bid.
- 26.3 Notwithstanding the provisions of paragraph 26.2 above, between the opening of bids and the award of the Contract, if a bidder wishes to enter into contact with the Contracting Authority for reasons having to with his bid may do so in writing.

Article 27: Clarifications on the bids and contact with the Contracting Authority

- 27.1 To ease the examination, evaluation and comparison of bids, the Tenders Board may, if it so desires, request any bidder to give clarifications on his bid. This request for clarification and the response thereto are formulated in writing but no change on the amount or content of the bid is sought, offered or authorized, except it is necessary to confirm the correction of calculation errors discovered by the Evaluation Sub-committee during the evaluation in accordance with the provisions of article 30 of the General Regulations.
- 27.2 Subject to the provisions of paragraph 1 above, bidders shall not contact members of the Tenders Board and the Evaluation Sub-committee for questions related to their bids, between the opening of envelopes and the award of the Contract.

- 28.1 The Evaluation sub-committee shall carry out a detailed examination of bids to determine if they are complete, if the required guarantees are furnished, if the documents were correctly signed and if generally the bids are in proper order.
- 28.2 The Evaluation sub-committee shall determine if the bid is essentially in compliance with the conditions fixed in the Tender File based on the content without recourse to external elements of proof.
- 28.3 A bid that complies with the Tender File shall essentially be a bid that respects all the terms, conditions and specifications of the Tender File, without substantial divergence or reservation. A substantial divergence or reservation is that:

which substantially limits the scope, quality or realization of the works; which substantially limits, contrary to the Tender File, the rights of the Contracting Authority or his obligations in relation to the Contract; Whose correction would unjustly affect the competitiveness of the other bidders who

presented bids that essentially complied with the Tender File.

- 28.4 If a bid is essentially not in compliance, it shall be rejected by the competent Tenders Board and shall
- 28.5 The Contracting Authority reserves the right to accept or reject any modification, divergence or reservation. Modifications, divergences, variants and other factors which are beyond the requirements of the Tender File shall not be considered during the evaluation of bids.

# Article 29: Qualification of the bidder

The Evaluation sub-committee shall ensure that the successful bidder retained for having submitted a bid substantially in compliance with the provisions of the Tender File, fulfil the qualification criteria stipulated in article 6 of the Special Regulations. It is essential to avoid any arbitrariness in

# Article 30: Correction of errors

30.1 The Evaluation sub-committee shall verify bids considered essentially in compliance with the Tender File to correct the possible calculation errors. The Evaluation sub-committee shall correct the errors in

where there is an incoherence between the unit price and the total obtained by multiplying the unit price by the quantity, the unit price being authentic, the total price shall be corrected, unless the Evaluation sub-committee judges that it is a gross error of decimal point in the unit price in which case the total price as presented shall be authentic and the unit price corrected.

If the total obtained by addition or subtraction of the totals is not exact, the sub totals shall be

Where there is a difference between the price indicated in letters and in figures, the amount in letters shall be considered authentic, unless the amount is linked to an arithmetical error confirmed by the sub-detail of the said price, in which case the amount in figures shall prevail subject to paragraphs (a) and (b) above.

- 30.2 The amount featuring in the bid shall be corrected by the Evaluation sub-committee, in accordance with the error correction procedure above and with confirmation by the bidder, the said amount shall
- 30.3 If the bidder who presented the bid evaluated as the lowest refuses the correction thus carried out, his

# Article 31: Conversion into a single currency

- 31.1 To facilitate the evaluation and comparison of bids, the Evaluation sub-committee shall convert the prices of bids expressed in various currencies into those in which the bid is payable in CFA francs.
- 31.2 The conversion shall be done using the selling rate fixed by the Bank of Central African States (BEAC) under the conditions defined by the Special Regulations.

# Article 32: Evaluation and comparison of financial bids

- 32.1 Only bids considered as being in compliance, as per the provisions of article 28 of the General Regulations, shall be evaluated and compared by the Evaluation sub-committee.
- 32.2 By evaluating the bids, the Evaluation Sub-committee shall determine for each bid the evaluated amount of the bid by rectifying the amount as follows:

By correcting any possible error in accordance with the provisions of article 30.2 of the General

By excluding projected sums and where necessary provisions for unforeseen occurrences featuring in the bill of quantities and estimates but by adding the amount of works done under State supervision where they are cost in a competitive manner as specified in the Special Regulations.

By converting into a single currency the amount resulting from the rectifications (a) and (b) above, in accordance with the provisions of article 31(2) of the General Regulations;

By appropriately adjusting any other modification, divergence or quantifiable reservation on

By taking into consideration the various execution time-limits proposed by the bidders, if they are

If need be, in accordance with the provisions of article 13(2) of the General Regulations and the Special Regulations by applying the rebates offered by the bidder for the award of more than one lot, if this Invitation to Tender is launched simultaneously for several lots.

If need be, in accordance with the provisions of article 18(3) of the Special Regulations and the Technical Specifications, the proposed technical variants, if they are permitted, shall be evaluated on their own merit and independently of the fact that the bidder offered or not a price for the technical solution specified by the Contracting Authority in the Special Regulations.

32.3 The estimated effect of price revision formulae featuring in the GAC and SAC applied during the period of execution of the Contract shall not be considered during the evaluation of bids.

32.4 If the bid judged the lowest bid is considered abnormally low or strongly unbalanced in relation to the estimates of the Project Owner for the works to be executed in this Contract, the Tenders Board may, from the sub-details of prices furnished by the bidder for any element or all the elements of the bill of quantities and estimates, verify if these prices are compatible with the construction methods and proposed calendar. In the case where the justifications presented by the bidder are not satisfactory, the Contracting Authority may reject the bid after the technical opinion of the Public Contracts Regulatory Agency.

National Contractors shall benefit from a margin of national preference during the evaluation of bids as provided for in the Public Contracts Code.

- The Contracting Authority shall award the Contract to the bidder whose bid was judged essentially in Article 34: Award compliance with the Tender File and who has the required technical and financial capacities to execute the Contract satisfactorily and whose bid was evaluated as the lowest by including, where necessary, proposed rebates
- If, according to article 13(2) of the General Regulations, the Invitation to Tender comprises several lots, the lowest bid shall be determined by evaluating this Contract with other lots to be awarded concurrently, by taking into account the rebates offered by the bidders in the case of more than one lot.
- Any award of Contract shall be made to the bidder fulfilling the technical and financial capacities required resulting from the evaluation criteria and presenting the bid evaluated as the lowest. 34.3

Article 35: The right by the Contracting Authority to declare an Invitation to Tender unsuccessful or

The Contracting Authority reserves the right to cancel a procedure of Invitation to Tender after the authorization of the Minister Delegate at the Presidency in charge of Public Contracts where the bids have been open or to declare an Invitation to Tender unsuccessful after the advice of the competent Tenders Board, without any claims being entertained.

# Article 36: Notification of award of the Contract

27 | MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECTS 2024

Before the expiry of the validity of the bids set in the Special Regulations, the Contracting Authority shall notify the preferred bidder by telecopy confirmed by registered mail or by any other means that his bid was retained. This letter will indicate the amount the Project Owner will pay the Contractor to execute the works and the execution time-limit.

# Article 37: Publication of results of award and petitions

- 37.1 The Contracting Authority shall communicate to any bidder or administration concerned, upon request addressed to it within a maximum deadline of five (5) days after Publication of the award results, the Independent Observer's report as well as the minutes of the award session of the related Contract to which shall be attached the evaluation
- 37.2 The Contracting Authority is bound to communicate the reasons for the rejection of bids of the bidders concerned
- 37.3 After Publication of the award results, bids that are not withdrawn within fifteen (15) days shall be destroyed, without any claims for compensation being entertained. Only the copy destined for the body in charge of regulation shall be kept.
- 37.4 In case of petition, it should be addressed to the Public Contracts Authority, with copies to the body in charge of the regulation of Public Contracts, the Contracting Authority and the chairperson of the Tenders Board concerned. It must take place within a maximum deadline of five (5) working days after the Publication of the results.

# Article 38: Signing of the Contract

- 38.1 After Publication of the results, the draft Contract subscribed by the successful bidder is submitted to the Tenders Board for examination and where applicable, to the Minister in charge of Public Contracts for prior endorsement.
- 38.2 The Contracting Authority has a deadline of seven (7) days to sign the Contract from the date of reception of the draft Contract examined by the competent Tenders Board and subscribed by the successful bidder and where applicable, the endorsement of the Minister in charge of Public Contracts.
- 38.3 The Contract must be notified to the successful bidder within five (5) days of its date of signature.

### Article 39: Final Bond

- 39.1 Within twenty (20) days of the notification by the Contracting Authority, the Contractor shall furnish the Project Owner with a final bond, to guarantee the complete execution of the works.
- 39.2 The bond whose rate varies between 2 and 5 percent of the amount of the Contract inclusive of all taxes, may be replaced by a guarantee from a banking establishment approved according to the instruments in force with the Project
- 39.3 Small and medium-sized enterprises (SME) constituted of national capital and managed by nationals may, in lieu of the guarantee, provide a statutory lien or a bond issued by a banking establishment or first rate financial institution
- Failure to produce the final bond within the prescribed time limit shall likely cause the termination of the Contract under the terms laid down in the General Administrative Conditions.

# Document N°. 3 SPECIAL REGULATIONS OF THE INVITATION TO TENDER

# Special regulations of the Invitation to Tender

References of the General regulations	General
	Definition of works: Rural electrification of MUGHEFF DOWN / TWAFUNDONG VILLAGES in NJINIKON Municipality, BOYO Division.
	Name and address of the Contracting Authority: The LORD MAYOR NJINIKOM COUNCIL Reference of Invitation to Tender: N° 11/12/ONIT/MINDDEVEL/NC/NCITB/PIB/2024 OF
	/_/2024 Execution deadline: ninety (90) days
	Source of financing Works which form the subject of this Invitation to Tender shall be financed by the 2024 Public Investment Budget of the Ministry of water resources and energy.
	List of pre-qualified candidates, not applicable
1	Origin of building materials, equipment, materials, supplies and equipment: The materials will generally be from natural sources in Cameroon.

### 6.1 Evaluation criteria

The bids shall be evaluated according to the main criteria as follows:

### Eliminatory criteria

Absence or non-conformity of a document in the administrative file;

Deadline for delivery higher than prescribed;

False declaration or falsified documents;

Absence or insufficient bid bond;

A bid with the external envelope carrying a sign or mark leading to the identification of the bidder;

Change of quantity or unit;

Non respect of 37/43 (85%) of essential criteria;

Non completion of any project in previous years in the Country and suspended by MINMAP.

### Essential criteria

General presentation of the Tender Files;

Financial capacity;

References of the company in similar achievements;

Quality of the personnel;

Technical organization of the works;

Safety measures on the site;

Logistics:

Attestation and report of site visit;

Special Technical Clauses initialed in all the pages and signed at the last page;

Special Administrative Clauses completed and initialed in all the pages and signed at the last page.

The criteria relating to the qualification of candidates could be indicative on the following:

The essential criteria are subjected to minima whose detail is given in the Special Tender Regulation (RPAO).

This evaluation will be done in a purely positive way (yes) or negative (no) with an acceptable minimum from at least 37/43 (85%) of the essential criteria taken in account.

The Contract will be awarded to the bidder who would have proposed the offer with the lowest amount, in conformity with the regulations of the Tender Documents and having satisfied to 100% of the eliminatory criteria and at least 37/43 (85%) of the essential criteria.

The offer like any correspondence and all documents concerning the tender, exchanged between the renderer ARTICLE 6 : Language of the bids: and the Project Owner will be written in French or English. The complementary documents and the printed papers form provided by the Bidder can be written in another language in condition of being accompanied by a precise translation in French or English; in which case and for purposes of interpretation of the offer, the translation will be taken.

The bids prepared in English or French and in seven (07) copies with one (01) original and six (06) copies PRESENTATION OF THE TENDER. marked thus, shall be presented in three (03) volumes as follows:

- Administrative Documents A)
- **Technical Documents** B)

Financial Documents

5.1

Each bidder shall seal these three (03) envelopes (A, B and C) in one common envelope on which shall be written.

/ONIT/NJINIKOM COUNCIL/NCITB/2024 OF \_/\_/2024 FOR THE RURAL ELECTRIFICATION OF MUGHEFF DOWN / TWAFUNDONG VILLAGES << OPEN NATIONAL INVITATION TO TENDER N° IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION. >>

"TO BE OPENED ONLY DURING THE BID-OPENING SESSION"

The external envelope should not carry any mark or sign that can lead to the identification of the bidder. N.B:

Internal envelopes 8.2

Three (03) internal envelopes must be sealed in an external envelope.

<ENVELOPE A: ADMINISTRATIVE DOCUMENTS>> and shall contain the administrative documents of the enterprise. These documents shall be original or copies certified by competent authorities not more than three months.

# ADMINISTRATIVE DOCUMENTS.

	DERDMINMAPRIPTION
DOCUMENT	
N°	Certified Copy of the Business Registration, not more than three months old.  Certified Copy of the Business Registration, not more than three months old.
A.2	Declaration of intention to tender start-
A.3	Declaration of intention to tender stamped with Court of 1st instance or the Chamber Commerce Certificate of non-bankruptcy established by the Court of 1st instance or the Chamber Commerce Industry and Trade of the place of residence of the bidder, not more than three (03) months.
A.4	Attestation of bank account of the bidder, issued by a first rate-bank approved by the Ministry in charge of Finance or by a foreign bank the first order not more than three months.
A.5	Purchase receipt of Tender File issued by NJINIKOM COUNCIL treasury  Purchase receipt of Tender File issued by NJINIKOM COUNCIL treasury
A.6	Purchase receipt of Tender File issued by NJINIKOM COUNCIL treasury  A bid bond of 400 000 CFA (Four hundred thousand francs CFA) issued by a first rate-bank approved by the Ministry in charge of Finance in conformity with COBAC conditions  N.B. 440 000 CFA for TWAFUNDONG  An attestation of non-exclusion from Public Contracts issued by the Public Contract Regulatory
A.7	Board (ARMP) Suppose Fund stating that the bidder has met all his
A.8	An Attestation of the National Social Insurance Fund stating obligations vis a vis the Fund; the attestation valid within the given time.  A valid Certificate of imposition certified by the chief of center for taxation
A.9	A valid Certificate of imposition certified by the enter

A.10	Business License (photocopy certified by the chief of center of Taxes, not more than three months)
A.11	Certified Copy of a valid taxpayers and delivery
A.12	Certified Copy of a valid taxpayers card, delivered by the chief of center of Taxes.  A Clearance Certificate signed by the chief of Centre of Taxes that the bidder has met all the than three months old.  Plan and otherwise.
A.13	Plan and attestation of the state of the sta
A.14	Plan and attestation of location of the Company signed by the Chief of Taxation  Power of attorney if necessary
A.15	Attestation of non-Bankruptcy

The absence or the nonconformity of the one of these documents will result to the elimination of the offer The second Internal Envelope shall be labeled << ENVELOPE B: TECHNICAL DOCUMENT>> and shall contain the following:

General presentation of the Tender document  - Presence of intermediary separation		
		100
1 - See are numbered	1111111	
- Document is spirally bound		
- VISA and Signed converse.		
- Visa and Signed copy of Particular Administration		
Visa and Signed copy of Special Technical Conditions     Visa and Signed copy of Particular Administrative Conditions (Jobbing Order)     Personnel of the Enterprise (Engineers).		
Detailed technical note on the price [Engineer(s), Foreman and Co-ordinator]	111111111111111111111111111111111111111	
experience in the domain of electricity of the personnel, their level of education as well as their		
Engineer:		W 1
More than 05 years experience		
More than 03 years experience		
Less than 2 years experience		1 145 -
Attestation of availability of Engineer		
Higher technician:		
More than 5 years experience	1 -	
5 years experience	E 14	
Less than 2 years experience		
Attestation of availability and a series of a series o		
Attestation of availability of Higher Technician  Technician:	- 1	
More than 5 years experience	- 6	
Less than 5 years experience		
attestation of availability of Technician		
of the conject of the control	- 1	
Certified true copies of the certificates of personnel + attestation of presentation of originals Curriculum Vitae of personnel involved in the project		
Project	- 1	

• References of the Enterprise in the domain of Electricity.  ertified true copies of the Jobbing Order and the minutes of the Final or Provisional cceptance of electrical energy supply project(s) realized by the Enterprise, if any  More than Two Final or Provisional Acceptance Reports Two Final or Provisional Acceptance Reports One Final or Provisional Acceptance Report Certified true copies of Jobbing Orders or Contracts of Electrification Projects realized by the Enterprise: More than two (02) projects At least two (02) projects One (01) project only Have you constructed a medium voltage three-phase line (proof- PV+Tech acceptance)?  More than Two kilometres Two kilometres	
- Less than One kilometre - Have you constructed a medium voltage single-phase line (proof-PV+Tech acceptance)? - More than Three kilometres - Three kilometres - More than Two kilometres - Less than or equal to Two kilometres	
<ul> <li>Equipment of the Enterprise         <ul> <li>Certified true copies of vehicle documents signed not more than 3 months</li> <li>List of key equipment and proof of ownership or hired (yard truck, electric drill, engine saw, GPS device, climbers, spades, dig axes, drill, service cord, set of screws drivers, pegging markers, fork, signalling cones, pliers.)</li> <li>Methodology for executing the works.</li> <li>Detailed technical description of the works to be executed, in conformity with execution plans</li> <li>Organizational chart of the project</li> <li>Manpower deployment schedule</li> <li>Execution timeframe with a maximum deadline of four (04) months</li> <li>Acceptable planning</li> <li>Genuine Report of Worksite</li> <li>Attestation of Site Visit</li> </ul> </li> </ul>	
■ Capacity to Pre-finance.  □ By 100% personal financial means (bank statement)	

# ENVELOPE C- FINANCIAL FILE

No.	DESIGNATION.
C1	A submission letter, signed, dated and stamped.(see ANNEX 3)  A submission letter, signed, dated and stamped.(see ANNEX 3)
C2	Completed and signed frame work of unit prices.  Signed Bills of quantities and cost estimates indicating the total amount without taxes (HT) and
	Signed Bills of quantities and cost estimates indicating the
with tax	with taxes (TTC)
04	Sub details of unit prices
C4	Sub dotains is seed in the Tender Documents, su

- The bidders will use for this purpose the documents and models envisaged in the Tender Documents, subject to the provisions of Article 19.2 of the RGAO concerning the other possible forms of bid bond.
- The various parts of the same file must be separated with colour guides from as well in the original as in the copies, so as to facilitate its examination

### Supply price

# ARTICLE 8: Currency of payment

This National Invitation to Tender is awarded on total and Contractual price, inclusive of all taxes, firm and non-revisable for the whole of the works and the equipment defined in the present Invitation to Tender.

The corresponding amount will be calculated inclusive of all taxes and the prices will be obligatorily expressed in francs CFA.

The unit schedule price expressed out in figures and letters and in seven (07) copies will be joined to the offer. In the event of error between the prices in figures and letters, the latter will precede and be used as a basis of calculation of the amount of the offer.

The establishment of the prices will be done on the basis of economic condition into force in Republic of Cameroon at the handover date of the offers.

# ARTICLE 9: Transport and delivery

The materials for work must be protected during transportation through packaging whether by air, railway or road according as the case may be. The conditions of storage must be of tropical type.

# ARTICLE 10: Guarantee and retention guarantee

### 10.1 Provisional guarantee

The amount of the provisional guarantee or guarantee of tender is fixed at 2 000 000 CFA (Two Million francs CFA). FOR MUGHEFF DOWN,

# N.B. 2,200,000 FCFA FOR TWAFUNDONG

The time of validity of this guarantee is sixty (60) days as from the date of depositing of the offers.

### 10.2 Final Bond

The final Bond is fixed at two percent (2%) of the initial amount of the services envisaged in the country.

It could be replaced by a guarantee personal and interdependent of a banking house approved by the Ministry of Finances following COBAC conditions.

It will have to be made up in the twenty (20) days following the notification of the signature of the Contract in a bank approved by the Minister in charge of Finances. 10.3 Guarantee Retention

Guarantee Retention of ten percent (10%) will be operated on amount including all taxes of the Contract. The corresponding sum will be paid or the released guarantee, with the final acceptance of work.

# ARTICLE 11: Period of validity of the offers

The bidder will remain committed to his offer for sixty (60) days as from the handover date of the offers.

If at the end of this period, the Contract were not notified to him, the bidder will be able, either to cancel his offer, or to ask for a new negotiation of the unit prices.

# ARTICLE 12: A number of copies of the offer which must be filled and sent

The tender, as all the parts accompanying it will have to be given in seven (07) copies, including one (01) original and six (06) copies. The bidder will present his dossier inside a sealed outer jacket being marked: << OPENED NATIONAL INVITATION TO TENDER N°\_

### \_/ONIT/NJINIKOM COUNCIL/NCITB/2024 \_/\_/2024 FOR THE RURAL ELECTRIFICATION OF MUGHEFF DOWN / TWAFUNDONG VILLAGES IN NJINIKOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WEST REGION. >>

# TO BE OPENED ONLY DURING THE OPENING SESSION»

ARTICLE 13: Date and latest time of deposit of offers The offers will have to arrive under closed fold and seal latest \_\_/\_/2024 at 12:00AM, by mail registered with acknowledgement of delivery or by deposit against receipt to the following address:

# THE SERVICE OF THE CONTRACTING AUTHORITY, THE LORD MAYOR NJINIKOM COUNCIL

Beyond this time no offer will be received nor accepted.

The opening of the folds will be carried out in the conference room of the NJINIKOM Council ARTICLE 14: Opening of the tenders Internal Tenders' Board on \_\_/\_/2024 as from 11:00AM, by the Council Tender Board sitting in the presence of the duly elected bidders or their representatives and having a good knowledge of the file.

# AWARD OF THE CONTRACT

The Tenders Board will propose to the Contracting Authority to award the Contract to the bidder ARTICLE 15: Award of the Contract who will have presented the offer with the lowest offer, essentially conforming to the regulations the Tender File, having satisfied to 100% of all the eliminatory criteria and at least 37/43 (85%) of the essential criteria taken into account.

The decision carrying attribution of the Contract will be published by way of press release or any other means of Publication of use in the Administration.

If the Contract passed on the basis of technical alternative suggested by the bidder, the Contracting Authority reserves the right to introduce all the provisions there allowing him to guarantee itself against the real overrun costs of the alternative compared to his estimate of origin. In the absence of these last precise details, any additional charge due to an alternative will be inadmissible.

To this end, it is specified that a bidder cannot claim to be compensated, if it is not taken action on

The Contracting Authority reserves the right not to take action on an Invitation to Tender, if it did not obtain a proposal which appears acceptable to him.

# ARTICLE 16: COMMENCEMENT OF WORK:

Before the commencement of work the Contractor must be installed on the site by the following:

- ❖ The Authorizing Officer or his representative, THE LORD MAYOR NJINIKOM COUNCIL;
- The Contract Engineer, Divisional Delegate for MINEE Boyo or his representative;
- The Contract Manager SG
- ❖ The COUNCIL DEVELOPMENT OFFICER (CDO)
- The DD MINMAP for Boyo or his representative;
- ❖ Representative of ENEO NW;
- The Divisional Delegate of MINEPAT for Boyo or his representative;
- The Project Manager, The Divisional chief of service for energy MINEE Boyo
- The Representative of the Beneficiary Community

# Document N°. 4 SPECIAL ADMINISTRATIVE CONDITIONS (SAC)

#### Table of contents

#### Chapter I: General

- Subject of the Contract Article 1
- Award procedure
- Article 3 Definitions and duties (article 2 of GAC supplemented)
- Language, applicable law and regulations Article 4
- Constituent documents of the Contract (article 4 of GAC) Article 5
- General applicable instruments Article 6
- Communication (GAC articles 6 and 10 supplemented) Article 7
- Administrative Orders (article 8 of GAC supplemented)
- Article 9 Contracts with conditional phases (article 15 of GAC)
- Article 10 Contractor's personnel (article 15 of GAC supplemented)

#### Chapter II: Financial conditions

- Article 11 Guarantees and bonds (articles 29 and 41 of GAC supplemented)
- Article 12 Amount of Contract (articles 18 and 19 supplemented)
- Article 13 Place and method of payment
- Article 14 Price variation (article 20 of GAC)
- Article 15 Price revision formulas
- Article 16 Price updating formulas (article 21 of GAC)
- Article 17 Work under State supervision (article 22 of GAC supplemented)
- Article 18 Evaluation of works (article 23 supplemented)
- Article 19 Evaluation of supplies (article 24 of GAC) supplemented)
- Article 20 Advances (article 28 of GAC)
- Article 21 Payments for the works (articles 26, 27 and 30 of GAC supplemented)
- Article 22 Interests on overdue payments (article 31 of GAC supplemented)
- Article 23 Penalties for delay (article 32 of GAC supplemented)
- Article 24 Payment in case of a group of enterprises (article 33 of GAC)
- Article 25 Final detailed account (article 35 of GAC)
- Article 26 General detailed account (article 35 of GAC)
- Article 27 Tax and customs schedule (article 36 of GAC)
- Article 28 Stamp duty and registration (article 37 of GAC)

#### Chapter III: Execution of the works

- Article 29 Nature of works
- Article 30 Obligations of the Project Owner (GAC supplemented)
- Article 31 Execution deadline of Contract (article 38 of GAC)
- Article 32 Roles and responsibilities of the Contractor (article 40 of GAC)
- Article 33 Making available documents and site (article 42 of GAC)
- Article 34 Insurance of structures and civil responsibility (article 45 of GAC)
- Article 35 Documents to be furnished by the Contractor (article 49 supplemented)
- Article 36 Organisation and security of sites (article 50 of GAC)
- Article 37 Implantation of structures (article 52 of GAC)
- Article 38 Sub-Contracting (article 54 of GAC)
- Article 39 Site laboratory and trials (article 55 of GAC)
- Article 40 Site logbook (article 56 of GAC supplemented)
- Article 41 Use of explosives (article 60 of GAC)

#### Chapter IV: Acceptance

- Article 42 Provisional acceptance (article 67 of GAC)
- Article 43 Documents to be furnished after execution (article 68 of GAC)
- Article 44 Guarantee time-limit (article 70 of GAC)
- Article 45 Final acceptance (article 72 of GAC)

#### Chapter V: Miscellaneous provisions

- Article 45 Termination of the Contract (article 74 of GAC)
- Article 46 Force majeure (article 75 of GAC)
- Article 47 Differences and disputes (article 79 of GAC)
- Article 48 Drafting and dissemination of this Contract
- Article 49 and last: Entry into force of the Contract

#### Chapter I: General

#### Article 1: Subject of Contract

The subject of this Contract shall be the Rural Electrification of MUGHEFF DOWN VILLAGE IN NJINIKOM SUB DIVISION, BOYO Division).

#### Article 2: Contract award procedure

This Contract shall be awarded by OPENED National Invitation to Tender N° \_\_\_/ONIT/NJINIKOM

## Article 3: Definitions and duties (article 2 of GAC supplemented)

- General definitions (cf. Code)
  - ✓ The Contracting Authority shall be the LORD MAYOR NJINIKOM COUNCIL; in this respect he preserves the original documents relating to the Jobbing Order and transmits copies to the Public Contract Regulatory
  - ✓ The CONTRACT ENGINEER shall be the DIVISIONAL DELEGATE OF WATER RESOURCES AND ENERGY FOR BOYO in collaboration with ENEO. He shall, with ENEO validate the different crucial phases of work done, from the installation of the Contractor to the Provisional Technical Reception (Connection to the National Grid and Energizing of new line). He shall take care of the regular follow-up of work at the site.
  - ✓ The Project Manager shall be the COUNCIL DEVELOPMENT OFFICER FOR NJINIKOM COUNCIL (CDO), charged with the daily MONITORING AND EVALUATION project and report to the ✓ The Contractor shall be [to be specified].

#### 2.2. Security

This Contract may be used security subject to any form of transfer of the debt.

- -1 The authority in charge of ordering payment shall be the MAYOR NJINIKOM COUNCIL (Authorizing
- The body or official in charge of payment shall be the NJINIKOM COUNCIL.
- -1 The official competent to furnish information within the context of execution of this Contract shall be the Divisional Delegate of Water Resources and Energy for Boyo.
- 2.3. Duties of the Control Mission, Project Manager
- 1.1.1. Missions [not applicable].
- 1.1.2. Means put at the disposal of the Control Mission [not applicable].

### Article 4: Language, applicable law and regulation

- 2.2. The language to be used shall be [English and/or French].
- 2.3. The Contractor shall be bound to observe the law, regulations and ordinances in force in Cameroon both within

If the laws and regulations in force at the date of signature of this Contract are amended after the signature of the Contract, the possible direct resulting costs shall be taken into account without gain or loss for either party.

## Article 5: Constituent documents of the Contract (Article 4 of GAC)

The constituent Contractual documents of this Contract are in order of priority: (to be adapted to the nature of the 1) The tender or commitment letter;

- 2) The bidder's tender and its annexes in all provisions not contrary to the Special Administrative Conditions (GAC) and the Special Technical Conditions (STC) hereunder; 3) The Special Administrative Conditions (SAC);

- 5) The particular elements necessary for the determination of the Contract price, such as, in order of priority: the unit price schedule, the statement of all-in prices, detailed estimates, the breakdown of all-in prices and the subdetails of unit prices;
- 6) Plans, calculation notes, trial documents, geotechnical documents;
- 7) The General Administrative Conditions applicable on Public works Contracts that went into effect by Order No. 033/CAB/PM of 13 February 2007;
- 8) The General Technical Condition(s) applicable on the services forming the subject of the Contract.

This Contract shall be governed by the following general instruments [to be adapted according to the case]:

- 1. Framework Law No. 96/12 of 5th August 1996 on the management of the environment;
- 2. The Mining Code:
- 3. Instruments governing the various professional bodies;
- 4. Decree No. 2001/048 of 23<sup>rd</sup> February 2001 relating to the Setting up, Organization and Functioning of the
- 5. Decree No. 2003/651/PM of 16<sup>th</sup> April 2003 to lay down the Procedure for Implementing the Tax and Customs System applicable to Public Contracts;
- 6. Decree No. 2004/275 of 24th September 2004 to institute the Public Contracts Code;
- 7. Decree No. 2012/074 of 8th March 2012 relating to the Creation, Organization and Functioning of Tenders Boards amended and supplemented by Decree No. 2013/271 of 5 August 2013;
- 8. Decree No. 2012/075 of 8th March 2012 to organize the Ministry in charge of Public Contracts;
- 9. Circular No. 001/CAB/PR of 19th June 2012 relating to the Award and Control of Execution of Public
- 10. Letter No; 00908/MINTP/DR of 1997 to publish guidelines for the consideration of environmental impact of
- 11. Circular [to be indicated as applicable] relating to the Execution, and Control of Execution of the Budget of the State, Public Administrative Establishments and Regional and Local Authorities and other bodies receiving government subsidies
- 12. Unified Technical Documents (DTU) for building works;
- 13. Applicable standards; 14. Other instruments specific to the domain concerned with the Contract.

Article 7: Communication (Articles 6 and 10 supplemented) 7.1 All notifications and written communication within the framework of this Jobbing order shall be sent to the following address:

In the case where the contractor is the addressee : beyond the time-limit of 15 days fixed in Article 6 (1) of the GAC to make his domicile known to the Chief of Service and immediately after completion of the works, correspondences shall be validly address to council where the Contractor Resides.

In the case where the Contracting Authority in the addressee: The Regional Delegate of Public Contracts for North West Region with copies addressed to the Chief of Service and the Engineer.

The contractor shall address all written notifications or correspondences to the Engineer with a copy 2.2. to the Chief of Service.

### Article 8: Administrative Orders (Article 8 of GAC)

The various Administrative Orders shall be established and notified as follows:

- The Administrative Order to start execution of works shall be signed by the Contracting Authority and notified to the Contractor by the Project Owner with a copy to the Contracting Authority, the Contract Manager, Contract Engineer, the Paying Body and the Project Manager, where applicable.
- Upon proposal by the Project Owner, Administrative Orders with an incidence on the objective, the amount and execution deadline shall be signed by Contracting Authority and notified by the Project Owner to the Contractor with a copy to the Contracting Authority, the Contract Manager, the Contract Engineer, the 1.2.

Project Manager and the Paying Body. The prior endorsement of the Paying Body shall possibly be required before the signature of those that have an incidence on the amount.

- Administrative Orders of a technical nature linked to the normal progress of the work and without financial 1.3. incidence shall be signed directly by Contract Manager and notified to the Contractor by the Contract Engineer or Project Manager (where applicable) with a copy to the Contracting Authority and Contract
- Administrative Orders serving as warnings shall be signed by the Contracting Authority and notified to the Contractor by the Contract Engineer with a copy to the Project Owner and Project Manager.
- Administrative Orders for suspension or resumption of work as a result of the weather or any other case of 1.5. force majeure shall be signed by the Contracting Authority and notified by the Contract Engineer to the Contractor with a copy to the Project Owner, Contract Manager and Project Manager. 1.6.
- Administrative Orders prescribing works necessary to remedy disorders which could appear on structures during the guarantee period and not related to normal usage shall be signed by the Contract Manager upon the proposal of the Contract Engineer and notified to the Contractor by the Contract Engineer.
- The Contractor has a time-limit of fifteen (15) days to issue reservations on any Administrative Order 1.7. received. Having reservations shall not free the enterprise of executing the Administrative Orders received.
- Concerning Administrative Order signed by the Contracting Authority and notified by the Project Owner, the 1.8. notification must be done within a maximum of 30 days from the date of transmission by the Contracting Authority to the Project Manager. Beyond this deadline, the Contracting Authority shall establish the default of the Project Owner, take over from him and carry out the said notification.

## Article 9: Contracts with conditional phases (Article 9 of GAC)

- [Specify if the Contract has one or several phases] At the end of a phase, the Project Owner shall carry out the acceptance of the works and issue an attestation of proper execution to the Contractor. This attestation shall condition the start of the following conditional
- 9.2 The time-limit granted for notification of the Administrative Order to start execution of a conditional phase shall

## Article 10: Contractor's equipment and personnel (Article 15 of GAC supplemented)

- Any modification, even partial, made to the technical bid shall only occur after the written approval of the Contract Manager. In case of modification, the Contractor shall have himself replaced by a member of staff of equal competence (qualifications and experiences).
- In any case, the lists of supervisory staff to be used shall be subject to the approval of the Project Owner in 1.2. the days following notification of the Administrative Order to start execution. The Project Manager has 5 (five) days to notify his opinion in writing with a copy sent to the Contract Manager. Beyond this time-limit,
- Any unilateral modification on the supervisory staff made in the technical bid prior to and during the works 1.3. shall be a reason for termination of the Contract as mentioned in article 45 NJINIKOM or the application of

#### Chapter II: Financial conditions

#### Article 11 Guarantees and bonds (Articles 29 and 41 of GAC) 11.1 Final bond

The final bond shall be set at 2 % of the amount of the Contract, inclusive of all taxes.

It is constituted and transmitted to the Contract Manager within a maximum deadline of twenty (20) days of the notification of the Contract.

The bond shall be returned or the guarantee released within one month following the date of provisional acceptance of the works, following a release issued by the Contracting Authority upon request by the Contractor.

The retention fund shall be set at 10 % of the amount of the Contract, inclusive of all taxes. 2.2. Performance bond

The return or release of the retention fund or security shall be done within one month after final acceptance by release issued by the Contracting Authority upon request by the Contractor.

The contractor may be granted a start off amount of 20% of the Jobbing Order amount (inclusive of taxes) upon

The start-off payment shall be guaranteed at 100% by a Cameroonian bank recognized by the Ministry in charge of Finance.

## Article 12: Amount of the Contract (Articles 18 and 19 of GAC supplemented)

The amount of this Contract as indicated by the attached [detail or estimates] is \_\_\_\_\_ (in figures)\_\_\_\_(in letters) CFA francs Inclusive of All Taxes; that is:

	, · · · · · · · · · · · · · · · · ·	( ) CFA F
-1	Amount exclusive of VAT:	CEAE
	· · · · · · · · · · · · · · · · · · ·	) CFA F.

- -1 Amount of VAT: \_\_\_ -1 Amount of TSR and/or
- -1 Net to be paid= EVAT-TSR and/or AIR

Article 13: Place and method of payment

The Project Owner shall release the sums due in the following manner:

Owner shall release the sums due in are	
For payments in CFA francs (amount in figures and letters	to account
in Gaures and letters	s exclusive of laxes) by create
The same onto in CFA francs (amount in figures and letters)	hank
No. opened in the name of the Contractor in the	Dank.
ananad in the liality of the Community	
Noopened in the name of	I't to account
112	trans exclusive of taxes) by credit to account
i amount in figures and let	iters exclusive of
For payments in foreign currencies (amount in figures and let	hank.
	Outrice
N°. opened in the name of the	
11,	

#### Article 14: Price variation (Article 20 of GAC)

1.1. Prices shall be firm.

Payments on account made to the Contractor as advances shall not be revisable.

Revision shall be "frozen" upon expiry of the Contractual time-limit, except in the case of price reductions.

1.2. Price updating modalities (not applicable)

Article 15: Price revision formulae (article 21 of GAC) (not applicable)

Article 16: Price updating formulae (article 21 of the GAC) (not applicable)

Article 17: Works under State supervision (Article 22 of GAC supplemented)

- 1.1. The percentage of works under State supervision shall be [must not exceed 2 %] of the amount of the Contract and its additional clauses, where applicable.
- 1.2. In the case where the Contractor were invited to execute works under State supervision, the submitted and duly justified expenditures shall be reimbursed to him under the following conditions:
- 41 | MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECTS 2024

- -1 The quantities considered shall be the hours used or the quantities of building materials and materials used
- -1 The remunerations and salaries effectively paid to local labour shall be increased by forty percent (40 %) to
- -1 The hours put in by the heavy equipment shall be counted at the rate featuring in the sub-detail of prices;
- -1 Building materials and materials shall be reimbursed at cost price duly justified at the place of use, marked
- -1 The amount for services thus calculated, including the hours put by heavy equipment shall be marked up by 25 % to take into account the overheads, profits and the Contractor's unforeseen.

### Article 18: Evaluation of works (article 23 of the GAC)

The work done shall be evaluated using the unit price.

## Article 19: Evaluation of supplies (article 24 of the GAC supplemented)

- 1.1. [indicate, where applicable, the modalities for payment of supplies].
- 1.2. No security shall be requested for payments on account on supplies.

#### Article 20: Advances (article 28 of the GAC)

- 1.1. The Contracting Authority may grant a start-off advance equal to 20 % of the amount of the Contract.
- 1.2. This advance whose value cannot exceed twenty (20) percent of the initial amount inclusive of all taxes shall be guaranteed at one hundred (100) percent by a banking establishment governed by Cameroon law or a firstrate financial institution in accordance with the instruments in force and reimbursed by deduction of the payments on accounts to be paid to the Contractor during the execution of the Contract according to the modalities laid down in the Special Administrative Conditions.
- 1.3. The total amount of the advance must be reimbursed not later than when the value in basic price of the works
- 1.4. As the reimbursement advances, the Project Owner shall issue the release of the corresponding part of the
- 1.5. The possibility of granting start-off advance or advance for supplies must be expressly stipulated in the Tender

#### Article 21: Payment for works (articles 26, 27 and 30 of the GAC supplemented) 1.1. Establishment of works executed

Before the 30th of each month, the Contractor and the Project Manager shall jointly establish a job cost sheet which summarizes and fixes the quantities executed and established for each item on the schedule during the month and

#### 2.2. Monthly detailed account

No later than the fifth (5<sup>th</sup>) of the month following the month of the services, the Contractor shall hand over to the Project Manager two draft provisional monthly detailed accounts in seven copies (one detailed account exclusive of VAT and the other inclusive of taxes), according to the agreed model and establishing the total amount of the sums to which he may lay claim as a result of the execution of the Contract since the start of the Contract.

Only the detailed account exclusive of VAT shall be paid to the Contractor. The detailed account of the amount of the taxes shall be the subject of an entry into the budgets of the Ministry in charge of Finance

Only the amount exclusive of VAT shall be paid to the Contractor as follows:

- -1 [100-1.1 and/or (7.5 or 15%)] paid directly into the account of the Contractor;
- -1 2.2 Or 5.5 % paid to the Public treasury as AIR due by the Contractor.
- -1 7.5% or 15% paid into the Public treasury as TSR due by the Contractor.

The amount of payment on account shall not exceed the value of the technical execution phases carried out.

Payment on account may be spread over the duration of the execution of the Jobbing Order according to technical

Payment on account shall take place within thirty (30) days from the date of transmission to the competent accounting officer, of the documents giving entitlement to payment.

The contractor shall transmit seven (7) copies of the partial invoices to the Engineer for approval before the 5th of

The Engineer shall within a time-limit of seven (7) days forward the approved partial invoices to the Chief of Service. the month following the works executed. The Chief of Service has a maximum time-limit of twenty-one (21) days to sign the partial invoice and to produce the documents giving entitlement to payment on account and transmit same to the competent accounting officer.

3.3. Detailed account of start-off account (if applicable).

Article 22: Interest on overdue payments (Article 31 of the GAC) Possible interests on overdue payments are paid by statement of sums due in accordance with article 88 of Decree No. 2004/275 of 24 September 2004 to institute the Public Contracts Code.

#### Article 23: Penalties (Article 32 of the GAC supplemented)

#### Penalties for delay

1.1. The amount set for penalties for delays shall be set as follows:

One two thousandth (1/2000th) of the initial Contract amount all taxes inclusive per calendar day of delay from the first to the 30th day beyond the Contractual time-limit;

One thousandth (1/1000th) of the initial amount of the Contract inclusive of all taxes per calendar day beyond the 30th day.

1.2. The cumulated amounts of penalties for delay shall be limited to ten percent (10 %) of the initial Contract inclusive of all taxes.

#### Specific penalties [amount to be indicated]

- 1.3. Independently of penalties for overrun of Contractual time-limit, the Contractor shall be liable for the following special penalties for the non-observation of the provisions of the Contract, especially:
  - -1 Late submission of final bond;
  - -1 Late submission of insurances;
  - -1 Late submission of the draft execution schedule if the lateness is caused by the Contractor.

## Article 24: Payment in case of a group of enterprises (article 33 of the GAC)

- 1. In the case of a group of enterprises, indicate the method of payment of co- and sub-Contractors, where need
- 2. Indicate the method of payment of sub-Contractors, where need be.

#### Article 25: Final detailed account (article 34 of the GAC)

- 1.1. After completion of the works and within a maximum time-limit of fourteen (14) days after the date of provisional acceptance, the Contractor shall establish, based on joint reports, the draft final detailed account of works executed and which detailed account summarizes the total sums to which the Contractor may be entitled as a result of the execution of the whole Contract.
- 1.2. The Contract Engineer has up to thirty (30) days to notify the corrected and approved draft to the Project owner.
- 1.3. The Contractor has up to thirty (30) days to return the corrected and approved final detailed account to the competent accounting officer.
- 43 | MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECTS 2024

Article 26: General and final detailed account (article 35 of the GAC)

1.1. The Contract Manager or the Project Manager has up to thirty (30) days to establish the general detailed account and forward to the Contractor after final acceptance.

At the end of the guarantee period which results in the final acceptance of the works, the Authorizing Officer draws up the general and final detailed accounts of the Contract which he had signed jointly by the Contractor and the Contracting Authority. This detailed account includes: -1 the final detailed account,

- -1 the balance
- -1 the summary of monthly payments on account.

The signing of the general and final detailed account without reservation by the Contractor definitely binds the two parties, puts an end to the Contract, except with regard to interest on overdue payments.

2.2. The Contractor has up to thirty (30) days to return the signed final detailed account.

Article 27: Tax and customs regulations (article 36 of the GAC)

Decree No. 2003/651/PM of 16 April 2003 lays down the Terms and Conditions for Implementing the Tax regulations and Customs Procedures applicable to Public Contracts. The taxes applicable to this Contract include

- -1 Taxes and dues relating to industrial and commercial profits, including the IAR which is a deduction on company
- -1 Registration dues in accordance with the Tax Code;
- -1 Dues and taxes attached to the execution of services provided for in the Contract;
  - Duties and taxes of entry into Cameroonian territory (customs duties, VAT, computer tax);
  - ☐ Council dues and taxes;
  - Dues and taxes relating to the extraction of building materials and water.

These elements must be included in the costs which the undertaking imputes on its running costs and constitute one of the elements of the sub-details of prices exclusive of taxes.

All taxes inclusive prices means VAT included.

Article 28: Stamp duty and registration of Contracts (article 37 of GAC)

Seven (7) original copies of the Contract shall be stamped by and at the cost of the Contractor, in accordance with the

#### Chapter III: Execution of works

#### Article 29: Nature of the works (article 46 of GAC)

The works shall include especially: (position or volume of works) (To be specified cf. Special Technical Conditions)

Article 30: Roles and responsibilities of the Project Owner (GAC supplemented)

30.1 The Project Owner shall be bound to furnish the Contractor with information necessary for the execution of his mission and to guarantee, at the cost of the Contractor, access to sites of projects.

30.2 The Project Owner shall ensure the Contractor of protection against threats, insults, violence, assault and battery, slander or defamation of which he could be victim by reason of or during the exercise of his mission.

Article 31: Execution time-limit of the Contract (article 38 of the GAC)

31.1 The time-limit for the execution of the works forming the subject of this Contract shall be one hundred and twenty (120) days.

31.2 This time-limit shall run from the date of notification of the Administrative Order to commence execution of the works.

Article 32: Roles and responsibilities of the Contractor (article 40 of the CAG)

The detailed and general plan of progress of the works shall be communicated to the Contract Engineer in five (05) copies at the beginning of each.

Article 33: Provision of documents and site (article 42 of the GAC)

A reproducible copy of the plans featuring in the Tender File shall be submitted by the Contract Engineer.

The Project Owner shall make available the site and access ways to the Contractor at the appropriate time as the works progress.

Article 34: Insurance of structures and civil liabilities (article 45 of GAC)

The Contractor shall take out a third party risk insurance concerning persons, property or liabilities from an insurance company governed by the "CIMA" insurance code.

## Article 35: Documents to be furnished by the Contractor (Article 49 of the GAC supplemented)

1.1. Programme of works, Quality Assurance Plan and pegging map.

Within a minimum deadline of fifteen (15) days from the date of notification of the Administrative Order to commence execution, the Contractor shall submit in six (6) copies for the approval of project owner after the endorsement of the Contact Engineer the execution programme of the works, his supply calendar, his draft Quality Assurance Plan and the Environment Management Plan, where applicable and the electricity network pegging map at

This programme shall be exclusively presented according to the furnished models.

Two (2) copies of these documents will be returned to him within a deadline of fifteen (15) days from the date of reception with:

- -1 Either the indication "GOOD FOR EXECUTION";
- -1 Or the indication of their rejection including the reasons for the said rejection.

The Contractor has eight (8) days to present a new draft. The Contract Manager or the Project Manager then has a deadline of five (5) days to give his approval or possibly make comments. Delay in approving the draft execution schedule shall stay the execution deadline.

The approval given by the Project Owner does not in any way release the Contractor of his responsibilities. Meanwhile, works executed before the approval of the programme shall neither be ascertained nor paid for. The updated and approved schedule will become the Contractual schedule.

The Contractor shall constantly update on site, a schedule that will take account of real progress of the site. Significant modifications may only be made on the Contractual programme upon receiving the approval of the Project engineer. After approval of the execution schedule by the Contract Manager, the latter shall transmit it within five (5) days to the Contracting Authority without staying its execution. However, if important modifications alter the objective of the Contract or the nature of the works, the Contracting Authority shall return the execution schedule accompanied by reservations to be lifted within fifteen (15) days of the date of reception.

The Environment Management Plan should bring out notably the choice technical conditions of the site and basic life, conditions of the backfill of the extraction sites and conditions for reinstating the works and installation sites.

The Contractor shall indicate in this schedule the equipment and methods which he intends to use as well as the personnel he intends to employ.

The approval granted by the Contract Engineer shall in no way diminish the responsibility of the Contractor with regard to the harmful consequences which their implementation may cause both towards third parties and the respect

#### 2.2. Execution draft

The execution plan documents (calculations and drawings) necessary for the realization of all the parts of the structure must be submitted for the endorsement of the Contract Engineer at most fifteen (15) days prior to the date provided for the commencement of execution of the corresponding part of the structure.

The Contract Engineer has a deadline of five (05) days to examine and make known his observations. The Contractor then has a deadline of (04) four days to present a new file including the said observations.

35.3 In case of the non-observance of the approval deadlines of the above documents by the Administration, these

### Article 36: Organization and safety of sites (article 50 of the GAC)

- 1.1. Signboards at the beginning and end of each section must be placed within a maximum deadline of fifteen days after the notification of the Administrative Order to commence work. It must have the following characteristics: Height = 2.80m, width=1.20m, board thickness=2.5cm at 1.20m above the ground level. The Contract Engineer shall put the Contractors' disposal the text to be used.
- 2.2. The services to inform in case of interruption of traffic or along the deviated itinerary: [To be specified in
- 2.3. Indicate the special measures demanded of the Contractor, other than those provided for in the GAC, for rules of hygiene and safety and for circulation around or in the site.

#### Article 37: Implantation of structures

The Project Manager shall notify within [five] days following the date of notification of the Administrative Order to commence work, the basic points and levels of the project.

#### Article 38: Sub-Contracting (article 54 of the GAC)

The part of the works to be sub-Contracted shall be 30 % of the initial amount of the Contract and its additional

### Article 39: Site laboratory and trials (article 55 of GAC)

- 1.1. Indicate if necessary the modalities for carrying out the trials and geotechnical studies provided for in the
- 1.2. The Contract Manager has a deadline of three days to approve the Contractor's personnel and laboratory as soon

## Article 40: Site logbook (article 56 of the GAC supplemented)

- 1.1. The Site logbook must be systematically jointly signed by the Project Manager or Engineer, where need be and
- 1.2. It is a joint document in a single copy. Its pages must be numbered and initialed. No page should be removed. The erased or cancelled parts must be mentioned on the margin for validation.

#### Article 41: Use of explosives (article 60 of the GAC)

#### Chapter IV: Acceptance

#### Article 42: PROVISIONAL ACCEPTANCE

Before the acceptance of the works the Contractor shall ask in writing to the Contract Engineer, to organize a 42.1 PRE-ACCEPTANCE OPERATIONS technical visit for pre-acceptance. This visit shall include the following operations.

- Qualitative and quantitative evaluations of the different works that have been executed.
- Findings and statement of the unexecuted task envisaged in the present jobbing order.
- > Findings relative to the completion of the work
- > Findings on the quantity of works that have been effectively realized

These operations shall be subject to a site report drawn up on the field, signed by the following.

-Contract Engineer,

During this pre-reception, the Engineer shall eventually specify the reserves to be lifted and the -Contractor. corresponding works to be effected before the reception. The Engineer shall fix the reception date in collaboration with the chief of service for the Contract.

#### Acceptance 42.2

The acceptance commission shall comprise:

eptance commission shall comprise:	(Chairman)
eptance commission shall comprise:  The Authorizing Officer or his representative	(Secretary)
The Authorizing Officer or his representative  The Contract Engineer or his representative.  The Contract Manager	(member)
The Contract Manager	(member)
The Project Manager of his representative	(Member)
The Council Development Officer	(Member)
The representative of beneficiary Community	(Observer)
The Divisional Delegate MINNIAT	(Member)
The Contractor or his Representative	(Member)
The Contractor or his Representative  The Stores Accountant NJINIKOM Council	shall proceed to the acceptar

The commission shall examine the report of the pre-acceptance and shall proceed to the acceptance. An acceptance report (process - verbal) of the works shall be prepared by the Contract Engineer and sign by all the commission members.

## ARTICLE 43: DOCUMENTS TO BE FURNISHED AFTER EXECUTION

- The contractor shall furnish within one (1) month after completion of the works three (3) copies of all working documents and drawings as executed, especially those relevant to the exploitation and maintenance of the works.
- A penalty of 30% of the guarantee retention shall be retained in the event where the contractor fails to 43.2 comply with Article 43.1 above.

#### Article 44: GUARANTEE PERIOD.

The guarantee period is one (01) year from the date of the provisional acceptance.

#### Article 45: Final acceptance (article 72 of the GAC)

Final acceptance shall take place within a maximum deadline of [fifteen (15) days] from the date of expiry of the

The procedure for final acceptance shall be the same as for provisional acceptance

#### Chapter V: Sundry provisions

The Contract may be terminated as provided for in Part III Paragraph IV of Decree No. 2004/275 of 24 September Article 46: Termination of the Contract (article 74 of the GAC) 2004 and equally under the conditions laid down in articles 74, 75 and 76 of the GAC especially in one of the following cases:

- -1 Delay of more than fifteen (15) calendar days in the execution of an Administrative Order or unjustified
- -1 Delay in work resulting in penalties of more than 10 % of the amount of the works;
- -1 Refusal to repeat poorly executed works;
- -1 Default by the Contractor;
- -1 Persistent non-payment for services.

#### Article 47: Case of force majeure (article 75 of the GAC)

If the Contractor were to raise the issue of force majeure, the thresholds NJINIKOM which claims shall not be

- -1 Rainfall: 200 millimeters in 24 hours;
- -1 Wind: 40 meters per second;
- -1 Flood: decennial flood frequency.
- -1 SOCIAL UNREST / PANDEMICS

## Article 48: Disagreements and disputes (article 79 of the GAC)

Disagreements and disputes resulting from the execution of this Contract may be settled amicably.

Where no amicable solution can be found for a disagreement, it is brought before the competent court in the North-West Region of the Republic of Cameroon.

## Article 49: Production and dissemination of this Contract

SEVEN (07) copies of this Contract shall be produced at the cost of the Contractor and furnished to the Contract

#### Article 49 and last: Entry into force of the Contract

This Contract shall be final only upon its signature by the Contracting Authority. It shall enter into force as soon as it

# Document N°. 5 SPECIAL TECHNICAL CONDITIONS (STC)

#### INTRODUCTION.

This specification aims to define the mode of execution of work to be done following the norms and approved standards, according to the documents of the Contract.

The choice of technological options for achieving the proposed work has the sole concern to ensure a better functionality of facilities in compliance with safety rules for the protection of property and persons. It has been established as a guide to clarify and supplement the guidance of the estimate and drawings

#### B-MODE OF EXECUTION OF WORK

#### General:

For all construction arteries medium voltage, single-phase or three-phase sub-stations, MV/LV, LV single-phase and three-phase lines, generator house, thermal electricity production, and security measures and environmental protection to be observed, they must conform to the requirements, laws, decrees, orders, standards, norms and Publications in force in Cameroon and for management of the electricity sector. In default the texts will be applied in this order:

- The recommendations of the International Electro-technical Committee (IEC Publication);
- The European standards CEN-CENELEC (EN);
- The French AFNOR standards;
- The decision of 2 April 1991 laying down the Technical Conditions to be satisfied by the distribution of electricity, published in the Official Gazette of the French Republic on May 4, 1991;
- Circular No. 78-79 of 6th July 1978 on the implementation of the Decree of May 26, 1978' - Standards Approved French NFC;
- French UTE standards and in particular;
- C 10-100;
- C 10 101;
- C 10 200:
- Any other norms recognized in the system (ISO).

All these rules may be modified under the responsibility of the Administration in charge of electricity to reflect local conditions, knowing that the works will be built to suit the conditions defined NONIw: - Average temperature: 35° C

- Humidity correspondent: 98 %
- Extreme temperature (indoor):
- The Minimum + 10°C;
- Max + 50° C;
- Exceptional speed winds 180 km/h;
- Normal speed winds 5 to 35 km/h

Wooden poles shall conform to the standard UPDEA.

### \* Specific case of mini and micro diesel power plants:

They are part of the internal electrical installations for power up to 100 KW (125 KVA). It will often consist of compact units with low voltage three-phase output or separate elements with a low voltage general control board, transformer, three-phase MV outlet. Documents:

The Works will be performed according to the following documents;

- The technical offer of the bidder (detailed technical definition of the consistency of the work and execution plans,) - The attached cost estimates;
- The general administrative terms and conditions applicable to works Contracted on behalf of State; - The various international standards recognized in the system (ISO) and may apply to the environment and
- -The local power authority, safety and environmental protection regulations applicable in Cameroon; The Contract documents are complementary and must be accepted as a whole. They explain and complement each

All that would be missed by some, but noticed by others and that would be required to complete the work in accordance with the clear intent of the said Contract documents to be executed by the Contractor without additional charges

The single-phase or three-phase antenna will be derived from a phase of the triple phase mainline. It will be constructed in 11m wooden poles, class D and Almelec 34.4 mm<sup>2</sup> or 30 mm<sup>2</sup> aluminum or 50 mm<sup>2</sup> cables as the case, stretched on a rigid glass insulator mounted on spindle on wooden poles. A derivation is made as a bypass with a fuse that will swing making the fuse opening visible and easily locate the faults in the line. The works of involve:

- 601001: Supply and installation of rigid glass insulators Including perforated attachment and all constraints of supply and labor;

- 601002: Supply and installation of 30KV chain of three insulators;

- 601003: Supply and installation U bolts for insulation chain, including supply and installation galvanized bolts;
- 601004: Supply and installation of overhead support spindle;
- 601005: Supply and installation "Danger of Death" plate;
- 601006: Supply and installation number plate on wooden poles;
- 601007: Supply and installation breakage 70/600;
- 601008: Supply and installation mounting brackets;
- 601009: Supply and installation single-phase fuses cutout including all accessories;
- 601010: Supply and installation of 27 KV surge arrester including connection;
- 601011: Supply and stringing of 34.4mm<sup>2</sup> Almelec cable;
- 601012: MV junction and bypass single-phase;
- 601013: Supply and planting simple wooden pole 11m class D;
- 601014: Supply and planting twin wooden pole 11m class D;
- 100000: Studies and pegging leading to the establishment of an implementation plan to be approved by the Regional Service of Energies;
- 101001: Excavation in natural terrain;
- 101002: Excavation in semi rocky terrain;
- 101004: Excavation in rocky terrain;

The fuses cutout will be installed from the beginning of each branch; class 2A for the derivation  $\square$  500m feeding a single transformer.6A class for long-lead and those supplying several transformers.

At each MV/LV transformer is consistently associated surge arrester which determines the level of surge the transformer (125KV) can withstand and the nominal voltage is 27 KV.

It is mounted on the same support as the transformer and connected between one phase and the ground circuit.

It is expected to be on a class D post in transit or at the end and installed with a platform to maneuver in solid concrete. Work to be done

- 602001: Supply and installation pigtail BQC 14-250;
- 602002: Supply and installation of two bolts for hanging transformer 16-300;
- 602004: Supply and installation of 25 KVA transformer 17.32 KV/B2;
- 602006: Supply and installation arm bis 70  $\square$  600 for support of pairing;
- 602006: Supply and installation of dischargers;
- 602007: Fixing and connecting surge arrester 27 KV;
- 602008: Setting up and connecting single phase fuses cutout;
- 602011: construction of earth grounding;
- A mechanical protection or gutter tube galvanized pipeØ40;
- Tube PVCØ25 length 2 × 8.8 cm;
- Copper Cable 25 mm<sup>2</sup>-18m;
- straight and level including; · Two copper fittings. 602013: Making a grounding type C, provided with cable
- A cable 29 mm<sup>2</sup> bare copper in trench  $0.5 \times 0.80$  of length equal to  $2 \times 15$ m;
- 602017: Full equipment of a post on post-17 single-phase 25 KVA, 17.32 KV/231V with a land type 2BH;

The transformer should be new and tested in one of the ENEO testing Centers.

#### BT NETWORK SINGLE PHASE OR THREE-PHASE

51 | MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECTS 2024

Low voltage lines will be built on simple 9m wooden posts spaced 45m apart, with 4□25mm² twisted cable for the Single-phase and 3x50mm<sup>2</sup>+1NP+EP preassembled cable for Three-phase. In case of mixed network MV/LV, the materials will be 11 m poles spaced apart with a maximum distance of 45 meters.

The cables will be assembled in pairs and connected to the terminals of the combined protection in order to build a cable round trip, so it is electrically 2 x 25mm<sup>2</sup> a cable, which allows for long lines in the order of 2 to 3km from the The works to be done;

- 603001: Supply and installation of alignment support;
- 603002: Supply and installation of anchoring clamp;
- 603003: Supply and installation of all IT D76 4 connections;
- 603004: Supply and installation of anchor arms BORØ12L including a hook 250, an anchoring clamp 27 or AFU
- 603005: Providing and laying stringing 4x25 mm<sup>2</sup> Alu twisted cable;
- 603007: Grounding type C cable will work cable, compound cable numbered from 0 and 1;
- 603008: Supply and planting simple wooden poles 9m class C;
- 603009: Supply and planting twin wooden poles 9m class C;
- 6030010: Supply and planting of strutted wooden poles 9m class C;
- 6030011: Supply and fitting end cap on retractable cable pre-assembled or twisted;

#### HOUSEHOLD CONNECTIONS

This is to cover aerial connections two or - 701001: Connecting household 2 wire 220V; four wires. The work involved will include;

- 701003: Connecting aerial 2 wire 2 220 V counter or 4'wire- 220/380V counter.

#### Clearing and pruning

It involves the, cutting and clearing of trees in urban and rural areas, including bushes with opening of transects 10

#### THE DELIVERIES AND HANDLING

The transportation of material and its handling from the place of supply to the construction site including distribution

#### GENERATOR

- a) Description and characteristics
- Diesel suitable power range meets the needs of the electrification of remote areas;
- Control panel and accessories to control the operation;
- Alternator excitation device and control systems;
- · Control and monitoring electrical cabinet equipment;
- Common Chassis and its cabinet, adapted to working conditions. b) Types of uses:
- Continuous operation during 24/24. At this stage the generator should not be subject to overload;
- Continuous operation limited to 3500h per year and variable load. Ability to operate 24/24 during certain periods Possibility of transient overload of 10% with a daily service less than or equal to 12 hours

Plus or minus 15% of rated voltage for power factor between 0.8 and 0.95 and a balanced load of about 10%

## CHOICE OF THE NUMBER AND TYPE OF GENERATOR

#### Electrification of remote areas;

The production must be adapted to the nature of the proposed distribution. means of Intermittent Distribution: 6h/24 for domestic lighting. At this level one generator will be sufficient. But provide maintenance for a few days a year. The power demand must not go NJINIKOM w 30-50% of rated output;

Semi-continuous distribution: 12h/24 suitable for domestic lighting, a few craft needs, some utilities such as water pumping, carpentry, bakery Etc. Two generators are sufficient for a minimum power between 50 and 100% of

Continuous distribution: 24/24, in cities where there is an industrial and craft activity large enough. Two generators minimum are required, in principle, of different power to allow better adaptation to the charges and avoid operation NJINIKOM 30 to 50% of rated output. The distribution of powers within plus or minus 10%. The need to

choose a power supply less than or equal to 0.85 x 0.9 x E Generator power. Specific details will be given by the

For mini diesel central requiring voltage step up, specific details related to any facility will be given after each manufacturer data sheets. project by the Contracting Authority.

#### DIMENSIONNEMENT DU RESEAU.

#### √ Réseaux moyenne tension et basse tension

La tension de service du réseau monophasée est de : 17,32KV

La tension de ser CONDUCTEURS NORMALISE	FLECH DE POSE	u monophasée est o RESISTANCE LINEIQUE	POUISSANCE INSTALEE KVA	NOMINALE	RESEAU	
	- 1-	R=1.20Ω/km	20 -25 KW	96	1km	20% (380/220V)
Câble torsadé	0.47 m	R=1.2022KIII	20 20			20%
Alu 4x25mm² Câble almélec de 34mm²	0.30 m	R=0.958Ω/km	75KVA	0,7	5km	

Portée équivalente en BT : 50 – 60m de manière à éviter les efforts longitudinaux (mise à la terre type copperweld à tous les trois cent mètres et un support après le transformateur).

Portée équivalente en MT : 100 - 110m (ligne sur isolateurs rigides) câble almélec 34mm<sup>2</sup> : masse

Les isolateurs sont en verre trempés de type HT36 ou HT38 ; les chaînes d'isolateurs seront de 3 éléments pour les lignes 30 KV.

SUPPORTS	CLASSE C	CLASSE D	ANGLE	PROFONDEUR FOUILLES (M)	HAUTEUR HOR SOL (TERRAIN NORMAL)	HAUTEUR HOR SOL (TRAVERSEE ROUTE)	
Poteaux bois 9m/s	190 DAN	300 DAN	≤10° Alignement	H/10 +0.5	6,15m	8,20m	Chois poteaux 9m simple Classe D
Poteaux	570	900 DAN	45° à 90°	H/10 + 0.5	6,15m	8,20m	9m jumelés aux angles
bois 9m/	jDAN		45° à 90°	H/10 + 0.5	3,75		9m contrefichés
Poteaux	1450	2250 DAN	43 4 30	H/10 + 0.5	6,15m	8,20m	aux arrêts Terrain latéritiqu
bois 9m/z	x1000	1250 DAN	25° à 60°	H/10 + 0.5	7,95m	10m	
bois 11m/		2250	60° à 90°				Calage à la pierr
Poteau bois11m		2250 DAN	00° a 90°	H/10 + 0.5	7,95m	10m	sèche

#### √ <u>DIMENSIONNEMENT DES OUVRAGES.</u>

La puissance demandée est de P = 54,1 KVA. Compte tenu des pertes dans les réseaux et le degré de charge d'un transformateur normalisé à 80% cette puissance appelée est de 64,8 KVA soit un transformateur monophasé de 25 KVA.

Cependant, le présent projet prévoit de satisfaire dans un premier temps, uniquement la demande en énergie domestique d'une partie de la population du secteur et il aura un transformateur monophasé de 25KVA.

La desserte en BT-Mono du reste de la Communauté se fera à la suite du présent projet par extension à la demande des populations bénéficiaires.

#### Coupe-circuits

53 | MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECTS 2024

Les normes prévoient pour le réseau monophasé de plus de 500mètres des coupe-circuits : Un au point de dérivation et un autre au niveau du transformateur.

#### PROTECTION DU RESEAU ET NORMALISATION.

Ces deux préoccupations doivent être prises en compte aux raccordements au réseau ENEO, car cette société insiste sur l'aspect normalisation des équipements et des installations électriques avant tout branchement sur son réseau. Cette normalisation vise surtout à protéger et à sécuriser les installations, ainsi qu'à assurer la fourniture d'une

Les recommandations faites dans le cadre de la présente étude sont conformes aux normes en vigueur. Il faudra simplement veiller à leur respect et à l'acquisition du matériel électrique répondant à ces normes. Ces préoccupations justifient les recommandations majeures ci-après :

 Pose d'un coupe-circuit à expulsion au point de raccordement et à chaque transformateur pour isoler des tronçons de réseau en cas de problèmes ;

· Pose d'un poteau jumelé à chaque arrêt de ligne et chaque dérivation ;

- Utilisation des poteaux normalisés de 11 mètres pour les lignes MT et mixtes ; 9 mètres pour les tronçons BT simples:
- Pose d'équipement de mise à la terre en arrêt des lignes, sur chaque poteau-transformateur et sur chaque poteau entourant un transformateur;
- Câble almélec 1×34 mm² pour la ligne moyenne tension et câble torsadé 4× 25 mm² en aluminium pour le transport BT.
  - Les poteaux sont implantés selon le schéma normalisé.

Ligne moyenne tension et ligne mixte.

- \* Poteau simple (S) de 11 mètres avec isolateur suspendu et équipement d'ancrage, pour alignement droit et angle jusqu'à 10°:
- \* Poteau jumelé (J) de 11mètres avec isolateur suspendu et équipement d'ancrage, pour angle entre 60° à 90°; Ligne basse tension
- \* Poteau simple (S) de 9mètres avec console de suspension et pince d'alignement, pour alignement droit et angle jusqu'à 10°:
- \* Poteau jumelé (J) de 9mètres avec console de suspension et pince d'alignement, pour angle 10° et 45° et pour dérivations (≥ 90°).

#### MATERIELS POUR LA MISE EN ŒUVRE DU PROJET.

En conformité avec les normes utilisée au Cameroun, les différents types d'assemblage pour le réseau

Code	EAU SIMPLE 11 mètres EN ALIGNEMENT DROIT (angle jusqu'à MT-101	25°)
	Elément	Quantité
	Console de tête	
	Isolateur en verre renforcé	1
	Petits accessoires (attache, boulon, plaquette galva, rondelle)	1
2. POT	EAU SIMPLE 11 miles DN 43200	2
Code	EAU SIMPLE 11mètres EN ANGLE VERTICAL (angle 25° à 60°) MT-102	
	Elément	
	Crochet d'ancrage type queue de cochon 14 x 450	Quantité
	Isolateurs à 3 éléments (suspendu horizontalement)	1
	Pince d'angle	î
	Petits accessoires (hall sockets and the	i
	Petits accessoires (ball sockets, roulet, plaquette galva, rondelle)	i
. POTE	AU JUMELE 11 mètres EN ANGY E	1
Code	AU JUMELE 11mètres EN ANGLE VERTICAL (angle 60° à 90°)	
	Elément	
	Crochet d'ancrage type queue de cochon 14 x 450	Quantité
1 MUGH	EFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECT	2

		2
	Isolateurs à 3 éléments (suspendu horizontalement)	2 2
	Pince de renvoi	1
	Console de tête	1
	- Famaá	4
	Petits accessoires (attache, boulon, plaquette garvan, rondon)	
4 DOTE	AU CONTREFICHE 11 mètres EN ANGLE VERTICAL (angle p	olus de 90°)
4. POTEA Code	MT-104	Quantité
0041	Elément 14 v 450	2
	Crochet d'ancrage type queue de cochon 14 x 450	2
	Isolateurs à 3 éléments (suspendu nonzontalement)	2
	Pince de renvoi	1
	Console de tête	1
	Isolateur en verre renforcé	4
	Petits accessoires (attache, boulon, plaquette galvan, rondelle)	1
	Ferrure de contrefichage en acier gaivantse	
5 POTI	EAU HAUBANE 11 mètres EN ANGLE VERTICALE (angle plus	de 90°)
Code	MT-105	Quantité
0000	Elément	2
	Crochet d'ancrage type queue de cochon 14 x 450	2
	Isolateurs à 3 éléments (suspendu nonzontalement)	2
	Pince de renvoi	1
	Console de tête	1
	Isolateur en verre renforcé	4
	Petits accessoires (attache, boulon, plaquette galvan, london)	
6 POT	EAU SIMPLE 9mètres EN ALIGNEMENT DROIT (angle jusqu'à 10°	)
Code	BT-301	Quantité
Cour	Elément	1
	Console de suspension	1
	Pince d'alignement Petits accessoires (attache, boulon, plaquette galvan, rondelle)	1
	Petits accessoires (attache, boulon, plaquette games	5°)
7. POT	TEAU JUMELE 9mètres EN ALIGNEMENT DROIT (angle de 10° à 4	
Code	BT-302	Quantite
	Elément	1
	Console de suspension	1
	Pince d'alignement Petits accessoires (attache, boulon, plaquette galvan, rondelle)	
	TEAU CONTREFICHE 9mètres EN ANGLE VERTICAL (angle de 10	o° à 45°)
8. PO	BT-303	Quantité
Code	Elément	2
	Console d'ancrage	2
		3
	Pince d'ancrage Petits accessoires (attache, boulon, plaquette galvan, rondelle) Ferrure de contrefichage en acier galvanisé	1
	remuie de contientames	
	OTEAU JUMELE 9mètres DE DERIVATION BT	200
9. PC		
9. PC	Code BT-304	Quantité
	Code BT-304  Elément  Console d'ancrage  MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PE	1

Pince d'ancrage		
Petits accessoires (attache bould	on plaquette 1	1
Console de suspension	on, praquette galvan, rondelle)	2
Pince d'alignement		1
		1
10. POTEAU JUMELE 9mètres EN AR	PET DT	
Edge B1-305	GKE I BI	
Elément		
Console d'ancrage		Quantité
Pince d'ancrage		1
Petits accessoires (attache, boulon Capuchons		i
Capuchons (attache, boulon	, plaquette galvan, rondelle)	2
Ceinture de fixation		
Tration		6
11. MISE A LA TERRE		M. E. C. Land L. Harris
Code BT-306		
Elément		
Conducteur en cuivre 29 m		•
Connecteur à griffes		Quantité
Crampe de fixation		1
Feuillard de 20 mm		1
Protectour v. (		2
Protecteur mécanique		1
Raccord de dérivation alu-cuivre		1
Tube isolant		1
Piquet terre		1
12 DAGGODD		1
12. RACCORDEMENT AU RESEAU MT	ENALIGNEMENT	
12. RACCORDEMENT AU RESEAU MT Code MT-106	(sur transform	nateur MTN)
Element		
Crochet d'ancrage type queue de co	chon 14×450	Quantité
a J Cleffients (suchand), L	Orizontalement)	1
40 1011 101	orizontalement)	1
Console de tête		1
Isolateur en verre renforcé		1
Petits accessoires (attache boulen	plaquetta colore	1
Coupe-circuit à expulsion	oraquette gaiva, rondelle)	2
Bras incliné bis		ī
		i
12 TD INCH		
13. TRANSFORMATEUR MONOPHASE I Code MT-108 + BT-304	EN ARRET + DEDIVATION	
Code MT-108 + BT-304	DERIVATION BT	
Elément		
Crochet d'ancrage type queue de coch	10n 14 × 450	Quantité
d 5 Cicilicilis Islighandu ham	izontala	1
	izontalement)	1
Console de tête		1
Isolateur en verre renforcé		i
Petits accessoires (attache houlen mis-	2000	1
Console d'ancrage	quette galva, rondelle)	8
Pince d'ancrage		1
Console de suspension		1
Pince d'alignement		1
Parafoudre 27 KV		1
m		1
Transformateur monophasé		1
Transformateur monophasé Coupe-circuit à expulsion		1
Coupe-circuit à expulsion		1
Coupe-circuit à expulsion Bras incliné bis    MUGHEFF DOWN / TWAFUNDONG RURAL		1 1 1

# Document No. 6 SCHEDULE OF UNIT PRICES

## RURAL ELECTRIFICATION OF MUGHEFF DOWN VILLAGE IN NJINIKOM SUB DIVISION, BOYO

Ref Nº	DESCRIPTION OF WORKS	SUPP	RICE SC LY	HEDUL	LABO	IID		
					LADOUR			
100	1x34,4mm2 & 4x25 mm <sup>2</sup> MV/LV SINGI	U.P LE PHASE	LINE T	.P	U.P	T.P		
101	Pegging (Code 10000)							
102	Excavation of holes ( Code 100001)							
103	S & F U anchor iron (Code 60113)							
104	S & F Single 11m wooden poles class D (Code 601014)							
105	S & F twin 11m wooden poles class D (Code 601015)							
106	S & F Rigid glass insulator 30kv (Code 601001)							
107	S & F Chain of three insulator (Code 601002)							
108	S & F Spindle (Code 601004)							
109	S & F Warning plates DM (Code 601005)							
110	S & F Number plate + Numbering (Code 601006)							
11	S & Stringing 34.4 mm <sup>2</sup> Almelec cable (Code 601011)		1	Facility				
12	S & F LV Alignment support (Code 603001)							
13	S & F LV Anchoring clamp (Code 603004)	Mes						
	S & F Stringing 4x25 mm <sup>2</sup> twisted cable (Code 601011)							
	S & F Set of four LV line taps (3504035)  Electrical caps with retractable ends						3 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
	(Code 603011)							
	Type C earth plug (Code 603007)  S & F Line tap (Code 3504035)							
2	Sous Total 100		_					
) [	LV SINGLE PHASE LINE							
]	Pegging (Code 10000)							
E	excavation of holes (Code 100001)							
6	& F LV Alignment support (Code 03001)							
60	& F LV Anchoring clamp (Code							
10	& F Single 9m wooden poles class C Code 603008) & F twin 9m wooden poles class C						-	
1(0	code 603009) & F Set of four LV line taps							
(3:	\$504035) & F Number plate +							
Nu	Admitsel plate + Imbering (Code 601006)  & F Stringing 4x25 mm² twisted cable							
100	5de 001011)							
100	ode 601011)  JGHEFF DOWN / TWAFUNDONG R U R A L	ELECTR	IFICAT	101	0.01.0			

	Electrical caps with retractable ends					
	(Code 603011) Type C earth plug (Code 603007)					
11	Sous Total 200					
	SINGLE PHASE TRANSFORME	R H61-25	KVA 17.32	KV/B2		
00	SINGLE PHASE TRANSFORME	K Hor 20				
01	S & F 25KVA Transformer (Ref					
01	22 001 050048)					
302	S & F twin 12m concrete pole					
	000 1(Codo 601015)	001				
303	S & F Type 2BH earth plug (Ref 22 050049)	.001				
304	S & F chain of three insulator discharger					
305	S & F Mounting bracket (code					
306	S & F 27KV Surge arrestor (Ref					
307	Full equipment of single phase stati					
308	S & F Fuse cutout 2A(Ref 22 001					
309	S & F Earth plug for mass					
	Sous Total 300					
401	Production and validation of an environmental impact notice					
1	CHVII OHITICITIAN 1-1-1					
	Sub-total 400					
500	Sub-total 400					
T. W. S. S. S. S.	Sub-total 400 SUNDRY EXPENSES	york				
501	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Network (Ref 22 001 050022)	vork				
501	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Netwood (Ref 22 001 050022) Clearing and pruning (Code 201002)					
501	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Netwood (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of material (Code 2003)					
501	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Netwood (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of materic (Code 2003) Transport wooden poles (Code 2004)					
501 502 503	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Netwood (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of materic (Code 2003) Transport wooden poles (Code 2004) Control connection + ENEO CAMEROON Subscription (Ref 22 009 050001)	al				
501 502 503	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Netwood (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of materic (Code 2003) Transport wooden poles (Code 2004) Control connection + ENEO CAMEROON Subscription (Ref 22 009 050001) Transport of workers (Code 2005)	al				
501 502 503 504	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Netwood (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of materic (Code 2003) Transport wooden poles (Code 2004) Control connection + ENEO CAMEROON Subscription (Ref 22 009 050001) Transport of workers (Code 2005) Sous Total 500	al				
501 502 503 504	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Netwood (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of materic (Code 2003) Transport wooden poles (Code 2004) Control connection + ENEO CAMEROON Subscription (Ref 22 009 050001) Transport of workers (Code 2005)	al				
501 502 503 504	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Netwood (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of materic (Code 2003) Transport wooden poles (Code 2004) Control connection + ENEO CAMEROON Subscription (Ref 22 009 050001) Transport of workers (Code 2005) Sous Total 500	al				
501 502 503 504	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Network (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of materic (Code 2003) Transport wooden poles (Code 2004) Control connection + ENEO CAMEROON Subscription (Ref 22 009 050001) Transport of workers (Code 2005) Sous Total 500 TOTAL WITHOUT TAXES  VAT AIR	al				
501 502 503 504	Sub-total 400 SUNDRY EXPENSES  Connection to AES SONEL Network (Ref 22 001 050022) Clearing and pruning (Code 801002) Transport and handling of materic (Code 2003) Transport wooden poles (Code 2004) Control connection + ENEO CAMEROON Subscription (Ref 22 009 050001) Transport of workers (Code 2005) Sous Total 500 TOTAL WITHOUT TAXES	al				

COMPANY:

## RURAL ELECTRIFICATION OF TWAFUNDONG VILLAGE IN NJINIKOM SUB DIVISION, BOYO DIVISION

UNIT PRICE SCHEDULE DESCRIPTION OF WORKS Ref SUPPLY No LABOUR U.P 1x34,4mm2 & 4x25 mm<sup>2</sup> MV/LV SINGLE PHASE LINE 100 T.P U.P T.P 101 Pegging (Code 10000) Excavation of holes (Code 100001) 102 S & F U anchor iron (Code 60113) 103 S & F Single 11m wooden poles class D 104 (Code 601014) S & F twin 11m wooden poles class D 105 (Code 601015) S & F Rigid glass insulator 30kv (Code 106 601001) S & F Chain of three insulator (Code 107 601002) 108 S & F Spindle (Code 601004) S & F Warning plates DM (Code 109 601005) 110 S & F Number plate + Numbering (Code 601006) 111 S & Stringing 34.4 mm<sup>2</sup> Almelec cable (Code 601011) S & F LV Alignment support (Code 112 603001) S & F LV Anchoring clamp (Code 113 603004) S & F Stringing 4x25 mm<sup>2</sup> twisted cable 114 (Code 601011) 115 S & F Set of four LV line taps (3504035) Electrical caps with retractable ends 116 (Code 603011) 117 Type C earth plug (Code 603007) Sous Total 200 200 LV SINGLE PHASE LINE 201 Pegging (Code 10000) Excavation of holes (Code 100001) 202 203 S & F LV Alignment support (Code 603001) S & F LV Anchoring clamp (Code 204 603004) S & F Single 9m wooden poles class C 205 (Code 603008) S & F twin 9m wooden poles class C 206 (Code 603009) S & F Set of four LV line taps 207 (3504035)208 S & F Number plate + Numbering (Code 601006) S & F Stringing 4x25 mm<sup>2</sup> twisted cable 209 (Code 601011)

60 | MUGHEFF DOWN / TWAFUNDONG RURAL ELECTRIFICATION PROJECTS 2024

will it.

0	Electrical caps with retractable ends				
	(Code 603011) S & I complete Eneo subscription at	nd			
1	connection set with a single phase in (ref 22 009 050001)	neter			
12	Type C earth plug (Code 603007)				
-	Sous Total 300				
00	SINGLE PHASE TRANSFORM	ER H61-25KV	A 17.32KV	B2	
00					
01	S & F 25KVA Transformer (Ref 22 001 050048)				
302	S & F twin 12m concrete pole 800dan(Code 601015)	2.001			
303	S & F Type 2BH earth plug (Ref 2	22 001			
304	S & F chain of three insulator				
305	discharger S & F Mounting bracket (code				
303	601007)				
306	S & F 27KV Surge arrestor (Ref 21005010007)				
307	Full equipment of single phase sta (Ref 22 001 050002)	The same of the same of			
308	S & F Fuse cutout 2A(Ref 22 00 050038)	1			
	Sous Total 400	- I OTT OF			The state of the s
400	ENVIRONMENTAL IMPACT	NOTICE			
401	Production and validation of an				
401	environmental impact notice				
	Sub-total 500				
500					
501	(Ref 22 001 050022)	work			
502	801002)	ial			
503	(Code 2003)	lai			
	Transport wooden poles (Code				
504	2004)				
502	5 Transport of workers (Code 2005)				
15.53.0005	2004) 5 Transport of workers (Code 2005) Sous Total 500				
15.53.0005	5 Transport of workers (Code 2005)				
15.53.0005	2004) 5 Transport of workers (Code 2005) Sous Total 500				
15.53.0005	2004)  Transport of workers (Code 2005)  Sous Total 500  TOTAL WITHOUT TAXES  VAT  AIR				
15.53.0005	2004) 5 Transport of workers (Code 2005) Sous Total 500 TOTAL WITHOUT TAXES VAT				

#### COMPANY:

# Document N°. 7 BILL OF QUANTITIES AND ESTIMATES

# BILL OF QUANTITIES AND COST ESTIMATES FOR MUGHEFF DOWN RURAL ELECTRIFICATION PROJECT IN NJINIKOM SUB DIVISION, BOYO DIVISION

			UNI	r	TY	SU	PPLY			LABO	UR		S & L TOTAL	
	DE	SCRIPTION OF WORKS	UNI		211	U.I		T.I	)	U.P	T.F	•	IOIAL	
		4,4mm2 & 4x25 mm <sup>2</sup> MV/LV SIN	CLE	PHA	SE L	INE								
0	1x3	4,4mm2 & 4x25 mm <sup>2</sup> MV/LV SIN	KM	10	).35			T						
)1	Peg	ging (Code 10000)				-		+				And the second		
)2	Exc	cavation of holes (Code 100001)	M³		3	+		+						
03	S 8	F U anchor iron (Code 60113)	U	4	4						-			
04		& F Single 11m wooden poles class	U		5									
04	D	Codo 601014)		_	2			-	1977					
05	S	& F twin 11m wooden poles class	U		2									
	n	(Code 601015)	U		7									
06	S	& F Rigid glass insulator 30kv			35				- 140-471					
	(C	ode 601001) & F 3 Components anchor earth	U		4									
107	S	ring (Code 601002)												
108	Su	& F Spindle (Code 601004)	U		7			_			_	10/10/01		
109	0	& F Warning plates DM (Code	U		7									
109	61	11005)			7	-	-	-						
110	S	& F Number plate + Numbering	U		1									
	111	2-4-601006)	100	Л	367.	5								
111	S	& Stringing 34.4 mm <sup>2</sup> Almelec	, D.,											
110	C	able (Code 601011)  & F LV Alignment support (Code	U		4									
112	1 6	(02001)											1	
113	15	S & F LV Anchoring clamp (Cod	e U		4									
113	1/	(02004)		M	367	5								
114	1	S & F Stringing 4x25 mm <sup>2</sup> twiste		IVI	307									
	1	cable (Code 601011)	s U		1	_								
115		Electrical caps with retractable end	is   0		1									
		(Code 603011) Type C earth plug (Code 603007)	U	J	2									
116	5	S & F Line tap (Code 3504035)	U		1									
117	7	S & F Line tap (Code 3304035)												
	_	Sous Total 100												
20	-	LV SINGLE PHASE LINE	H	ζM	1									
20	1	Pegging (Code 10000)		M <sup>3</sup>	8				and the					
20	2	Excavation of holes (Code 100001)		U	8									
20	3	S & F LV Alignment support (Co 603001)	"		1									
20	14	S & F LV Anchoring clamp (Co	de	U	8									
20	/4	(02004)			1.							100		
20	)5	S & F Single 9m wooden poles cl	ass	U	10	0								
	estado.	C (Code 603008)		U	4									
20	06	S & F twin 9m wooden poles clas	SC	U	1									
		(Code 603009)  S & F Number plate + Numbering	1	U	2	0								
2	07	(Code 601006)		200					-			1		
-	00	S & F Stringing 4x25 mm <sup>2</sup> twis	sted	LM	1	050.0								
2	80.	11- (Codo 601011)	1				-		-					
2	209	Electrical caps with retractable e	nds	U	4	•								
-		(Code 603011)		U	-	5	1 7							
1	210	Type C earth plug (Code 603007)		U										
		Sous Total 200 SINGLE PHASE TRANSFORM	/ED	H61-	25KV	/A 17.	32KV/	В2						
	300	SINGLE PHASE TRANSFORM	f	U		1								
100	301	S & F 25KVA Transformer (Re 22 001 050048)	1											

	TOTAL WITH TAXES		5.5				
	AIR	%	2.20or	- 1			
-	VAT	%	19.25				
-	TOTAL WITHOUT TAXES						1
-	Sous Total 500						
		Ls	1				
07	Transport of workers (Code 2005)	Ls	1				
06	Site installation	Le	ļ				
405	Control connection + ENEO CAMEROON Subscription (Ref 22 009 050001)	U	1				
404	Transport wooden poles (Code 2004)		1				
403	Transport and handling materia (Code 2003)	l T/Km	1				
- 0.036	Clearing and pruning (Code 801002)	Km	1				
401	Connection to AES SONEL Network (Ref 22 001 050022)	k U	1			1	
<b>400</b> 401	SUNDRY EXPENSES						
400	Sous Total 300						
309	050038)	I U	1				
308	station (Ref 22 001 050002)		1				
307	S & F 27KV Surge arrestor (Ref 21005010007)		1				
306	- se i Dardi piug ior mass	U	1				
305	601007) Woulding bracket (co	de U	1				
304	discharger discharger		1				
303	001 050049) (Ref	1 22	1			-	
	S & F twin 12m wooden poles cl D (Code 601015)		1				

## BILL OF QUANTITIES AND COST ESTIMATES FOR TWAFUNDONG RURAL ELECTRIFICATION PROJECT IN NJINIKOM SUB DIVISION, BOYO DIVISION

<u> </u>	DESCRIPTION OF WORKS	UNIT	QTY	SI	SUPPLY			LABO	S & L TOTAL	
ef				U	.P		T.P	U.P	T.P	
_	1x34,4mm2 & 4x25 mm2 MV/LV SIN	GLE PH	IASE	LINE						
0	IN COLUMN TO THE	KM	0.35							
1	Pegging (Code 10000)	M <sup>3</sup>	3	_						
2	Excavation of holes ( Code 100001)	IVI	3				7-2-1	 		
12	S & F U anchor iron (Code 60113)	U	4							
)3		U	5							
)4	S & F Single 11m wooden poles class D (Code 601014)		1200							
05	S & F twin 11m wooden poles class	U	2							
	D (Code 601015)	U	7				Court of			
06	S & F Rigid glass insulator 30kv (Code 601001)	O								
07	S & F 3 Components anchor earth	U	4							
	string (Code 601002)					-				
08	S & F Spindle (Code 601004)	U	7					-		
109	S & F Warning plates DM (Code	U	7							
109	601005)						-	-		
110	S & F Number plate + Numbering	U	7							
110	(Cada 601006)		36	57.5						
111	S & Stringing 34.4 mm <sup>2</sup> Almelecticable (Code 601011)	Livi		346.233				-		
112	= Code	U	4							
112	603001)		4				-			
113	S & F LV Anchoring clamp (Cod	e U	4							
5000000	603004) 4.25 mm² twiste	d LM	3	67.5						
114	ashla (Code 601011)									
115	'41 trooteble end	s U	1							
115	(Code 603011)		-	2		***				
116	Type C earth plug (Code 603007)	U		1	-	-				
117	7 S & F Line tap (Code 3504035)	U		1		- 10				
118	8 Sous Total 100									
20	0 LV SINGLE PHASE LINE	LVA	•	1	T					
20	1 Pegging (Code 10000)	KN M³	50	8	1					
20	2 Excavation of holes (Code 100001)			8						1
20	S & F LV Alignment support (Co 603001)	de O					_			
20	- Tri t - Laring clamp (Co	de U		8						
20	603004)			16						
20	OS & F Single 9m wooden poles cl C (Code 603008)	ass U		10						
-	· · · · · · · · · · · · · · · · · ·	s C U		4						
20	(Code 603009)			20						
2	07 S & F Number plate +	U		20						
	Numbering (Code 601006)	ated I	M	1050.0	)					
2	S & F Stringing 4x25 mm <sup>2</sup> twiscable (Code 601011)						_			
-	Electrical caps with retractable e	nds U		4						
1	(Code 603011)		ī	6	-					
2	Type C earth plug (Code 603007)		,	-						
-	Sous Total 200 65   MUGHEFF DOWN / TWAFUN									5 2024

301	SINGLE PHASE TRANSFOR  S & F 25KVA Transformer (Ref 22 001 050048)		U	1							
302	S & F twin 12m wooden poles	oloss	1				100				
303	D (Code 601015)		U	1							
303	001 050049)		U	1							
304	S & F chain of three insu	ılator	U	1							
305	discharger  S & F Mounting bracket (										
206	001007)	code	U	1					+		
306	S & F Earth plug for mass		U	1	-						
307	S & F 27KV Surge arrestor	(Ref	U	1							
308	[ 21003010007)	0		-							
	Full equipment of single pi station (Ref 22 001 050002)	- 1	Set	1					-		
309	S & F Fuse cutout 2A(Ref 22 050038)	001	U	1				_			
	Sous Total 300					200					
400	SUNDRY EXPENSES										
401	Connection to AES SONEL Netw	a.l. 1			10-2						N.
	(Ref 22 001 050022)	OFK	U	1					1		
402	Clearing and pruning (Code 801002)	I	Km	1		-					
403	Transport and handling mater (Code 2003)	rial 7	Γ/Km	1						. 10 Te	
104	Transport wooden poles (Code 2004)	Г	7/Km	1		_					
105	Contrôl		93-1 I								The
	CONTROL Connection + ENE CAMEROON Subscription (Ref : 009 050001)	EO   U	J	1						19/4	-4
06	Environmental impact notice	L	C								
07	Site installation	Ls		1							1
80	Transport of workers (Code 2005)	Ls		1		+					
	Sous Total 500	-									
	TOTAL WITHOUT TAXES	-									
	VAT	-									
-	AIR	IR %		19.25						-	
		%		2.20						-	
	TOTAL WITH TAXES			OR 5.5							
1	NET PAYMENT the present Cost Estimate at the Sum	-				Efficiency				_	

Ordered the present Cost Estimate at the Sum (Taxes inclusive) of: CFA Francs

## Document N°. 8 SCHEDULE OF SUB-DETAIL OF PRICES

#### SUBDETAILS OF PRICES

DESIGN	output on of execution NATION :	••••••		· · · · · · · · · · · · · · · · · · ·	······················
No	Daily out put		Total quantity	Unit	Duration (
•	Category	No	Daily wage	Days bre	activity  ak  Amount
WORKMAN SHIP				Up	
MAN					B =
R		3-4-516			
× ×					
	TOTAL			12 10	
	TOTAL A				
EQUIPMENT/MECHINES	Туре	No	Daily rate	Days brea	k Amount
WE					
Į,					
PM					
NO.					
11-12-12	TOTAL B				
ño	Туре	Unit	Unit cost	Quantity	Amount
AN					,
E					
MIS					
9					
₹					
_					
RIAL					
ATERIAL					
	OTAL C				
D	IRECT TOTAL COST		A	+B+C	
D G	IRECT TOTAL COST ENERAL SITE EXPENESES			+B+C x%	
D G G	IRECT TOTAL COST ENERAL SITE EXPENESES ENERAL OFFICE EXPENSES		D.	THE RESERVE OF THE PARTY OF THE	
D G G Ni	IRECT TOTAL COST ENERAL SITE EXPENESES ENERAL OFFICE EXPENSES ET COST		D.	x%	
D G G NI RI	IRECT TOTAL COST ENERAL SITE EXPENESES ENERAL OFFICE EXPENSES		D. D:	x% x%	

# Document N°. 9 MODEL CONTRACT

REPUBLIC OF CAMEROON Peace — Work — Fatherland

MINISTRY OF DECENTRALIZATION AND LOCAL DEVELOPMENT

NORTH WEST REGION

**BOYO DIVISION** 

NJINIKOM COUNCIL INTERNAL TENDERS BOARD P.O BOX 01, NJINIKOM TEL: 677669400/677323293/670294650



REPUBLIQUE DU CAMEROUN Paix-Travail-Patrie

MINISTERE DE LA DECENTRALISATION ET DU DEVELOPPEMENT LOCAL

**REGION DU NORD-OUEST** 

DEPARTEMENT DE BOYO

COMMISSION INTERNE DE PASSATION DES MARCHES PUBLICS DE LA COMMUNE DE NJINIKOM B.P. 01, NJINIKOM TEL: 677669400/677323293/670294650

		077007400/677323293/670294650
JOBBING (	ORDER Nº	JO/ NJINIKOM COUNCIL/NCITB/2024 OF 2024
Awarded at COUNCIL	ter OPENED NATION /NCITB/2024 OF/_ DOWN / TWAFUNDO	AL INVITATION TO TENDER N°/ONIT/ NJINIKOM /2024 FOR THE RURAL ELECTRIFICATION OF NG VILLAGES IN NJINIKOM MUNICIPALITY, BOYO OF THE NORTH WEST REGION
Project Owner: To HOLDER:	HE LORD MAYOR NJI	
P.O. Box	, Tel:Fax:	
	/ Nº. at	
	ution of	works:
PLACE :_		
	EADLINE :	() months
AMOUNT IN CF	AF:	
	IAT EVAT VAT (19.25%) AIR (Income tax) (2.2 or Net to be paid	r 5.5%)
FINANCING	: [indicate the source	of financing]
BUDGET HEAD	: [to be completed]	
	SIGINED ON:	O ON: : ON:

Between: hereinafter referred to the
The Government of the Republic of Cameroon, represented by hereinafter referred to the "Contracting Authority"
On the one hand,
And
(enterprise)
PO Box Tel: Fax:
Business Registry No Taxpayer's No
Taxpayer's No, its General Manager, hereinafter referred to as the "Contractor"
On the other hand,
Agree on the following:

#### Summary

Part I: Special Administrative Conditions (SAC)

Part II: Special Technical Conditions (STC)

Part III: Schedule of Unit Prices (SUP)

Part IV: Details or Estimates

Awarded affer OF ENLL MITTO	JO/ NJINIKOM COUNCIL/NCITB/2024 OF 2024  FAL INVITATION TO TENDER N°/ONIT/ NJINIKOM R THE RURAL ELECTRIFICATION OF MUGHEFF DOWN DOM MUNICIPALITY, BOYO DIVISION OF THE NORTH WES REGION
th,	
or the execution ofworks	
KECUTION DEADLINE(_	months
mount of Contract in CFA F:	
IAT	
EVAT	
VAT (19.25)	
AIR (2.2 or 5.5 %)	
Net to be paid	
Read and accepted by the Contractor	
(place of signature)_	(date)
Signature of Contracting Authority	
(place of signature)_	)(date)
Registration	

# Document N°. 10 FORMS AND MODELS TO BE USED BY BIDDERS

#### TABLE OF MODELS

Annex N° 1: Model of declaration to Tender

Annex N° 2: Model Bid

Annex N° 3: Model Bid Bond

Annex N° 4: Model Final Bond

Annex N° 5: Model Retention fund (Guarantee Retention)

Annex N° 6: Schedule framework

Annex N° 7: Model attestation of site visit

Annex N° 8: Model site visit report

Annex N° 9: Model table of reference

Annex N° 10: Model table of equipment

# Annex N° 1: MODEL OF DECLARATION TO TENDER

# DECLARATION OF THE INTENTION TO TENDER

I the undersigned	
signatory),	(indicate the name and capacity of
rationally	
Representing the	
	company or enterprise or group with head office at
registered in	the trade register of Under the number
box, hereby acknowledg	ge receipt of the file for Opened National Invitation to Tender N <sup>0</sup>
And hereby declare my intention to tender for	
Done at	
	Signature of In the capacity of
	Duly authorized to sign the tenders on behalf of

#### Annex N° 2: MODEL BID

<ul> <li>TWAFUNDONG VILLAGES IN NATIONAL REGION, after having personally taking account of the and under my responsibility, the nature and difficulty of         <ul> <li>Hereby submit, bearing my signature, the sched the structure featuring in the Tender File;</li> <li>Submit and commit myself to execute the work which I myself establish for each type of submit and in words) FCFA inclusive of all taxes.</li> <li>I pledge to execute the works within a deadline</li> <li>I pledge to maintain my offer for a duration of the Contracting Authority shall pay the sums due for the Signing of the Contract, this tender accepted.</li> </ul> </li> </ul>	or mentioned in the Tender file: tender N° For the Electrification of MUGHEFF DOWN /
Done at	
	Signature of  In the capacity of  Duly authorized to sign the tenders on behalf of

### Annex N° 3: MODEL BID BOND

Addressed to the Contracting Authority
Whereas the undertaking
We
The conditions of this commitment are as follows:
If the Bidder withdraws his offer during the validity period specified by the Bidder in the tender; or validity:  Output  Description:
Falls or refuses to sign the contract even the contract
We undertake to pay the Contracting Authority an amount up to the maximum of the sum referred to above upon that in its demand the Contracting Authority shall note that the amount claimed by him is due, because one or the other or both of the above condition(s) has (have) been fulfilled and he shall specify which condition(s) has (have) have the contracting to substantiate his demand, provided other or both of the above condition(s) has (have) been fulfilled and he shall specify which condition(s) has (have) have the contract (final bond) as provided for by the contract.
submission of tenders. It shall remain valid up till the thirtieth day inclusive following the end of the deadline for the validity of tenders. Any request by the Contracting Authority to cause it to take effect should reach the bank by registered mail with an acknowledgement of receipt before the end of this period of validity
This bond shall, for purposes of its interpretation, be submitted to Cameroon law. Cameroon courts shall be the only jurisdictions competent to rule on this commitment and its consequences.
Signed and authenticated by the bank
at, on

#### Annex N° 4: MODEL FINAL BOND

Bank:  Reference of the Bond N°:
Addressed to The Mayor of Njinikom Council "Contracting Authority"
Whereas
Whereas we have agreed to provide the Contractor with this guarantee; We,
We hereby agree that no change or addendum or any other amendment shall release us of any obligation incumbent onus by virtue of this bond and we hereby derogate by the present to the notification of any amendment, addendum or change.
This bond shall enter into force upon signature. It shall be released within thirty (30) days from the date of the Provisional Reception of the works.
After this date the caution shall no longer be valid and shall be returned to us without any request on our part.
Any request for payment formulated by the Contracting Authority by virtue of this bond should be done by registered mail with acknowledgement of receipt to reach the bank during the period of validity of this commitment.
This bond shall, for purposes of its interpretation and execution, be subject to Cameroon law. Cameroon courts shall be the only jurisdictions competent to rule on this pledge and its consequences.
Signed and authenticated by the bank at on

# Annex N° 5: MODEL OF PERFORMANCE BOND (GUARANTEE RETENTION)

	Bank: Reference of the Bond No:
	Addressed to The Divisional Delegate of Public Contracts for Boyo Hereinafter referred to as "The Contracting Authority"
	Whereas
	Whereas it is stipulated in the Contract that the Guarantee Retention fixed at ten percent (10%) of the amount of the Contract may be replaced by a joint guarantee;
	Whereas we have agreed to provide the Contractor with this guarantee; We,
	Hence, we hereby affirm that on behalf of the Contractor, we guarantee and are responsible to the Contracting Authority for a maximum amount of
	And we pledge to pay to the Contracting Authority within a maximum deadline of eight (8) weeks upon his simple written request declaring that the contractor has not fulfilled his contractual obligations or is indebted to the Contracting Authority within the meaning of the contract, amended where need be, by its additional clauses, without equal to ten percent (10%) of the total amount of the works featuring in the final detailed account, without the Contracting Authority having to prove or give the reasons nor the motive for the amount of the sum indicated above.
	We hereby agree that no change or addendum or any other amendment shall release us of any obligation incumbent onus by virtue of this bond and we hereby derogate by the present to the notification of any amendment, addendum or change.
	This bond shall enter into force upon signature. It shall be released within thirty (30) days from the date of the final acceptance of the works and upon released issued by the Contracting Authority.
ŀ	Any request for payment formulated by the Contracting Authority by virtue of this bond should be done by registered mail with acknowledgement of receipt to reach the bank during the period of validity of this commitment. This bond shall, for purposes of its interpretation and execution, be subject to Cameroon law. Cameroon courts shall be the only jurisdictions competent to rule on this pledge and its consequences.
S	Signed and authenticated by the bank at

#### ANNEX N° 6: SCHEDULE FRAMEWORK

Note on the presentation of schedules

The quantities, daily outputs, the duration of execution of works and the slowdowns or even the due interruptions must be clearly brought out in the schedules.

The financial schedules resulting from the schedules of works must indicate month by month, the estimated amounts of the detailed accounts of works by item and cumulatively by taking into account the incidence of rainy seasons for the basic solution and possibly variant solution.

## Annex Nº 7: MODEL ATTESTATION OF SITE VISIT

#### LETTER HEAD HERE

TO WHOM IT MAY CONCERN

#### ATTESTATION OF SITE VISIT

This is to testify that Mr	
Managar/Technic 175	
Manager/Technical Director/Engineer of	
Has effectively visited the site for	
in view to tender for the said project.	
This attestation is issued to serve the purpose for which it is intended for.	
The Beneficiary	: Entrepreneur
	zini opi ciicui

# Annex N° 8: MODEL SITE VISIT REPORT

INTRODUCTION TENDER N <sup>0</sup>				
NAME OF THE ENTERPRISE:				
DATE:				
COMMENTARY				
Nature of the project site:				
Accessibility to the project site:				
Vegetation:				
Topography of the site:				
AVAILABILITY OF SERVICES				
AVAILABILITY OF MATERIALS				
DIFFICULTIES				
CONCLUSION				
	Sig	nature of the	contractor	s' engine

# Annex N° 9: MODEL TABLE OF REFERENCE LIST OF ELECTRIFICATION PROJECTS EXECUTED BY THE COMPANY

Νo	YEAR	NAME OF THE PROJECT	NAME OF THE PROJECT OWNER AND TELEPHONE NUMBER	ORIGINAL PROJECT AMOUNT	CONTRACT AMOUNT	CONTRACT DURATION	DATE OF ACCEPTANCE
							POLIST EL PLES
					-		
						itania a i	

DONE ON	grand and a second a second and
Mr	AT
SIGNATURE	AT

#### Annex N° 10: MODEL TABLE OF EQUIPMENT

## LIST OF EQUIPMENT AND MATERIALS AVAILABLE FOR THE

(project name).....

No	DESIGNATION OF THE EQUIPMENT	DERDMINMAPRIPTION, MARK	AGE AND STATE	NUMBER AVAILABLE	OWNER OR NOT
	EQUIT MEITH				
			F		

DONE ON	
Mr	
SIGNATURE	

ANNEX No. 6: Framework of schedules

No	Daily out put		Total quantity	Unit	Duration activity
	Category	No	Daily wage	Days break	Amount
				96	
E					
Z					
WORKMAN SHIP					
8					
>					
	TOTAL A				
S					value mit
EQUIPMENT/MECHINES	Туре	No	Daily rate	Days break	Amount
표				up	CONTROL CARLOS DAS ASSUME
¥.					
Ä					
<u>P</u>					
Ø					
	TOTAL B				
D MISCELLANOUS	Туре	Unit	Unit cost	Quantity	Amount
A					
핊					
VISC					
٥					
MATERIAL AN					
Ι¥Γ					
표					
AA	TOTAL C				
	DIRECT TOTAL COST		1.	11212	
	GENERAL SITE EXPENESES			A+B+C	
	GENERAL OFFICE EXPENSES			0x%	
	NET COST			0x% 0+E+F	
	RISK + BENEFITS			9x%	
	TOTAL COST (HT)			9+H	
	UNIT COST (HT)			/Q'TY	

# Document N°. 11 PRELIMINARY STUDIES

#### Note on preliminary studies

In accordance with the Public Contracts Code, the Project Owner or Delegated Project Owner must, prior to commencing the procedure to award Contracts or refer to the competent Tenders Board, ensure that draft Tender Files are prepared based on preliminary studies.

These studies must be required during the examination of the Tender File (TF) by the Tenders Board.

The Project Owner is bound to fill the questionnaire in annex 1 accompanied by justifications of the said studies.

### Annex N°. 7: Justification of preliminary studies

- 1. Attach the preliminary studies.
- 2. Indicate
  - 1.1. The date studies were carried out;
  - 1.2. The name of the Public or private Project Manager
  - 1.3. References of the Contract, if Private Manager carried it out;
- 1.4. If maintenance works
  - 1.1.1. Description of the studies;
  - 1.1.2. Attach the outline of the itinerary bringing out readings of degradations as well as the approved programming documents.
- 5.5. Rehabilitation or new works
  - 1.1.3. Are quantities in the quotations the same as those of the studies?
  - 1.1.4. Description of studies: Draft Preliminary Study, Detailed Preliminary Study;
  - 1.1.5. Attach the said studies.
- N.B. For services of less scope, the Project Owner may furnish a justification of calculation of quantities of the Tender File.
- -1 The chairperson of the Tenders Board may, before taking a decision, seek expert advice on the quality of the studies.

# Document N°.12

LIST OF BANKING ESTABLISHMENTS AND FINANCIAL BODIES AUTHORISED TO ISSUE BONDS FOR PUBLIC CONTRACTS

#### I- BANKS

Afriland First Bank

Banque Atlantique

Banque Gabonaise pour le Financement International (BGFI BANK)

Banque International du Cameroun pour l'Epargne et le Crédit (BICEC)

CITI Bank

Commercial Bank of Cameroon (CBC)

Ecobank

National Financial Credit Bank

Société Camerounaise de Banque au Cameroun

Société Générale Cameroun

Standard Chartered Bank Cameroon

Union Bank of Cameroon

United Bank for Africa.

#### II- Insurance companies

Chanas Insurance

Activa Insurance

Zenithe Insurance SA BP Douala

#### **EVALUATION GRID**

\_/ONIT/ NJINIKOM COUNCIL/NCITB/2024 OF \_\_/\_\_/2024 Opened National Invitation to Tender No FOR THE RURAL ELECTRIFICATION OF MUGHEFF DOWN VILLAGE IN NJINIKOM SUB DIVISION, **BOYO DIVISION** 

#### ADMINISTRATIVE DOCUMENTS.

DOCUMENT N°	DESCRIPTION	YES OR NO
OCCUMENTA	not more than three months old.	
A.1	Certified Copy of the Business Registration, not more districted written by the bidder).	
A.2	Certified Copy of the Business Registration, not more than three means the bidder).  Declaration of intention to tender stamped with the tariff in force (written by the bidder).	
A.3	Declaration of intention to tender stamped with the tark interest.  Certificate of non-bankruptcy established by the Court of 1st instance or the Chamber Commerce, Industry and Trade of the place of residence of the bidder, not more than three (03) months.	
A.4	Attestation of bank account of the bidder, issued by a first rate-bank approved by the Ministry in charge of Finance or by a foreign bank the first order not more than three months.	
	Purchase receipt of Tender File issued by NJINIKOM COUNCIL treasury  Purchase receipt of Tender File issued by NJINIKOM COUNCIL treasury	2322
A.5		
A.6	approved by the Ministry in charge of Finance in comorning	
	N.B. 440 000 CFA for TWAFUNDONG  An attestation of non-exclusion from Public Contracts issued by the Public Contract Regulatory	
A.7	An attestation of non-exclusion from Fuone Confidence issues is	
A.1	Board (ARMP)  Board (ARMP)  Fund stating that the bidder has met all his	
A.8	Board (ARMP)  An Attestation of the National Social Insurance Fund stating that the bidder has met all his obligations vis a vis the Fund; the attestation should be less than three months old.	
A.8		
A.9	A valid Certificate of imposition certified by the chief of center of Taxes, not more than three	
A.10	A valid Certificate of imposition certified by the chief of center of Taxes, not more than three Business License (photocopy certified by the chief of center of Taxes, not more than three months).	
	of a valid toxpayers card delivered by the chief of center of Taxes.	
A.11	the Comment of Lover that the Dillich has met an	
A.12	A Clearance Certificate signed by the chief of Centre of Taxes that the bidder has met all the statutory declarations in issues of taxes in the current financial year; this certificate should be less than three months old.	
A.13		
A.14	Power of attorney if necessary  Plan and attestation of localization of Company signed by the Chief of Taxation	
100000000000000000000000000000000000000	Attestation of non faillite	
A.15	ruestation of non-	

The absence or the nonconformity of the one of these documents will result to the elimination of the offer The second Internal Envelope shall be labeled << ENVELOPE B: TECHNICAL DOCUMENT>> and shall contain the following:

YES	NO
1	
ir	
_	
	YES

Man-41 = :	
- More than 5 years' experience	
- 3 years' experience	
- Less than 2 years' experience	
- Attestation of availability of Engineer	
Higher technician:	
- More than 5 years' experience	
- 3 years' experience	-
- Less than 3 years' experience	
- Attestation of availability of Higher Technician	
reclinician;	
- More than 5 years' experience	
- Less than 5 years' experience	
- Attestation of availability of Technician-Certified true copies of the certificates of personnel +	
attestation of presentation of originals	
- Curriculum Vitae of personnel involved in the project	
• References of the Enterprise in the domain of Electricity.  Certified true copies of the Jobbing Order and the minutes of the Final or Provisional Acceptance of electrical energy supply project(s) realized by the Enterprise, if any  - More than Two Final or Provisional Acceptance Reports  - Two Final or Provisional Acceptance Reports  - One Final or Provisional Acceptance Report  Certified true copies of Jobbing Orders or Contracts of Electrification Projects realized by the Enterprise:  More than two (02) projects  At least two (02) projects  One (01) project only  Have you constructed a medium voltage three-phase line (proof- PV+Tech acceptance)?  Two kilometres  Less than One kilometre  Have you constructed a medium voltage single-phase line (proof-PV+Tech acceptance)?  More than Three kilometres  Three kilometres  Three kilometres  More than Two kilometres  Less than or equal to Two kilometres	
Equipment of the Enterprise	
Certified true copies of vehicle documents signed not make the	
List of key equipment and proof of ownership or hired (yard truck, electric	
ill, engine saw, GPS device, climbers, spades, dig axes, drill, service cord, set of screws ivers, pegging markers, fork, signalling cones, pliers.)	
ivers, pegging markers, fork, signalling cones, pliers.)	
Methodology for executing the sund.	
Detailed technical description of the works.	
Detailed technical description of the works to be executed, in conformity with execution	
Organizational chart of the project	
ranpower deployment schedule	
xecution timeframe with a maximum deadline of four (04) months	
and the state of four (04) months	
cceptable planning	
Senuine Report of Worksite	

#### ENVELOPE C- FINANCIAL FILE

No.	DESIGNATION.
C1	A submission letter, signed, dated and stamped.(see ANNEX 3)
C2	1 1 Company of unit prices
C3	Completed and signed frame work of thirt prices.  Signed Bills of quantities and cost estimates indicating the total amount without taxes (HT) and with taxes (TTC)
C4	Sub details of unit prices

This evaluation will be done in a purely positive way (yes) or negative (no) with an acceptable minimum from at least 37/43 (85%) of the essential criteria taken in account.

The Contract will be awarded to the bidder who would have proposed the offer with the lowest amount, in conformity with the regulations of the Tender Documents and having satisfied to 100% of the eliminatory criteria and at least 37/43 (85%) of the essential criteria.

#### Eliminatory criteria

Absence or non-conformity of an element in the administrative file;

Deadline for delivery higher than prescribed;

False declaration or falsified documents;

Absence or insufficient bid bond;

A bid with the external envelope carrying a sign or mark leading to the identification of the bidder;

Incomplete financial file.

Non respect of 37/43 (85%) of essential criteria

Change of quantity or unit

Non completion of any project in the previous year in the Country and suspended by MINMAP in 2017

#### Essential criteria

General presentation of the Tender Files;

Financial capacity;

References of the company in similar achievements;

Quality of the personnel;

Technical organization of the works;

Safety measures on the site;

Logistics;

Attestation and report of site visit;

Special Technical Clauses initialed in all the pages;

Special Administrative Clauses completed and initialed in all the pages.


#### 11. Main qualification criteria

The criteria relating to the qualification of candidates could be indicative on the following:

The essential criteria are subjected to minima whose detail is given in the Special Tender Regulation (RPAO).

This evaluation will be done in a purely positive way (yes) or negative (no) with an acceptable minimum from at least 37/43 (85%) of the essential criteria taken in account.

The Contract will be awarded to the bidder who would have proposed the offer with the lowest amount, in conformity with the regulations of the Tender Documents and having satisfied to 100% of the eliminatory criteria and at least 37/43 (85%) of the essential criteria.



C.P.R

Department SERVICE OPERATION : 5832100
TWAFUNDONG
GESTIONNAIRE : MAIRE TYPE OPERATION : 523415 - Centrales électriques et installations de distribution de l'éléctrictité 2004 Designation de L'acte de Déparse L'AUTORISATION DE DEPENSE DESIGNEE CI-DESSUS VOUS A ETE ATTRIBUEE AUTORISATION DE DEPENSE **AUTORISATION** Description of operation 05/02/2024 CREDIT 5832100705 - ELECTRIFICATION RURALE DU VILLAGE DE POSTE COMPTABLE ASSIGNATAIRE DIRECTION GENERALE DU BUDGET C549 - Commune de Njinikom RECORD NUMBER NUMERO DE L'ACTE 58 IZ05180 32 137 01 641644 464211 851 COMMUNE DE NJINIKOM Transferts aux communes IMPUTATION CHARGE Détails : MONTANT 22 000 000 22 000 000 AMOUNT

Name of accredited authority:

0,00

Account cambrol starn

ACS CA

ade dolt être annué : berrer la case 1 e operation has been cancelled cross out the spece

Y AURA - T-IL D'AUTRES

REGLEMENTS 7

{OUI

NON Z

> BARRER EN CROOK LA CASE INVINCE

CROSS OUT WHERE

BARRER EN CHOIX CHOSS OUT WHERE LA CASE INUTILE

O.H.P A.O.T.

Toma S

OTHER PAYMENTS ? WILL THERE BE ANY

son cours normal: barrer la case 0 has been normally executed cross out

0

INAPPLICABLE

REFERENCE OF INVOICE

MONTANT LIQUIDE OU ANNULE AMOUNT IN CASH OR CANCELED

MONTANT AMOUNT

Onthe

Direction Générals du Budget MINISTERE DES FINANCES REPUBLIQUE DU CAMEROUN PAIX - TRAVAIL - PATRIE

11

Code

NATURE OF PRESENT VOUCHER

NATURE DE LA PRESENTE PIECE

DESTINATAIRE ADRESSEE MINEE

> P.O.Box B.P.

\*\*\*\*

PROBMIS
Programme Budget Management Info

DELEGATION AUTOMATIQUE Mode de réglament demande Manner of payment C POSTAL CHEQUE CASH VOUCHER BOM DE CATUSE BARQUE BANK CCC Compts nº Account n Branch

General Directorate of Budget PEACE - WORK - FATHERLAND REPUBLIC OF CAMEROON MINISTRY OF FINANCE

5



C.P.R GESTIONNAIRE : Department TYPE OPERATION : 523415 - Centrales électriques et installations de distribution de SERVICE l'éléctrictité OPERATION 2004 Code \*\*\* L'AUTORISATION DE DEPENSE DESIGNEE CI-DESSUS VOUS A ETE ATTRIBUEE Designation de L'acte de Déponse NATURE OF PRESENT VOUCHER NATURE DE LA PRESENTE PIECE AUTORISATION DE DEPENSE Description of operation RECORD NUMBER AUTORISATION 05/02/2024 CREDIT MAIRE 5832100705 - ELECTRIFICATION RURALE DE MUGHEFF DOWN POSTE COMPTABLE ASSIGNATAIRE DIRECTION GENERALE DU BUDGET C549 - Commune de Njinikom NUMERO DE L'ACTE 58 32 137 01 641644 464211 851 IZ05179 Transferts aux communes COMMUNE DE NJINIKOM DESTINATAIRE ADRESSEE MINEE IMPUTATION Détails : CHARGE EGATION AUTOMATIQUE 20 000 000 MONTANT 20 000 000 AMOUNT P.O.Box 7 9 Rom de l'autorité accréditée Name of accredited authority : Si l'acte doit être ennulé : berrer la cese † if the speration has been cancelled cross out the space Si facte a suivi son cours normal : barner la case 0
If the operation has been normally executed cross out Signature REFERENCE DE LA FACTURE REFERENCE OF INVOICE C Y AURA - T-IL D'AUTRES MONTANT LIQUIDE OU ANNULE AMOUNT IN CASH OR CANCELED OTHER PAYMENTS ? WILL THERE BE ANY REGLEMENTS 7 POSTAL CHEQUE CASH VOUCHER BANQUE BANK BON DE CAMBE O.H.P AOT 200 YES Compte nº Account n° 9 Visa comptable essignateir Tom Branch Chabi Nema NON ZO Carnoscation 0 MONTANT AMOUNT Account control INAPPLICABLE CHOSS OUT WHERE BARRER EN CROX BARRER EN CROIX RANCS CFA INAPPLICABLE

Direction Générale du Budget MINISTERE DES FINANCES REPUBLIQUE DU CAMEROUN PAIX - TRAVAIL - PATRIE

Coos

Programme Budget Management Information System PROBMIS

DEL

General Directorate of Budget REPUBLIC OF CAMEROON
PEACE - WORK - FATHERLAND MINISTRY OF FINANCE

