

REPUBLICUE DU CAMEROUN  
-----  
PAIX – TRAVAIL – PATRIE  
-----  
REGION DU NORD- OUEST  
-----  
DEPARTEMENT DU DONGA MANTUNG  
-----  
COMMUNE DE NDU  
-----  
COMMISSION INTERNE DE PASSATION  
DES MARCHES



REPUBLIC OF CAMEROON  
-----  
PEACE – WORK – FATHERLAND  
-----  
NORTH WEST REGION  
-----  
DONGA MANTUNG DIVISION  
-----  
NDU COUNCIL  
-----  
INTERNAL TENDERS BOARD

## TENDER FILE

PROJECT OWNER:

THE MAYOR OF NDU

CONTRACTING AUTHORITY:

THE MAYOR OF NDU

TENDERS BOARD:

NDU COUNCIL INTERNAL TENDER'S BOARD (NCITB)

OPEN NATIONAL INVITATION TO TENDER  
Nº ~~06~~/ONIT/NWR/DMD/NC/NCITB/2026 OF THE ~~20/01/~~2026 FOR  
THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN  
NTABA MARKET IN NDU SUB DIVISION DONGA MANTUNG  
DIVISION, NORTH WEST REGION

(EMERGENCY PROCEDURE)

FINANCING: MINCOMMERCE PUBLIC INVESTMENT BUDGET (PIB) - 2026

EXPENDITURE AUTHORIZATION N°

-----  
VOTE OF CHARGE N°

-----  
2026 FISCAL YEAR

## TABLE OF CONTENTS

Document No. 1:	Tender notice
Document No. 2:	General Regulations of the invitation to tender
Document No. 3:	Special Regulations of the invitation to tender
Document No. 4:	Special Administrative Conditions
Document No. 5:	Special Technical Conditions
Document No. 6:	Schedule of unit prices
Document No. 7:	Bill of quantities and estimates
Document No. 8:	The sub-detail of prices
Document No. 9:	Model contract
Document No. 10:	Model documents to be used by bidders
Document No. 11:	Annexes
Document No. 12:	List of banking establishments and financial bodies authorized to issue bonds for public contracts
Document No. 13:	WORKING PLANS

REPUBLICUE DU CAMEROUN

PAIX – TRAVAIL – PATRIE

REGION DU NORD- OUEST

DEPARTEMENT DU DONGA MANTUNG

COMMUNE DE NDU

COMMISSION INTERNE DE PASSATION  
DES MARCHES



REPUBLIC OF CAMEROON

PEACE – WORK – FATHERLAND

NORTH WEST REGION

DONGA MANTUNG DIVISION

NDU COUNCIL

INTERNAL TENDERS BOARD

DOCUMENT No 1  
**TENDER NOTICE**

**OPEN NATIONAL INVITATION TO TENDER N° ~~10~~/ONIT/NWR/DMD/NC/NCITB/2026 OF  
THE ~~20101~~2026 FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN  
NTABA MARKET IN NDU SUBDIVISION, DONGA MANTUNG DIVISION, NORTH WEST  
REGION**

**1) SUBJECT OF THE INVITATION TO TENDER:** Within the framework of the execution of the 2026 state budget, the State of Cameroon represented by the Mayor of Ndu Council hereby launches an open national invitation to tender for the construction of a market shed with 10 stores in Ntaba market in Ndu Subdivision, Donga-Mantung Division, North West Region.

**2) NATURE OF SERVICE:** Work to be done consists of:

- Preparatory works
- Earth works
- Foundation
- Wall masonry (elevation)
- Carpentry-roof works
- Joinery/Metals
- Electricity
- General finishing
- Plumbing and Sanitary fittings
- Painting
- General rain water drainage (External works)

**3) DURATION OF EXECUTION:** The maximum duration for the execution provided for by the Contracting Authority shall be **four months** (120 calendar days) with effect from date of notification of the Administrative Order to start works.

**4) LOTS:** The work is in one (1) lot as follows; - construction of a market shad and 10 stores in Ntaba market in NDU Subdivision, Donga-Mantung Division, North West Region

**5) ESTIMATED COST:** The estimated cost after preliminary studies is Forty-eight million (48 000 000) fcfa

Subject	Amount for the Project	Vote of charge N°	Expenditure authorization N°
The Construction of a market shed and 10 stores in Ntaba market.	48 000 000 FCFA		AWAITING CREDIT CARD

**6) PARTICIPATION AND ORIGIN:** Participation in this invitation to tender is open to competent Cameroonian enterprises that are in compliance with the fiscal laws and who are not currently excluded from public procurement.

**7) FINANCING:** The said works shall be financed as per the programmed budget of the 2026 Public Investment Budget (PIB 2026) of the Republic of Cameroon under the Ministry of COMMERCE assigned to the Mayor of NDU Council.

**8)-BID BONDS:** Each bidder must include in his administrative documents, a bid bond issued by a first-rate banking establishment approved by the Ministry in charge of finance - the list of which is found in document No. 12 of the Tender File, and validated by CDEC in the amount of **Nine hundred and sixty thousand (960,000) francs CFA**, and valid for thirty (30) days beyond the deadline of validity of bids.

**9) CONSULTATION OF TENDER FILE:** The Tender documents may be consulted immediately after publication of this invitation to tender from the Services of the Contracting Authority (Service in charge of the award of contracts of NDU Council), the COLEPS platform and the ARMP website

Subject	Locality	Bid Bond	Tender fee
Construction of a market shad and 10 stores in Ntaba market in NDU Subdivision	Ntaba, NDU Subdivision Division	960,000 fcfa	96,000fcfa

**10) ACQUISITION OF TENDER FILE:** The Tender file may be obtained from the Premises of the Contracting Authority (Service of Contracts award) of NDU Council as soon as this notice is published against payment of a non-refundable sum of Forty thousand (96,000Fcfa), CFA francs, and payable at Municipal Treasury of NDU.

**11) SUBMISSION OF BIDS:** Each bid written in English or French shall be signed by the bidder or by a duly authorized representative and presented in Seven (7) copies, that is one (01) original and six (06) copies labelled as such. These shall be submitted in one external envelope - sealed, containing three (3) internal envelopes, that is, Envelope A: Administrative Documents, Envelope B: Technical file and Envelope C: Financial file, an electronic version of the bids must be included in the envelope. The sealed external envelope shall bear no information about the company and shall reach the Service of contracts award of NDU Council not later than the ~~10/01/2026~~ at 10am local time and note should be taken that in case of any ambiguities or differences during opening, only the original shall be considered authentic. The sealed pack shall bear the following inscriptions:

**OPEN NATIONAL INVITATION TO TENDER No. ~~06~~/ONIT/NWR/DMD/NC/NCITB/2026, OF THE ~~20/01/2026~~ FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**  
*(To be opened only during the bids opening session)*

**12) ADMISSIBILITY OF BIDS:** At the risk of being rejected, only originals or certified true copies by the issuing service or administrative authorities (Senior Divisional Officer, Divisional Officers) must imperatively be produced in accordance with the Special Regulations of this Invitation to Tender. They must not be more than three (3) months old as at the date of submission of bids or must not be established before the signature of the tender notice. Any bid not in compliance with the prescriptions of the Tender File shall be declared inadmissible. This refers especially to the absence of a bid bond issued by a first-rate bank approved by the Minister in charge of Finance or its non-compliance.

**13) OPENING OF BIDS:** The bids shall be opened in a single phase, in the conference hall of NDU COUNCIL, on ~~10/01/2026~~ at 11:00am. Only bidders or their authorized representatives, having a perfect knowledge of the file may attend the bids opening session. Any bid which shall not comply with the requirements of the Tender File shall be rejected.

**14) Evaluation criteria:** The evaluation of bids shall be carried out in three stages:

- 1<sup>st</sup> Stage : verification of the conformity of each administrative document ;
- 2<sup>nd</sup> Stage : Evaluation of technical bids ;
- 3<sup>rd</sup> Stage: Analyses of Financial bids.

The criteria of evaluation shall be as follows:

#### 14.1-Eliminatory criteria

- Absence of a document in the administrative file and not submitted within 48hrs on request;
- Bids submitted after the deadline for submission;
- Deadline of execution more than the prescribed;
- False declaration or falsified documents;
- External envelope bearing identification marks of the Bidder;
- Absence of, or insufficient or non-compliance bid bond;
- Omission of a quantified task on the bill of quantities and cost estimates
- Enterprises suspended from public procurement
- Failure to obtain at least 75% in the evaluation of the technical proposal.

**14.2. Main Qualification criteria:** The criteria relating to the qualification of candidates could indicatively be on the following:

- Financial situation
- Experience
- Personnel
- Equipment.
- Methodology/organization of the site

**15) Award:** The evaluation will be done in a purely binary manner - (yes) or (no). The contract shall be awarded to the bidder who would have obtained a minimum technical score of 75% in the essential criteria and 100% in the eliminatory criteria, taken in consideration and who would have proposed a bid with the lowest amount, in conformity with the regulations of the tender documents


16) DURATION OF TENDER VALIDITY: Bidders shall remain committed to their offers for a period of ninety (90) days from the last date of the submission of tenders, that is, the tenders shall be valid for 90 (ninety) days with effect from their submission deadline.

17) FURTHER INFORMATION: Additional (supplementary) technical information may be obtained during working hours from the service for the award of contracts at the NDU Council, tel: 670 39 48 72

18) AMENDMENT TO THE INVITATION TO TENDER: The Contracting Authority reserves the right, if need be, to subsequently amend this invitation to tender in conformity with the Public Contracts Code.

Ndu, the.....  
20 JAN 2026

THE MAYOR  
(Contracting Authority)



*Abba Kankon Borno*  
PROFESSEUR DES LYCÉES D'ENSEIGNEMENT GÉNÉRAL  
(PLEG)

Copies:

- MINMAP
- ARMP
- DD MINCOMMERCE
- Chairperson of NCITB
- File/Chrono
- Notice Boards

REPUBLICHE DU CAMEROUN

PAIX – TRAVAIL – PATRIE

REGION DU NORD- OUEST

DEPARTEMENT DU DONGA MANTUNG

COMMUNE DE NDU

COMMISSION INTERNE DE PASSATION  
DES MARCHES



REPUBLIC OF CAMEROON

PEACE – WORK – FATHERLAND

NORTH WEST REGION

DONGA MANTUNG DIVISION

NDU COUNCIL

INTERNAL TENDERS BOARD

DOSSIER No. 01

### AVIS D'APPEL D'OFFRES

AVIS D'APPEL D'OFFRES NATIONAL OUVERT No. 01 /AONO/NWR/DMD/NC/NCITB/2026 DU 20/01/2026, POUR LES TRAVAUX DE CONSTRUCTION D'UN HANGAR ET 10 BOUTIQUE AU MARCHE DE NTABA DANS L'ARRONDISSEMENT DE NDU, DEPARTEMENT DU DONGA-MANTUNG, REGION DU NORD-OUEST.

#### (PROCEDURE D'URGENCE)

1) OBJET DE L'APPEL D'OFFRES : Dans le cadre de l'exécution du Budget d'Investissement Public 2026, l'Etat de Cameroun représenté par, le Maire de Ndu lancé un Appel d'Offres national ouvert pour les travaux de CONSTRUCTION D'UN HANGAR ET 10 BOUTIQUE AU MARCHE DE NTABA DANS L'ARRONDISSEMENT DE NDU, DEPARTEMENT DU DONGA-MANTUNG, REGION DU NORD-OUEST

2) Consistance des travaux : Les travaux comprennent notamment :

- Travaux préparatoires
- Terrassement
- Fondations
- Maçonneries en élévations
- Charpente-couverture
- Menuiserie métallique
- Menuiserie bois
- Electricité
- Peinture et Revêtement
- VRD

3) DUREE D'EXECUTION : Le délai prévu pour l'achèvement des travaux du présent appel d'offre est de Cent-vingt (120) jours continus (04 mois) à partir du jour de la notification de l'ordre de service de démarrage des travaux.

4) Allotissement : Les travaux sont en un (01) lots ci-après définis : Construction d'un entrepôt d'agriculteur à Ntaba dans l'arrondissement DE NDU, Département du Donga-Mantung, Region du Nord-Ouest

5) Coût prévisionnel : Le coût prévisionnel de l'opération à l'issue des études préalables est de ;

Projet	Localité	coût prévisionnel	Achat DAO
CONSTRUCTION D'UN HANGAR ET 10 BOUTIQUE AU MARCHE DE NTABA	Ntaba, dans l'arrondissement DE NDU,	48,000,000fcfa	96,000fcfa

6) Participation et origine : La participation à cette consultation est ouverte aux entreprises de droit camerounais ayant une expérience avérée dans le domaine concerné et ayant réalisées des opérations similaires.

7) FINANCEMENT : Les travaux, objet du présent appel d'offres sont financés par le Budget d'Investissement Public de la République du Cameroun, Budget du MINCOMMERCE au titre de l'exercice 2026 assigné au Maire de Ndu, sur la ligne d'imputation budgétaire.

Objet	coût prévisionnel	N° de l' Imputation	N° de l'autorisation de dépense	cautionnement
CONSTRUCTION D'UN HANGAR ET 10 BOUTIQUE AU MARCHE DE NTABA	48,000,000 FCFA			960,000fcfa

8).CAUTIONNEMENT PROVISOIRE: Chaque soumissionnaire doit inclure dans ses documents administratifs, une garantie de soumission qui respecte le modèle prescrit dans le DAO établi par un établissement bancaire agréé par le Ministère en charge des Finances d'un montant égal à 960,000F (neuf cent soixante mille) francs CFA et valide par CDEC. Les cautionnements provisoires seront libérés au plus

tard trente (30) jours après le délai de validité des offres pour les soumissionnaires n'ayant pas été retenus. Pour le soumissionnaire attributaire du marché, le cautionnement provisoire sera libéré après constitution du cautionnement définitif.

**9) CONSULTATION DU DOSSIER D'APPEL D'OFFRES :** Le dossier d'appel d'offres peut être consulté dès publication du présent avis d'appel d'offre aux services de l'Autorité Contractant (Service de passation des marchés de la marie d'Ndu), le platform COPLEPS et site web de ARMP.

**10) ACQUISITION DU DOSSIER D'APPEL D'OFFRES :** Le dossier d'appel d'offres peut être obtenu dès publication du présent avis d'appel d'offres aux services de l'Autorité Contractant (Service de passation des marchés de la Marie DE NDU) pendant les heures ouvrables contre versement d'une somme non remboursable de **quatre-vingt-seize mille (96,000F) francs cfa**, payable à la Recette Municipale de NDU.

**11) REMISE DES OFFRES :** Chaque offre rédigée en français ou en anglais en Sept (07) exemplaires, c.-à-d. Un original et six copies marqués comme tels sera remise au Service de Passation des Marchés de la marie de Ndu, au plus tard le **10/10/2026 à 10heures**. Il doit être dans un paquet contenant trois enveloppes marquées A : pour le dossier Administratif, B : pour le dossier technique et C : pour le dossier financier. La vaison électronique de l'offre doit être inclure Ce paquet devra porter la mention :

**AVIS D'APPEL D'OFFRES NATIONAL OUVERT No. 06/AONO/NWR/DMD/NC/NCITB/2026 DU 20/10/2026 POUR LES TRAVAUX DE CONSTRUCTION D'UN HANGAR ET 10 BOUTIQUE AU MARCHE DE NTABA DANS L'ARRONDISSEMENT DE NDU, DEPARTEMENT DU DONGA-MANTUNG, REGION DU NORD-OUEST**  
«A N'OUVRIR QU'EN SEANCE DE DEPOUILLEMENT»  
(PROCEDURE D'URGENCE)

**12) RECEVABILITÉ DES OFFRES:** Sous peine de rejet, les pièces du dossier administratif requises doivent être produites en originaux ou en copies certifiées conformes par le service émetteur ou une autorité administrative (Préfet, Sous-préfet,...), conformément aux stipulations du Règlement Particulier de l'Appel d'Offres. Elles doivent dater de moins de trois (03) mois précédent la date originale de dépôt des offres ou avoir été établies postérieurement à la date de signature de l'Avis d'Appel d'Offres. Toute offre incomplète conformément aux prescriptions du Dossier d'Appel d'Offres sera déclarée irrecevable. Notamment l'absence de la caution de soumission délivrée par une banque de premier ordre agréée par le Ministère chargé des Finances ou non conforme.

**13) Ouverture des plis:** L'ouverture des plis se fera le **10/10/2026 à 11heures**, heure locale en une phase par la Commission Interne de Passation des Marchés de la Commune de Ndu, (**Salle de conference de la marie**) en présence de chaque soumissionnaire qui le désire, ou son représentant dûment mandaté et ayant une parfaite connaissance des offres dont il a la charge. Une seule personne par offre remise, seule ou en groupement, sera admise. Les offres qui ne vont pas respecter les prescriptions du DAO seront rejetées. L'ouverture des plis sera faite en une phase.

**14) ÉVALUATION DES OFFRES:** L'évaluation des offres se fera en trois(03) étapes :

- 1<sup>ère</sup> étape : Vérification de la conformité du dossier administratif de chaque soumissionnaire ;
- 2<sup>ème</sup> étape : Evaluation des offres techniques ;
- 3<sup>ème</sup> étape: Analyse des offres financières.

Les critères d'évaluation des offres sont les suivants:

#### 14.1-Critères éliminatoires

- Absence ou non-conformité d'une pièce administrative et non livrée dans 48h sur demande ;
- Un dépôt après la date limite
- Délai d'exécution supérieur à celui prescrit (supérieur à quatre mois) ;
- Fausses déclarations ou pièces falsifiées;
- L'enveloppe avec les signes d'identification du soumissionnaire ;
- Absence ou insuffisance de la caution provisoire de soumission ou non conforme;
- Omission d'un prix quantifié dans le devis
- Entreprise suspendu du procurement public.

Non satisfaction d'au moins 75% des critères d'expériences requis

#### 14.2 Critères essentiels

L'évaluation sera faite sur la base des critères techniques prédéfinis pour une note globale de 100 points. Ces critères ont été groupés par rubriques ainsi qu'il suit:

- Capacité financière ;
- Références de l'entreprise;
- Qualité du personnel postulé;
- Moyens logistiques/equipment ;
- Méthodologie/Organisation des travaux ;

15) **Attribution** : Cette évaluation sera binaire (**OUI ou NON**). Le marché sera attribué au soumissionnaire qui aura proposé l'offre la moins disante, ayant satisfait à 100% des critères éliminatoires et au moins 75% des critères essentiels.

16) **DUREE DE VALIDITE DES OFFRES** : Les soumissionnaires restent tenus par leurs offres pendant quatre-vingt-dix (90) jours à partir de la date limite fixée pour la remise des offres.

17) **Les Renseignements Complémentaires** : Les renseignements complémentaires d'ordre technique peuvent être obtenus aux heures ouvrables au Service de Passation des Marchés de la mairie De Ndu ; tel : 670394872

18) **Additif à l'appel D'offres** : L'Autorité Contractante se réserve le droit, en cas de nécessité, d'apporter toute autre modification ultérieure utile au présent appel d'offres.

Copies :

- MINMAP
- ARMP ;
- DD MINCOMMERCE
- Présidents CIPM ;
- Chrono
- Affichage.

20 JAN 2026  
NDU, le.....

Le Maire  
(AUTORITE CONTRACTANTE)



*Abdou Karim Borno*  
PROFESSEUR DES LYCÉES D'ENSEIGNEMENT GÉNÉRAL  
(PLEG)

# General Regulations of the Invitation to Tender

## CONTENTS

### A. General

- Article 1: Scope of the tender.....
- Article 2: Financing.....
- Article 3: Fraud and corruption.....
- Article 4: Candidates admitted to compete.....
- Article 5: Building materials, supplies, equipment and authorised services...
- Article 6: Qualification of the bidder.....
- Article 7: Visit of site of works.....

### B. Tender File.....

- Article 8: Content of Tender File.....
- Article 9: Clarifications on Tender File and complaints.....
- Article 10: Modification of the Tender File.....

### C. Preparation of Bids

- Article 11: Tender fees.....
- Article 12: Language of bid.....
- Article 13: Constituent documents of the bid.....
- Article 14: Amount of bid.....
- Article 15: Currency of bid and payment.....
- Article 16: Validity of bids.....
- Article 17: Bid bond.....
- Article 18: Varying proposals by bidders.....
- Article 19: Preparatory meeting to the establishment of bids.....
- Article 20: Form and signature of bids.....

### D. Submission of bids.....

- Article 21: Sealing and marking of bids.....
- Article 22: Date and time-limit for submission of bids.....
- Article 23: Out of time-limit bids.....
- Article 24: Modification, substitution and withdrawal of bids.....

### E. Opening and evaluation of bids .....

- Article 25: Opening of bids.....
- Article 26: Confidential nature of the procedure.....
- Article 27: Clarifications on the bid and contact with Contracting Authority.....
- Article 28: Determination of their compliance.....
- Article 29: Qualification of the bidder.....
- Article 30: Correction of errors.....
- Article 31: Conversion into a single currency.....
- Article 32: Evaluation of financial bids.....
- Article 33: National preference.....

### F. Award of the contract.....

- Article 34: Award.....
- Article 35: Right of the Contracting Authority to declare an invitation to tender unsuccessful or to cancel a procedure.....
- Article 36: Publication of results
- Article 37: Notification of the award of the contract.....
- Article 38: Signature of the contract.....
- Article 39: Final bond.....

## A. General

### Article 1: Scope of the tender:

1.1 . The Contracting Authority as defined in the Special Regulations of the invitation to tender hereby launches an invitation to tender for the construction of the works described in the Tender notice and briefly described in the Special Regulations.

1.2 The bidder retained or the preferred bidder must complete the works within the time- limit indicated in the Special Regulations and which time-limit runs from the date of notification of the Administrative Order or that indicated in the said Administrative Order.

1.3 In this Tender File, the term "day" means a calendar day.

### Article 2: Financing: The source of financing of the works forming the subject of this invitation to tender shall be specified in the Special Regulations.

### Article 3: Fraud and corruption:

3.1 The Contracting Authority requires of bidders and contractors the strict respect of rules of professional ethics during the award and execution of public contracts. By virtue of this principle:

a) The following definitions shall be admitted:

a.1 Shall be guilty of "corruption" whoever offers, gives, requests or accepts any advantage in view of influencing the action of a public official during the award or execution of a contract;

a.2 Is involved in "fraudulent manoeuvres" whoever deforms or distorts facts in order to influence the award or execution of a contract;

a.3 "Collusive practices" shall mean any form of agreement between two or among several bidders (whether the Contracting Authority is aware or not) aimed at artificially maintaining the prices of bids at levels not corresponding to those resulting from competition;

a.4 "Coercive practices" shall mean any form of harm against persons or their property or threats against them in order to influence their action during the award or execution of a contract.

b) Any proposed award shall be rejected if it is proved that the proposed preferred bidder is directly or through an intermediary, guilty of corruption or is involved in fraudulent manoeuvres, collusive or coercive practices for the award of this contract.

3.2 The Minister Delegate at the Presidency in charge of public contracts may, as a precaution, take a decision of exclusion from bidding for a period not exceeding two (2) years against any bidder found guilty of influence peddling, of conflicts of interest, insider trading, fraud, corruption or production of non-genuine documents in the bid, without prejudice to criminal proceedings that may be brought against him

### Article 4: Candidates allowed to compete.

4.1 If the invitation to tender is restricted, consultation is addressed to all candidates retained after a pre-qualification procedure.

4.2 Generally, the invitation to tender is addressed to all entrepreneurs, subject to the following provisions:

a. A bidder (including all members of a group of enterprises and all sub-contractors to the bidder) must be from an eligible country, in accordance with the funding agreement.

b. A bidder (including all members of a group of enterprises and all sub-contractors to the bidder) must not be in a situation of conflict of interest, subject to disqualification. A bidder shall be judged to be in a situation of conflict of interest if he:

b.1 Is or was associated in the past with an enterprise (or a subsidiary of this enterprise) which provided consultancy services for the conception, preparation of specifications and other documents used within the scope of contracts awarded for this invitation to tender; or

b.2 Presents more than one bid within the context of invitation to tender, except authorized variants according to article 17, where need be; meanwhile, this does not prevent the participation of sub-contractors in more than one bid.

b.3 The Contracting Authority or Project Owner has financial interests in the capital in a way as to compromise the transparency of the procedures of award of public contracts.

c. The bidder must not have been excluded from bidding for public contracts.

d. A Cameroonian public enterprise may participate in the consultation if it can demonstrate that it is (i) legally and financially autonomous, (ii) managed according to commercial laws and (iii) not under the direct supervisory authority of the Contracting Authority or Project Owner.

### Article 5: Building materials, materials, supplies, equipment and authorized services:

5.1 Building materials, the contractor's materials, supplies, equipment and services forming the subject of this contract must originate from countries meeting the criteria of origin defined in the Special Regulations of the invitation to tender and all expenditure done within the context of the contract shall be limited to the said building materials, materials, supplies, equipment and services.

5.2 Within the meaning of this 5.1 above, the term "originate" shall designate the place where the goods are extracted, cultivated, produced, manufactured and from where the services originate.

**Article 6: Qualification of bidder:**

6.1 As an integral part of their bid, bidders must:

6.1.1 Submit a power of attorney making the signatory of the bid bound by the bid; and

6.1.2 Provide all information (complete or update information included in their request for pre-qualification which may have changed in the case where the candidates took part in pre-qualification) requested of bidders in the Special Regulations of the invitation to tender, in order to establish their qualification to execute the contract.

Where necessary, bidders should provide information relating to the following points:

- (i) The production of certified balance sheets and recent turnovers;
- (ii) Access to a line of credit or availability of other financial resources;
- (iii) Orders acquired and contracts awarded;
- (iv) Pending litigations; and
- (v) Availability of indispensable equipment.

6.2 Bids presented by two or more associated undertakings (joint-contracting) must satisfy the following conditions:

a. The bid must include all the information listed in article 6(1) above. The Special Regulations must indicate the information to be furnished by the group and that to be furnished by each member of the group;

b. The bid and the contract must be signed in a way that is binding on all members of the group;

c. The nature of the group (joint or several) must be specified in the Special Regulations and justified with the production of a joint venture agreement in due form;

d. The member of the group designated as the representative will represent all the undertakings vis à vis the Project Owner and Contracting Authority with regard to the execution of the Contract;

e. In case of joint co-contracting, the co-contractors shall share the sums which are paid by the Project Owner into a single account. On the other hand, each undertaking is paid into its own account by the Project Owner where it is joint co-contracting.

6.3 Bidders must equally present sufficiently detailed proposals to demonstrate that they comply with the technical specifications and execution time-limits set in the Special Regulations of the invitation to tender.

6.4 Bidders requesting to benefit from the margin of preference must furnish all the necessary information to prove that they satisfy the eligibility criteria set in article 33 of the General Regulations of the invitation to tender.

**Article 7: Visit of works site:**

7.1 The bidder is advised to visit and inspect the site and its environs and obtain by himself and under his own responsibility, all the information which may be necessary for the preparation of the bid and the execution of the works. The related cost of the visit of the site shall be borne by the bidder.

7.2 The Project Owner shall authorize the bidder and his employees or agents to enter the premises and the land for the said visit but only on the express condition that the bidder, his employees and agents free the Project Owner, his employees and agents of any responsibility that may ensue and indemnify them if necessary and that they shall remain responsible for any deadly or corporal accident, loss or material damages, costs and fees incurred from this visit.

7.3 The Project Owner may organize a visit of the site of the works during the preparatory meeting to establishing the bids mentioned in article 19 of the General Regulations of the invitation to tender.

**B. TENDER FILE**

**Article 8: Content of Tender File:**

8.1 The Tender File describes the works forming the subject of the contract, sets the consultation procedure of contractors and specifies the terms of the contract. Besides the addendum (addenda) published in accordance with article 10 of the General Regulations of the invitation to tender, it includes the following documents:

Document No. 1. The letter of invitation to tender (for restricted invitation to tender);

Document No. 2. The tender notice;

Document No. 3. The General Regulations of the invitation to tender;

Document No. 4. The Special Regulations of the invitation to tender;

Document No. 5. The Special Administrative Conditions;

Document No. 6. The Special Technical Conditions;

Document No. 7. The schedule of unit prices;

Document No. 8. The bill of quantities and estimates;

Document No. 9. The sub details of unit prices;

Document No. 10. Model documents of the contract:

- The execution schedule;

- Model of forms presenting the equipment, personnel and references;

- Model bidding letter;

- Model bid bond;

- Model final bond;

- Model of bond of start-off advance;

- Model of guarantee in replacement of the retention fund;

- Model contract;

Document No. 11. Models to be used by bidders;

- Model contract;

Document No. 12. Justifications of preliminary studies; to be filled by the Project Owner or Delegated Project Owner;

Document No. 13. List of first grade banking establishments or financial institutions approved by the Minister in charge of Finance authorized to issue bonds for public contracts to be inserted by the Contracting Authority.

8.2 The bidder must examine all the regulations, forms, conditions and specifications contained in the Tender File. It is up to him to furnish all the information requested and prepare a bid in compliance with all aspects of the said file.

#### **Article 9: Clarifications on the Tender File and complaints**

9.1 Any bidder who wants to obtain clarifications on the Tender File may request them from the Contracting Authority in writing or by electronic mail (fax or e-mail) at the Contracting Authority's address indicated in the Special Regulations of the invitation to tender and send a copy to the Project Owner. The Contracting Authority replies in writing to any request for clarification received at least fourteen (14) days prior to the deadline for the submission of bids. A copy of the Contracting Authority's response, indicating the question posed but not mentioning the author, is addressed to all bidders who bought the Tender File.

9.2 Between the publication of the tender notice including the pre-qualification phase of candidates and the opening of bids, any bidder who feels aggrieved in the public contracts award procedure may lodge a complaint to the Minister in charge of Public Contracts.

9.3 A copy of the complaint should be addressed to the Contracting Authority and to the body in charge of the regulation of public contracts and the chairperson of the Tenders Board.

9.4 The Contracting Authority has five (5) days to react. A copy of the reaction shall be forwarded to MINMAP and the body in charge of the regulation of public contracts.

#### **Article 10: Amendment of the Tender File**

10.1 The Contracting Authority may at any moment, prior to the deadline for the submission of bids and for any reason, be it at his initiative or in reply to a request for clarification formulated by a bidder, amend the Tender File by publishing an addendum.

10.2 Any published addendum shall be an integral part of the Tender File, in accordance with article 8.1 of the General Regulations of the invitation to tender and must be communicated in writing or made known by a traceable means to all bidders who bought the Tender File.

In order to give bidders sufficient time to take account of the addendum in the preparation of their bids, the Contracting Authority may postpone as is necessary, the deadline for the submission of bids, in accordance with provisions of article 22 of the General Regulations of the invitation to tender.

### **C PREPARATION OF BIDS**

**Article 11: Tender costs:** The candidate shall bear the costs related to the preparation and presentation of his bid and the Contracting Authority and the Project Owner shall in no case be responsible for these costs nor pay for them whatever the evolution or outcome of the invitation to tender procedure.

**Article 12: Language of bid:** The bid as well as any correspondence and any document exchanged between the bidder and the Contracting Authority shall be written in English or French. Complementary documents and the forms provided by the bidder may be written in another language on condition that a precise translation into either English or French of the passages concerning the bid is included; in which case for reasons of interpretation, the translation shall be considered to be authentic.

#### **Article 13: Constituent documents of the bid**

13.1 The bid presented by the bidder shall include the documents detailed in the Special Regulations of the invitation to tender, duly filled and put together in three volumes:

a. **Volume 1: Administrative file:** It includes:

a.1 All documents attesting that the bidder:

- Has subscribed to all declarations provided for by the laws and regulations in force;
- Paid all taxes, duties, contributions, fees or deductions of whatever nature;
- Is not winding up or bankrupt;
- Is not the subject of an exclusion order or forfeiture provided for by the law in force;

a.2 The bid bond established in accordance with the provisions of article 17 of the General Regulations of the invitation to tender;

a.3 The written confirmation empowering the signatory of the bid to commit the bidder, in accordance with the provisions of article 6(1) the General Regulations of invitation to tender.

b. **Volume 2: Technical bid**

b.1 **Information on qualifications:** The Special Regulations list the documents to be furnished by bidders to justify the qualification criteria mentioned in article 6(1) of the Special Regulations of the invitation to tender.

b.2 **Methodology:** The Special Conditions of the invitation to tender specifies the constituent elements of the technical bid of the bidders especially: a methodological statement on an analysis of the works and specifying the organization and programme which the bidder intends to put in place or use to execute the works (installations, schedule, Quality Assurance Plan (QAP), sub-contracting, attestation of visit of the site, where necessary, etc).

b.3 **Proof of acceptance of conditions of the contract:** The bidder shall submit duly initialed copies of the administrative and technical documents relating to the contract, namely:

- The Special Administrative Conditions (SAC);
- The Special Technical Conditions (STC).

b.4 **Commentaries (optional):** A commentary on the technical choices of the project and possible proposals.

c. **Volume 3: Financial bid:** The Special Regulations specify the elements that will help in justifying the cost of the works, namely:

- The signed and dated original bid prepared according to the attached model, stamped at the prevailing rate;
- The duly filled Unit Price Schedule;
- The duly filled detailed estimates;
- The sub-details of prices and/or breakdown of all-in prices;
- The projected schedule of payments, where need be.

In this regard, the bidders will use the documents and models provided in the Tender File, subject to the provisions of article 17(2) of the General Regulations of the invitation to tender concerning the other possible forms of guarantees.

13.2 If in accordance with the provisions of the Special Regulations of the invitation to tender, the bidders present bids for several lots of the same invitation to tender, they could indicate rebates offered in case of award of more than one lot.

#### **Article 14: Bid price:**

14.1 Except otherwise stated in the Tender File, the amount of the contract shall cover all the works described in article 1.1 of the General Regulations of the invitation to tender, on the basis of the price schedule and the detailed bill of quantities and estimates presented by the bidder .

14.2 The bidder shall fill the unit prices and totals of all items on the schedule and bill of quantities and estimates.

14.3 Subject to contrary provisions provided for in the Special Regulations and in the Special Administrative Conditions, all dues, taxes and fees payable by the bidder on grounds of the contract or on any other ground, thirty (30) days prior to the submission of the bids, shall be included in the prices and in the total amount of the bid presented by the bidder.

14.4 If a price revision/updating clause is provided for in the contract, the date of establishment of the initial price, as well as the price revision/updating conditions for the said price must be specified. This is with the understanding that any contract of duration less than one (1) year shall not be subject to price revision.

14.5 All unit prices must be justified by sub-details established in accordance with the structure proposed in document 8 of the Tender File.

#### **Article 15: Currency of bid and payment**

15.1 In case of international invitations to tender, the currencies of the bid shall follow the provisions of either Option A or Option B below, the applicable option being that retained in the Special Regulations of the invitation to tender.

15.2 **Option A:** The amount of the bid shall be entirely made in the national currency.

The amount of the bid, unit prices of the price schedule and the prices of the bill of quantities and estimates are completely made in CFA francs in the following manner:

- a. Prices shall be entirely drawn in the national currency. The bidder who intends to commit expenditures in other currencies for the execution of the works shall indicate in the annex to the bid the percentage(s) of the amount of the bid necessary to cover the needs in foreign currencies, without exceeding the maximum of the three currencies of member countries of the funding institution of the contract.
- b. The exchange rates used by the bidder to convert his bid into the national currency shall be specified by the bidder in an annex to the bid in compliance with the specifications of the Special Regulations. These rates shall be applied for any payment within the framework of the contract so that the retained bidder does not bear any change in the exchange rate.

**15.3 Option B:** The amount of the bid shall be directly made in the national and foreign currency at the rates fixed in the Special Regulations.

The bidder shall draw the unit prices of the price schedule and the prices of the bill of quantities and estimates in the following manner:

- a. The prices of inputs necessary for the works which the bidder intends to procure in the Contracting Authority's country shall be in currency of the Contracting Authority's country specified in the Special Regulations and called "national currency";
- a. The prices of inputs necessary for works which bidder intends to procure out of the Contracting Authority's country shall be in the currency of the country of origin of the bidder or of the currency of an eligible member country widely used in international trade.

**15.4** The Contracting Authority may request the bidders to explain the needs in national and foreign currencies and to justify that the amounts included in the unit and total prices and indicated in annex to the bids are reasonable; to this end, a detailed statement of their needs in foreign currencies shall be furnished by the bidder.

**15.5** During the execution of the works, most of the foreign currency to be paid as part of contract may be revised by mutual agreement between the Contracting Authority and the entrepreneur in a way as take account of any modification in the foreign currency needs within the context of the contract.

**Article 16: Validity of bids:**

16.1 Bids must remain valid during the period stated in the Special Regulations from the date of submission of the bids fixed by the Contracting Authority, in application of article 22 of the Special Regulations. A bid valid for a shorter period shall be rejected by the Contracting Authority or Delegated Contracting Authority as not being in compliance.

16.2 Under exceptional circumstances, the Contracting Authority may seek the approval of bidders to extend the validity time-limit. The request and the responses that will be given shall be in writing (or by fax). The validity of the bid bond provided for in article 17 of the General Regulations shall equally be extended for a corresponding duration. A bidder may refuse to extend the validity of his bid without losing his bid bond. A bidder who consents to an extension shall not be asked to modify his bid nor shall he be authorized to do so.

16.3 Where the contract does not include a price revision clause and that the period of validity of bids is extended by more than sixty (60) days, the amounts payable to the bidder retained shall be updated by application of the related formula featuring in the request for extension that the Contracting Authority addressed to bidders. The updating period shall run from the date of overrun of sixty (60) days to the date of notification of the contract or the Administrative Order for start of execution of works by the retained bidder, as specified in the Special Administrative Conditions. The effect of updating shall not be taken into account for purposes of evaluation of bids.

**Article 17: Bid bond**

17.1 In application of article 13 of the General Regulations, the bidder shall furnish a bid bond of the amount specified in the Special Regulations and which bid bond shall be a full part of his bid.

17.2 The bid bond must conform to the model presented in the Tender File; other models may be authorized subject to the prior approval of the Contracting Authority. The bid bond will remain valid for thirty (30) days beyond the original date set for the validity of bids or any other validity time-limit requested by the Contracting Authority and accepted by the bidder, in accordance with the provisions of article 16 (2) of the General Regulations.

17.3 Any bid without an acceptable bid bond shall be rejected by the Tenders Board as not in conformity. The bid bond of associated enterprises must be established in the name of the group submitting the bid and mention each member of the associated grouping.

17.4 The bid bonds of bidders who are not retained shall be returned within fifteen (15) days after publication of the award result.

17.5 The bid bond of the successful bidder shall be released as soon as the latter would have signed the contract and furnished the required final bond.

17.6 The bid bond may be seized:

- (a) if the bidder withdraws his bid during the period of validity;
- (b) if the retained bidder:

b.1 Fails in his obligation to register the contract in application of article 38 of the General Regulations;

b.2 Fails in his obligation to furnish the required final bond in application of article 38 of the General Regulations;

b.3 Refuses to receive notification of the Administrative Order to commence execution.

**Article 18: Varying proposals of bidders**

18.1 Where the works can be executed within variable deadlines, the Special Regulations shall specify these deadlines and shall indicate the method retained for the evaluation of the completion deadline proposed by the bidder within the specified deadlines. Bids that propose deadlines beyond those specified shall be considered as not being in conformity.

18.2 Except in the case mentioned in article 18(3) below, bidders wishing to offer technical variants must first assess the Secondary solution of the Contracting Authority as described in the Tender File and furnish in addition all the information which the Contracting Authority needs for a complete evaluation of the proposed variant, including the plans, calculations, technical specifications, sub-details of prices and proposed construction methods and all other useful information. If necessary, the Contracting Authority will examine only the technical variants of the bidder whose bid is in compliance with the Secondary solution has been evaluated as the lowest bid.

18.3 When according to the Special Regulations the bidders are authorized to directly submit the technical variants for certain parts of the works, these parts of the works must be described in the technical specifications. Such variants shall be evaluated on their own merit in accordance with the provisions of article 31(2) (g) of the General Regulations.

#### **Article 19: Preparatory meeting to the establishment of bids**

19.1 Except otherwise stipulated in the Special Regulations, a bidder may be invited to take part in a preparatory meeting which will hold at the date and place indicated in the Special Regulations.

19.2 The subject of the preparatory meeting shall be to furnish clarifications and answer any questions which may be raised at this stage.

19.3 As much as possible, the bidder is requested to submit any question in a way as to reach the Contracting Authority at least one week before the meeting. The Contracting Authority may not reply to questions received too late. In this case, the questions and answers shall be transmitted according to the methods set in article 19(4) below.

19.4 The minutes of the meeting, including the text of the questions asked and the replies given, including questions prepared after the meeting, shall be forwarded immediately to everyone who bought the Tender File. Any modification of documents of the Tender File listed in article 8 of the General Regulations which may prove to be necessary at the end of the preparatory meeting shall be done by the Contracting Authority by publishing an addendum in accordance with the provisions of article 10 of the General Regulations and not through the minutes of the preparatory meeting.

19.5 The fact that a bidder does not attend a preparatory meeting for the establishment of bids shall not be a reason for disqualification.

#### **Article 20: Form and signature of bid**

20.1 The bidder shall prepare an original of the constituent documents described in article 13 of the General Regulations in a volume clearly indicated "ORIGINAL". In addition, the bidder shall submit the number required in the General Regulations, bearing "COPY". In case of discrepancy, the original shall be considered as authentic.

20.2 The original and copies of the bid must be typed or written in indelible ink (photocopies shall be accepted in the case of copies) and shall be signed by the person(s) duly empowered to sign on behalf of the bidder, in accordance with article 6(1a) or 6(2c) of the General Regulations, as the case may be. All the pages of the bid containing alterations or changes must be initialed by the signatory (ies) of the bid.

20.3 The bid shall bear no modification, suppression or alteration unless such corrections are initialed by the signatory (i.e.) of the bid.

### **D. SUBMISSION OF BIDS**

#### **Article 21: Sealing and marking of bids**

21.1 The bidder shall seal the original and each copy of the bid in separate envelopes (internal envelopes) by marking on these envelopes "ORIGINAL" and "COPY", as the case may be. The envelopes shall then be placed in another envelope which will equally be sealed but which will not give any indication regarding the identity of the bidder.

21.2 The external and internal envelopes:

a) Should be addressed to the Contracting Authority at the address indicated in the Special Regulations;

b) should bear the name and identification number of the project as indicated in the Special Regulations and bear the inscription "TO BE OPENED ONLY DURING THE BID-OPENING SESSION" as specified in the Special Regulations.

21.3 The internal envelopes should equally carry the name and address of the bidder in a way as to enable the Contracting Authority return the sealed bid if it is late in accordance with article 23 and 24 of the General Regulations.

21.4 If the external envelope is not sealed and marked as indicated in paragraphs 21(1) and 21(2) above, the Contracting Authority shall not be responsible if the bid is misplaced or opened prematurely.

#### **Article 22: Date and time-limit for submission of bids**

22.1 The bids must be received by the Contracting Authority at the address specified in article 21(2) of the Special Regulations not later than the date and time stated in the Special Regulations.

22.2 The Contracting Authority may, at his discretion, postpone the deadline set for the submission of the bids by publishing an addendum in accordance with the provisions of article 10 of the General Regulations. In this case, all the rights and obligations of the Contracting Authority and bidders previously governed by the initial date will henceforth be governed by the new date.

**Article 23: Late bids:** Any bid received by the Contracting Authority beyond the deadline for the submission of bids in accordance with article 22 of the General Regulations shall be declared late and consequently rejected.

#### **Article 24: Modification, substitution and withdrawal of bids**

24.1 A bidder may modify or withdraw his bid after submitting it, on condition that the written notification of the modification or withdrawal is received by the Contracting Authority prior to the end of the time-limit prescribed for the submission of the bids. The said notification must be signed by an authorized representative in application of article 20(2) of the General Regulations. The modification or the corresponding replacement bid must be attached to the written notification. As the case may be, the envelopes must bear the inscription "WITHDRAWAL", and "REPLACEMENT BID" or "MODIFICATION".

24.2 Notification of modification, replacement or withdrawal of the bid by the bidder should be prepared, sealed, marked and forwarded in accordance with the provisions of article 21 of the General Regulations. Withdrawal may equally be notified by telex but should in this case be confirmed by a duly signed written notification whose date, post mark being authentic, shall not be posterior to the time-limit set for the submission of bids.

24.3 In application of article 24(1), bids being requested to be withdrawn by bidders shall be returned to them unopened.

24.4 No bid may be withdrawn during the interval between the submission of bids and the expiry of the validity of bids specified by the model tender. The withdrawal of a bid by a bidder during this interval may lead to the confiscation of the bid bond in accordance with the provisions of article 17(6) of the General Regulations.

#### **E. OPENING AND EVALUATION OF BIDS**

##### **Article 25: Opening of the bids and petitions**

25.1 The competent Tenders Board shall open the envelopes in single or double phases and in the presence of the representatives of bidders who wish to attend at the date, time and address specified in the Special Regulations. Representatives of bidders shall sign a register attesting to their presence.

25.2 Firstly, envelopes marked "withdrawal" shall be opened and the contents announced to the hearing of everyone, while the envelope containing the corresponding bid shall be returned to the bidder unopened. Withdrawal shall be allowed only if the corresponding notification contains a valid empowerment of the signatory to request this withdrawal and if this notification is read to the hearing of everyone. Then the envelopes marked "Replacement bid" are opened and announced to the hearing of everyone and the new corresponding bid substituted for the preceding one which will be sent to the bidder concerned unopened. The replacement of the bid shall only be allowed if the corresponding notification contains a valid empowerment of the signatory requesting the replacement and read to the hearing of everyone. Lastly, the envelopes marked "modification" shall be opened and their contents read to the hearing of everyone with the corresponding bid. The modification of the bid shall only be allowed if the corresponding notification contains a valid empowerment of the signatory requesting the modification and read to the hearing of everyone. Only bids which were opened and announced to the hearing of everyone during the opening of bids shall then be evaluated.

25.3 All envelopes shall be opened successively and the name of the bidder announced aloud as well as the possible modification mentioned, the price offered, including any rebates [in case of opening of financial bids] and any variant, where necessary, the existence of a guarantee of the bid if it is required and any other details which the Contracting Authority deems useful to be mentioned. Only rebates and variants of bids announced to the hearing of everyone during the opening of bids shall be submitted for evaluation.

25.4 Bids (and modifications received in accordance with the provisions of article 24 of the General Regulations) which were not opened and read to the hearing of everyone during the bid-opening session for whatever reason, shall not be submitted for evaluation.

25.5 Bid-opening minutes are recorded on the spot mentioning the admissibility of bids, their administrative regularity, prices, rebates and time-limits as well as the composition of the Evaluation sub-committee. A copy of the said minutes to which is attached the attendance sheet is handed over to all the participants at the end of the session.

25.6 At the end of each bid-opening session, the chairperson of the Tenders Board immediately hands over to the focal point designated by the body in charge of regulation of public contract an initialed copy of the bids presented by bidders.

25.7 In case of petition as provided for by the Public Contracts Code, it should be addressed to the Minister Delegate in charge of Public Contracts with a copy to the body in charge of the regulation of public contracts, the head of structure to which is attached the Tenders Board concerned.

It must reach within a maximum deadline of three (3) working days after the opening of bids in the form of a letter to which is obligatorily attached a sheet of the petition form duly signed by the petitioner and possibly by the chairperson of the Tenders Board.

The Independent Observer attaches to his report the sheet that was handed to him, including any related commentaries or observations.

##### **Article 26: Confidential nature of the procedure**

26.1 No information relating to the examination, clarification, evaluation and comparison of bids and verification of the qualification of the bidders and the recommendation for the award shall be given to bidders or to any person not concerned with the said procedure as long as the preferred bidder has not been made public, subject to the disqualification of the bid of the bidder and suspension of the authors from all activities in the domain of public contracts.

26.2 Any attempt by a bidder to influence the Tenders Board or the Evaluation sub-committee of bids or the Contracting Authority in its award decision may lead to the rejection of his bid.

26.3 Notwithstanding the provisions of paragraph 26.2 above, between the opening of bids and the award of the contract, if a bidder wishes to enter into contact with the Contracting Authority for reasons having to with his bid may do so in writing.

**Article 27: Clarifications on the bids and contact with the Contracting Authority**

27.1 To ease the examination, evaluation and comparison of bids, the Tenders Board may, if it so desires, request any bidder to give clarifications on his bid. This request for clarification and the response thereto are formulated in writing but no change on the amount or content of the bid is sought, offered or authorized, except it is necessary to confirm the correction of calculation errors discovered by the Evaluation Sub-committee during the evaluation in accordance with the provisions of article 30 of the General Regulations.

27.2 Subject to the provisions of paragraph 1 above, bidders shall not contact members of the Tenders Board and the Evaluation Sub-committee for questions related to their bids, between the opening of envelopes and the award of the contract.

**Article 28: Determination of compliance of bids**

28.1 The Evaluation sub-committee shall carry out a detailed examination of bids to determine if they are complete, if the required guarantees are furnished, if the documents were correctly signed and if generally the bids are in proper order.

28.2 The Evaluation sub-committee shall determine if the bid is essentially in compliance with the conditions fixed in the Tender File based on the content without recourse to external elements of proof.

28.3 A bid that complies with the Tender File shall essentially be a bid that respects all the terms, conditions and specifications of the Tender File, without substantial divergence or reservation. A substantial divergence or reservation is that:

- Which substantially limits the scope, quality or realization of the works;
- which substantially limits, contrary to the Tender File, the rights of the Contracting Authority or his obligations in relation to the contract;
- Whose correction would unjustly affect the competitiveness of the other bidders who presented bids that essentially complied with the Tender File.

28.4 If a bid is essentially not in compliance, it shall be rejected by the competent Tenders Board and shall not subsequently be rendered in compliance.

28.5 The Contracting Authority reserves the right to accept or reject any modification, divergence or reservation. Modifications, divergences, variants and other factors which are beyond the requirements of the Tender File shall not be considered during the evaluation of bids.

**Article 29: Qualification of the bidder:** The Evaluation sub-committee shall ensure that the successful bidder retained for having submitted a bid substantially in compliance with the provisions of the Tender File, fulfils the qualification criteria stipulated in article 6 of the Special Regulations. It is essential to avoid any arbitrariness in determining qualification.

**Article 30: Correction of errors**

30.1 The Evaluation sub-committee shall verify bids considered essentially in compliance with the Tender File to correct the possible calculation errors. The Evaluation sub-committee shall correct the errors in the following manner:

a. Where there is an incoherence between the unit price and the total obtained by multiplying the unit price by the quantity, the unit price being authentic, the total price shall be corrected, unless the Evaluation sub-committee judges that it is a gross error of decimal point in the unit price in which case the total price as presented shall be authentic and the unit price corrected.

b. If the total obtained by addition or subtraction of the totals is not exact, the sub totals shall be considered authentic and the total corrected.

c. Where there is a difference between the price indicated in letters and in figures, the amount in letters shall be considered authentic, unless the amount is linked to an arithmetical error confirmed by the sub-detail of the said price, in which case the amount in figures shall prevail subject to paragraphs (a) and (b) above.

30.2 The amount featuring in the bid shall be corrected by the Evaluation sub-committee, in accordance with the error correction procedure above and with confirmation by the bidder, the said amount shall be deemed to commit him.

30.3 If the bidder who presented the bid evaluated as the lowest refuses the correction thus carried out, his bid shall be rejected and the bid bond may be seized.

### **Article 31: Conversion into a single currency**

31.1 To facilitate the evaluation and comparison of bids, the Evaluation sub-committee shall convert the prices of bids expressed in various currencies into those in which the bid is payable in CFA francs.  
31.2 The conversion shall be done using the selling rate fixed by the Bank of Central African States (BEAC) under the conditions defined by the Special Regulations.

### **Article 32: Evaluation and comparison of financial bids**

32.1 Only bids considered as being in compliance, as per the provisions of article 28 of the General Regulations, shall be evaluated and compared by the Evaluation sub-committee.

32.2 By evaluating the bids, the Evaluation Sub-committee shall determine for each bid the evaluated amount of the bid by rectifying the amount as follows:

- a. By correcting any possible error in accordance with the provisions of article 30.2 of the General Regulations;
- b. By excluding projected sums and where necessary provisions for unforeseen occurrences featuring in the bill of quantities and estimates but by adding the amount of works done under State supervision where they are costed in a competitive manner as specified in the Special Regulations.
- c. By converting into a single currency, the amount resulting from the rectifications (a) and (b) above, in accordance with the provisions of article 31(2) of the General Regulations;
- d. By appropriately adjusting any other modification, divergence or quantifiable reservation on technical or financial basis.
- e. By taking into consideration the various execution time-limits proposed by the bidders, if they are authorized by the Special Regulations;
- f. If need be, in accordance with the provisions of article 13(2) of the General Regulations and the Special Regulations by applying the rebates offered by the bidder for the award of more than one lot, if this invitation to tender is launched simultaneously for several lots.
- g. If need be, in accordance with the provisions of article 18(3) of the Special Regulations and the Technical Specifications, the proposed technical variants, if they are permitted, shall be evaluated on their own merit and independently of the fact that the bidder offered or not a price for the technical solution specified by the Contracting Authority in the Special Regulations.

32.3 The estimated effect of price revision formulae featuring in the GAC and SAC applied during the period of execution of the contract shall not be considered during the evaluation of bids.

32.4 If the bid judged the lowest bid is considered abnormally low or strongly unbalanced in relation to the estimates of the Project Owner for the works to be executed in this contract, the Tenders Board may, from the sub-details of prices furnished by the bidder for any element or all the elements of the bill of quantities and estimates, verify if these prices are compatible with the construction methods and proposed calendar. In the case where the justifications presented by the bidder are not satisfactory, the Contracting Authority may reject the bid after the technical opinion of the Public Contracts Regulatory Agency.

**Article 33: Preference granted national bidders:** National contractors shall benefit from a margin of national preference during the evaluation of bids as provided for in the Public Contracts Code.

## **F- AWARD OF THE CONTRACT**

### **Article 34: Award**

34.1 The Contracting Authority shall award the contract to the bidder whose bid was judged essentially in compliance with the Tender File and who has the required technical and financial capacities to execute the contract satisfactorily and whose bid was evaluated as the lowest by including, where necessary, proposed rebates

34.2 If, according to article 13(2) of the General Regulations, the invitation to tender comprises several lots, the lowest bid shall be determined by evaluating this contract with other lots to be awarded concurrently, by taking into account the rebates offered by the bidders in the case of more than one lot.

34.3 Any award of contract shall be made to the bidder fulfilling the technical and financial capacities required resulting from the evaluation criteria and presenting the bid evaluated as the lowest.

**Article 35: The right by the Contracting Authority to declare an invitation to tender unsuccessful or cancel a procedure:** The Contracting Authority reserves the right to cancel a procedure of invitation to tender after the authorization of the Minister Delegate at the Presidency in charge of Public Contracts where the bids have been opened or to declare an invitation to tender unsuccessful after the advice of the competent Tenders Board, without any claims being entertained.

**Article 36: Notification of award of the contract:** Before the expiry of the validity of the bids set in the Special Regulations, the Contracting Authority shall notify the preferred bidder by telecopy confirmed by registered mail or by any other means that his bid was retained. This letter will indicate the amount the Project Owner will pay the contractor to execute the works and the execution time-limit.

### **Article 37: Publication of results of award and petitions**

37.1 The Contracting Authority shall communicate to any bidder or administration concerned, upon request addressed to it within a maximum deadline of five (5) days after publication of the award results, the Independent Observer's report as well as the minutes of the award session of the related contract to which shall be attached the evaluation report of the bids.

37.2 The Contracting Authority is bound to communicate the reasons for the rejection of bids of the bidders concerned who so request.

37.3 After publication of the award results, bids that are not withdrawn within fifteen (15) days shall be destroyed, without any claims for compensation being entertained. Only the copy destined for the body in charge of regulation shall be kept.

37.4 In case of petition, it should be addressed to the Public Contracts Authority, with copies to the body in charge of the regulation of public contracts, the Contracting Authority and the chairperson of the Tenders Board concerned. It must take place within a maximum deadline of five (5) working days after the publication of the results.

### **Article 38: Signing of the contract**

38.1 After publication of the results, the draft contract subscribed by the successful bidder is submitted to the Tenders Board for examination and where applicable, to the Minister in charge of Public Contracts for prior endorsement.

38.2 The Contracting Authority has a deadline of seven (7) days to sign the contract from the date of reception of the draft contract examined by the competent Tenders Board and subscribed by the successful bidder and where applicable, the endorsement of the Minister in charge of Public Contracts for contracts through mutual agreement.

38.3 The contract must be notified to the successful bidder within five (5) days of its date of signature.

### **Article 39: Final Bond**

39.1 Within twenty (20) days of the notification by the Contracting Authority, the contractor shall furnish the Project Owner with a final bond, to guarantee the complete execution of the works for projects above thirty million francs.

39.2 The bond whose rate varies between 2 and 5 per cent of the amount of the contract inclusive of all taxes, may be replaced by a guarantee from a banking establishment approved according to the instruments in force with the Project Owner as beneficiary or by a joint or several guarantee.

39.3 Small and medium-sized enterprises (SME) constituted of national capital and managed by nationals may, in lieu of the guarantee, provide a statutory lien or a bond issued by a banking establishment or first-rate financial institution approved in accordance with the instruments in force.

39.4 Failure to produce the final bond within the prescribed time limit shall likely cause the termination of the contract under the terms laid down in the General Administrative Conditions.

**DOCUMENT No. 3:**  
**SPECIAL REGULATIONS OF THE INVITATION TO TENDER**

The following provisions are specific to the works forming the subject of this *Invitation to Tender*, supplement or if necessary, modify the provisions of the General Regulations of the *Invitation to Tender*. In case of difference, the following provisions shall prevail over the clauses of the General Regulations.

**INTRODUCTION**

**ARTICLE 1: Definition of Works:**

Ref. of the General regulations	General
	<b>Definition of works:</b> construction of A MARKET SHED AND 10 STORES IN NTABA MARKET in NDU Subdivision, Donga-Mantung Division, North West Region
1.1	<b>Name and address of the Contracting Authority:</b> The Mayor of NDU COUNCIL, Contracting Authority
	<b>Reference of Invitation to tender:</b> /ONIT/NWR/DMD/NC/NCITB/2026 of the <b>2026</b>
1.2	Duration of Execution: One Hundred and twenty (120) days
2	<b>Source of financing:</b> Works which form the subject of this Invitation to Tender shall be financed through the 2026 Public Investment Budget of the Ministry of COMMERCE budget head No
3	<b>Origin of building materials and supplies:</b> The materials shall generally be from sources in Cameroon.

**OPEN NATIONAL INVITATION TO TENDER N°. /ONIT/NWR/DMD/NC/NCITB/2026 OF 2026, FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET, NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**

**Article 4: CONSISTENCY OF THE BIDS:** The bid shall include a file for:

**Envelope A: Administrative Documents:** It shall consist of the following documents, stapled and arranged in the following order.

1. **An undertaking** by the bidder (declaration to tender), stamped, dated and signed by the bidder or group representative in conformity with the model attached.
2. **An attestation of non-bankruptcy** not older than 03 months, issued by the chamber of commerce or court of competent jurisdiction of the place of residence of the bidder.
3. **An attestation of Bank account** in the name of the enterprise issued by a bank or any first-order credit institution approved by the Minister in charge of finance.
4. **Bid security (bank guarantee)** of Nine hundred and sixty thousand (**960,000 FCFA**) from a bank accredited by MINFI and recognized by COBAC (Bank caution) and validated by CDEC.
5. **Treasury Receipt** showing the payment of the tender fee as stipulated in the Tender Notice(96,000frs).
6. **An attestation of CNPS:** current certificate from the National Social Insurance Fund (CNPS) certifying that the bidder has effectively paid his/her social contributions.
7. **Certificate of non-exclusion** attesting that the bidder is not the subject of a temporary or permanent exclusion from Public Contracts, not older than three (03) months issued by ARMP.
8. **A certificate of tax assessment** certifying that the bidder owes no taxes signed by the Director or the head of Tax Center.
9. **Certificate of categorisation**
10. **A valid Tax payer's card.**
11. **A certified copy of Certificate of Incorporation.**
12. **Group agreement** as the case may be.
13. **Power of Attorney** as the case may be signed by a notary.
14. **The Special Administrative Conditions (SAC/CCAP)**, initialled on each page and signed, dated and stamped on the last page

**N.B:**

Absence of the following documents shall result in outright rejection

✓ Bid bond

**N.B:** All documents shall be originals as requested or certified true copies legalized by competent services or that which issued them and must not be more than three (03) months old. The documents shall be arranged in the order listed below and separated from each other by colour separators. *Any document with double certification shall not be accepted.*

**Envelope B: TECHNICAL PROPOSAL**

It shall contain the documents cited below and placed in the following order:

No	DOCUMENT	OPERATION REQUESTED	AUTHENTICATION
B1	<b>Equipment list</b> <i>(for enterprises who have presented only the receipt of categorization)</i>	It shall clearly show the means at the disposal of the enterprise to carry out the job (list of equipment and tools)	Attach certified copies of lease agreements, receipts, etc. These equipment and tools must be present at the site before and during each phase
B2	<b>Personnel list</b> <i>(for enterprises who have presented only the receipt of categorization)</i>	It shall contain: ☞ Works Supervisor: at least a Senior Civil Engineering Technician with at least 3 years' experience ☞ Foreman: at least a Civil Engineering Technician with at least 3 years' experience in the domain of Construction. ☞ Chief mason – holder of at least CAP/Probatoire/BAC ☞ Chief carpenter – holder of at least CAP/Probatoire/BAC ☞ Chief electrician – holder of at least CAP/Probatoire/BAC ☞ Chief plumber – holder of at least CAP/Probatoire/BAC	Attach for each person a CV signed and dated, as well as a certified copy of certificate. <i>(all key personnel must present a commitment of availability duly signed and must present a certified copy of a valid National Identity Card bearing 03 signatures of the bearer)</i>
B3	<b>Organisation of works/ methodology</b>	In conformity with article 7 below, it shall clearly show the organisation of the enterprise ( <i>methodology of execution, work schedule, site installation, supply of materials, etc</i> )	Date, signature and stamp of bidder at the end of document
B4	<b>Sub-contracting</b>	Information on the sub-contractor (equipment, personnel, references, etc)	Date and signature of sub-contractor. (only 30% maximum of the contract may be sub-contracted)
B5	<b>Attestation of Site Visit</b>	Attestation of Visit to the Site where the works are to be carried out. A Site Visit Report signed by the Engineer. ( see attached format)	Dated and signed on honour by the contractor
B6	<b>References of the enterprise.</b> <i>(for enterprises who have presented only the receipt of categorization)</i>	List of similar jobs executed in the last five (05) years by the enterprise and or other civil engineering works realized. (see attached format)	Amount of works, copies of (1 <sup>st</sup> and last pages) and minutes of Final Reception for all similar works executed before 2025 and minutes of Provisional Reception for 2025 projects.
B7	<b>Financial capability</b>	Attestation of pre-financing delivered by a banking institution recognised by MINFI/COBAC	Date and signature of bank Manager in charge.
B8	<b>Technical specifications</b>	Provided in Tender File.	Initialled on every page and Signed and stamped on the last page

#### ENVELOPE C: FINANCIAL PROPOSAL

No	DOCUMENT	OPERATION REQUESTED	AUTHENTICATION
C1	<b>The tender (Application letter)</b>	Format to be completed and tender amount inserted.	Signature, date and stamp of bidder. A Fiscal stamp of 1500 FCFA.
C2	<b>Unit Price Schedule</b>	Format to be completed showing detail breakdown of prices.	Initials on each page, all pages stamped and last page signed.
C3	<b>Bill of Quantities and Cost Estimates</b>	Format to be completed.	Initials on each page, dated, signature on the last page, all pages stamped.
C4	<b>Sub detail of Unit Prices</b>	Format to be completed showing the unit prices.	Initials on each page and signature on last page, all pages stamped with enterprise function stamp.

All these documents are to be arranged in the above order and separated with colour separators other than white.

**Note:** Plans supplied with Tender File should not be submitted.

**Building materials, materials, supplies equipment and authorised services:** The taxes and duties on the importation of materials for execution of works shall be in conformity with the legislation of the Republic of Cameroon.

#### **Article 5: Main qualification criteria of bidders:**

5.1 The criteria relating to the qualification of candidates could indicatively be on the following:

- General presentation of the Tender Files;
- References of the company in similar works;
- Quality of the personnel proposed;

- Attestation and report of *Site Visit*;
- Technical Organization of the works,
- Equipment put aside for this project,
- Safety measures on the site.
- Pre-financial capability

Any bid that shall not obtain (75%) in the evaluation of the above criteria shall simply be eliminated.

5.2 Bidders shall remain bound by their bids for a period of ninety (90) days from the date of submission of the bids

#### **ARTICLE 6: OBLIGATIONS AND CONDITIONS TO TENDER**

6.1 Any bid that does not respect any of the conditions for the tendering shall not be received.

6.2 The bidders shall submit six (06) copies with one (01) original and five (05) copies (indicated on them as such) of his/her bids drafted in English or French at the Service for the award of Ndu Council, against a receipt **on or before the 10:00a.m prompt**. No bid shall be received after this time and date. **2026 at**

6.3 After submission, no bid shall be withdrawn, modified or corrected for any reason.  
This condition shall apply before and after the submission date.

#### **ARTICLE 7: THE BIDDING DOCUMENTS**

7.1 The documents that make up this tender are as follows:

Document №: 1: *Invitation to Tender*.

Document №: 2: The General Tender Regulation

Document №: 3: The Special Tender Regulation

Document №: 4: The Special Administrative Conditions (SAC/CCAG)

Document №: 5: Special Technical Conditions (STC/CCTP)

Document №: 6: Form for Bill of Quantities and Cost Estimates (BQCE)

Document №: 7: Form for Unit Prices Schedule (UPS)

Document №: 8: Model Forms

- General information Form
- Submission Form
- Bank Guarantee Forms (Bid bond, Guarantee retentions)
- Form for Price Elaboration (Detailed Unit Price) (DUP)

Document №: 9: Execution plans.

#### **ARTICLE 8: AMENDMENT OF BIDDING DOCUMENTS**

8.1 At any time prior to the deadline for submission of bids, the Contracting authority, may modify the bidding documents for any reasons, whether at its own initiative, at the request of the tenders board or in response to a clarification requested by a prospective bidder.

8.2 All prospective bidders that have received the bidding documents shall be notified of all amendments in writing or shall be contacted by telephone to do so and all such modifications will be considered as an integral part of their bidding documents. In order to allow prospective bidders reasonable time in which to take the amendment into account in preparing their bids, the contracting authority at its discretion, may extend the deadline for the submission of bids if there were any such amendments

#### **ARTICLE 9: CALCULATION OF PRICES**

9.1 The amount shall be calculated on the bases of variable prices.  
The bidder shall fill, in letters and in figures, the unit prices in the unit price schedule and the unit prices are to be multiplied by the quantities given in order to obtain the amount of his/her offer for each item.

9.2 The unit price schedule must be completed. Any price lacking on this form shall be considered as follows:

- The corresponding price on the bill of quantities and costs estimates;
- The highest corresponding price furnished by the bidder technically qualified, if it exists in the same lot,
- The average of all the prices of bidders in the same lot if the bidder is the only qualified one.

9.3 The bidder shall express the prices in the UPS and BQCE in francs CFA excluding taxes before adding the taxes to the BQCE only.  
The prices on the UPS in words shall have priority over those of the BQCE and DUP. They shall serve as the bases of calculation of the bidding amount.  
The eventual calculation errors shall be corrected by the Sub Committee for Analysis and the amount altered if necessary, without any complaints from the bidder.

#### **ARTICALE 10: PRESENTATION OF BIDS**

a. Signature of bids – Power of Attorney

10. a.1 All the signatures and initials needed for the tender and indicated in this article must be those of the bidder himself or his/her/ her representative duly mandated.

10. a.2 If the bidder is a group of enterprises, each group member or representative must sign the bidding documents such that the result shall be a joint offer. The group shall choose a common representative who shall receive Service Orders and carry out all transactions in the name of the group.

b. **Presentation of bids:** The bid shall be presented in seven (07) copies (one (01) original and six (06) copies) marked as such and put inside three (03) sealed internal envelopes. The electronic version of the bid must be included

All these documents are to be arranged in the above order and separated with colour separators.

Note: Plans supplied with Tender File should not be submitted.

c. **Submission and opening of bids:** Envelopes A, B, and C are to be sealed and each envelope shall be marked "ADMINISTRATIVE DOCUMENTS, TECHNICAL FILE or FINANCIAL FILE" as the case may be. The three envelopes shall be placed in a fourth envelope, sealed and shall carry the following inscriptions:

OPEN NATIONAL INVITATION TO TENDER N°. \_\_\_\_/ONIT/NWR/DMD/NC/NCITB/2026 of the \_\_\_\_\_ 2026, FOR THE  
CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION,  
NORTH WEST REGION  
(TO BE OPENED ONLY DURING THE BIDS OPENING SESSION)

(EMERGENCY PROCEDURE)

All bids shall be deposited at the Service of Contracts award of the NDU Council, against a receipt according to the schedule in the Tender Notice. In the case where the envelope shall not be sealed or without the inscription on it, the administration shall decline all responsibility for misdirection or premature opening. Any bid opened prematurely shall be rejected and returned to the bidder. The bids shall be submitted in a sealed external envelop latest the 2026 at 10:00am, with acknowledgment of delivery at the following address:

MINISTRY OF DECENTRALISATION AND LOCAL DEVELOPMENT  
NDU COUNCIL  
SERVICE OF PUBLIC CONTRACTS AWARD

No bids shall be accepted, beyond the above stated date and time,

**ARTICLE 11: TECHNICAL PROPOSALS:** Proposals for different variants can be accepted from the bidder but the bidder has the obligation of costing the variant in the tender file.

**ARTICLE 11: BID BOND:** The bidder shall furnish a bid bond (provisional caution) of Nine hundred and sixty thousand (960,000 FCFA) from a banking institution of the first order accredited by the Ministry in charge of Finance according to the criteria of COBAC and validated by CDEC.

**ARTICLE 11: TENDER:** Each bidder shall tender following the conditions laid down in this Tender File.

**ARTICLE 12: CURRENCY:** The unit prices shall be calculated in Francs CFA, and furnish in figures and words without taxes, while the total amount shall be calculated without taxes and then with taxes according to the BQCE. The currency that shall be used for payment shall be the FCFA.

**ARTICLE 13: PAYMENT MODALITIES:** The contractor shall be paid upon presentation of monthly installment "Décomptes" established from attachments signed by Project Manager and visa by the Contracting Authority showing the work progress, presented by the Contract Engineer and countersigned by the Contract Manager (Authorizing Officer) and the Contractor.

**ARTICLE 14: IMPORTATION OF MATERIALS:** The taxes and duties on the importation of materials for execution of works shall be in conformity with the legislation of the Republic of Cameroon.

**ARTICLE 15: VERIFICATION OF BIDS:** The administration has a period of one (01) month to examine the bids and make its choice. It shall eventually rectify, as indicated in article 5.3, the bidding amount without any objection from the bidder.

15.1 At the request of the Tender Board, the bidder shall furnish in writing, within seven (07) calendar days, any information necessary for the examination of his/her bid or concerning errors and omissions noted.

15.2 The Tender Board reserves the right to convoke the bidder at his/her expenditure for complementary explanations. Any errors discovered by the Tender Board shall be rectified as follows:

15.2.1 Where there exists a difference between the amount in figures and the amount in letters, the amount in letters shall be taken as correct;

15.2.2 Where there exists a difference between a unit price and the amount obtained by the product of unit price and the quantity, the unit price shall be taken, except the Tender Board estimates that it is an error of decimal point, in which case the amount is taken and the unit price corrected.

15.2.3 The sub-committee for the evaluation of bids, whose members shall be designated by the tender's board members, shall be constituted during the bid opening session

**ARTICLE 16: VALIDITY OF BIDS:** The bidder shall be bound by his/her bid for a period of ninety (90) days from the day of submission of bids. If at the end of this period the jobbing Order is not notified to the bidder, he can withdraw his/her bid or accept the extension of duration on the written request of the administration.

**ARTICLE 17: OPENING/EVALUATION OF BIDS AND CHOICE OF CONTRACTOR:** The opening of bids shall take place on the date and place prescribed in the Tender File. Envelopes received from prospective bidders shall be opened at once and evaluated in two stages.

#### 1) OPENING OF ENVELOPES (A) (B) and (C) (FIRST STAGE)

- **OPENING/EXAMINATION OF ENVELOPE (A):**

(Administrative documents) shall be opened and the conformity of the documents shall be verified. The administrative documents must be complete, valid and authentic. The bid bond must conform to the format submitted. Only bids with documents that meet these requirements shall have their other envelopes evaluated.

- **OPENING/EXAMINATION OF ENVELOPE (B)**

(Technical Offer) shall be opened to determine whether the file is complete with the authenticity of documents checked and whether the documents are legalised by the competent services concerned and placed in the recommended order.

- **OPENING/EXAMINATION OF ENVELOPE (C)**

(Financial Offer) shall be opened but evaluated only for bids that have sailed through the first two steps.

Bid amounts shall be read aloud as inscribed in the Financial proposal of the bidder.

**NB:** Copies of the Financial proposal shall alongside the Administrative and Technical bids, be handed to a Sub-Technical committee for verification and evaluation of the Technical and Financial Proposal.

The bidder shall do everything to facilitate the job of the Sub-Technical Committee for Analysis by using Coloured separators, Title pages and summaries where necessary and presentation of documents according to the order given in the Tender File.

#### 17.1 **EVALUATION OF TECHNICAL PROPOSAL**

NDU COUNCIL INTERNAL TENDERS BOARD					
TECHNICAL ANALYSIS SUB COMMISION					
THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION					
TENDER No: ..... OF .....					
CONTRACTORS:					
A)					
B)					
C)					
Eliminatory Criteria (See evaluation of administrative files)					
Designation		BIDDERS			
		A	B	C	
a. General presentation of bids		EVALUATION (Yes or No)			
a1	Presence of all documents				
a2	Properly bound with spirals				
a3	Separators in colour apart from white				
a4	Order prescribed respected as in the Tender file				
	TOTAL a		1/4	1/4	1/4
b. The company references (if only a receipt of categorization is presented)		EVALUATION (Yes or No)			
References of the company in civil construction or similar works for the past Five years					

b1	At least 02 copies of similar contracts equal to or above the cost of the project (1 <sup>st</sup> and last page).			
b2	minutes of Provisional Reception for projects executed within the last five yrs (pluri annual projects accepted)			
b3	Minutes of final reception of similar projects executed within the past five years			
	<b>TOTAL b</b>	/3	/3	/3
	<b>c. Equipment (if only a receipt of categorization is presented)</b>		<b>EVALUATION (Yes or No)</b>	
c1	Proof of ownership or hire of a liaison vehicle (Pick up 4 x 4 or van) (Hired or owned)			
c2	Proof of ownership or hire of a truck of at least 20 tonnes capacity			
C3	Proof of ownership or hire of a manual compactor in good condition			
C4	Proof of ownership of a carpentry kit			
C5	Proof of ownership of a masonry kit			
	<b>TOTAL 2</b>	/5	/5	/5
	<b>d. Personnel of the Enterprise (if only a receipt of categorization is presented)</b>		<b>EVALUATION (Yes or No)</b>	
	<b>Works Engineer: Senior Civil Engineering Technician with at least 03yrs of experience (HND)</b>			
d1	Certified copy of valid <i>National Identity Card</i> , signed three times on it.			
d2	Diploma of Works Engineer certified			
d3	CV signed and dated by the Works Engineer			
D4	Attestation of availability duly signed by bearer and dated			
	<b>Site foreman: Civil Engineering Technician or HND with at least 3yrs experience</b>			
d5	Certified copy of valid <i>National Identity Card</i>			
d6	Certified copy of certificate of Foreman			
d7	CV signed and dated by Site Foreman			
d8	Attestation of availability duly signed by bearer and dated			
	<b>Chief builder: CAP F4, at least 3yrs of experience</b>			
d9	Certified copy of valid <i>National Identity Card</i> , signed three times on it.			
d10	Certified copy of diploma			
d11	Cv signed and dated			
d12	Attestation of availability duly signed by bearer and dated			
	<b>Chief carpenter: At least CAP in wood work/joinery at least three years</b>			
d13	Certified copy of valid <i>National Identity Card</i>			
d14	Certified copy of diploma			
d15	CV signed and dated			
d16	Attestation of availability duly signed by bearer and dated			
	<b>Chief electrician: CAP in electricity/house lighting at least 3years</b>			
d17	Certified copy of valid <i>National Identity Card</i>			
d18	Certified copy of diploma			
d19	Cv signed and dated			
d20	Attestation of availability duly signed by bearer and dated			
	<b>TOTAL d</b>	/20	/20	/20
	<b>e) Technical Proposals</b>		<b>EVALUATION (Yes or No)</b>	
e1	Attestation of <i>Site Visit</i> , signed by the director			
e2	<i>Site Visit</i> report with pictures duly signed by presenter (Director and Engineer)			
e3	Detailed technical note and proposals			
	<b>TOTAL e</b>	/3	/3	/3
	<b>f) The methodology of intervention and execution of work</b>		<b>EVALUATION (Yes or No)</b>	
f1	Site organisation in teams or options			
f2	Description of the socio - environment measures for site protection			
f3	Dispositions previewed for the securisation of personnel and other users			
f4	Use of local manpower			
f5	CCTP duly initialled and dated on each page and signed on the last page			
	<b>TOTAL f</b>	/5	/5	/5
	<b>g. Planning of execution of works</b>		<b>EVALUATION (Yes or No)</b>	
g1	Coherent planning with respect to tasks			
g2	Manpower deployment plan			
g3	Material deployment plan			
g4	Organisational chart of the enterprise			
	<b>TOTAL g</b>	/4	/4	/4
	<b>i. Pre-financing</b>		<b>EVALUATION (Yes or No)</b>	

e1	Attestation of credibility shall be at least 55% of the bid price			
	<b>TOTAL</b>	<b>/2</b>	<b>/2</b>	<b>/2</b>
	<b>GRAND TOTAL</b>	<b>/46</b>	<b>/46</b>	<b>/46</b>
<b>NB:</b> The minimal technical acceptable mark is 75% of the technical mark, i.e. All bids having less than 75/100 of the technical marks shall be eliminated.				
<b>Resolution:</b>				
<b>IV</b>	<b>FINANCIAL ANALYSIS</b>		<b>EVALUATION</b>	
			<b>A</b>	<b>B</b>
1	Unit Price Schedule			
2	Bill of Quantities and Cost Estimate			
3	Sub Detail of Unit Prices			
4	Bidder's Financial Proposal			
<b>NB)</b> The non-existence or Laxity noticed at the study of prices and Arithmetic errors shall be corrected by the Technical Sub Committee with respect to the invitation to Tender				
<b>FINAL RESOLUTION OF THE EVALUATION COMMISSION (use the corrected offer)</b>				

#### 17.2: Evaluation of Financial Proposal:

Careful study shall be carried out on the details of prices, unit prices, the bill of quantities and cost estimates presented to make sure the bidder did study the prices and has not made an arithmetic error to arrive at his/her final contract amount. The prices on the UPS shall have priority over those of the BQCE and DUP. They shall serve as the bases of calculation of the bidding amount.

The eventual calculation errors shall be corrected by the Sub Committee for Analysis and the amount altered if necessary, without any complaints from the bidder. Any laxity noticed at the study of prices shall lead to the disqualification of the bid.

#### 17.3: CHOICE OF CONTRACTOR (CRITERIA OF AWARDING CONTRACT):

According to article 33(1) (a) of the Public Contract Code, the contract shall be awarded to the meritorious and lowest bidder. Careful study must be carried out on the details of prices, unit prices, the bill of quantities and cost estimates presented to make sure the bidder did study the prices and has not made an arithmetic error to arrive at his/her final contract amount.

**ARTICLE 18: PROCEDURE OF AWARD OF CONTRACT:** The results from this tender shall be prepared, awarded and executed according to the rules and procedures defined by the legislation in force for Public Contracts.

18.1 The winner shall be notified through his/her official address or public media. He shall in five (05) days fulfil the formalities related to the awards, especially to submit seven (07) copies of the proposed contract that he/she has completed and signed, to the office of the Contracting Authority for final signature.

18.2 In the case where the enterprise does not fulfil these conditions, his/her choice shall simply be annulled without further notice and the next contender shall be called in for replacement.

Once the Contracting Authority has signed the contract, the contractor shall be notified with immediate effect. He has three (03) days to contact the Authorising Officer for the beginning of execution of works following notification of the Service Order to start work by the Project Manager. Failure to respect the date line shall call for withdrawal and eventual cancellation of contract.

18.3 The present contract can be cancelled outright in the cases provided for by Decree N°.:2018/366 of 20<sup>th</sup> June 2018 laying down the Public Contracts Code.

**DOCUMENT No. 4:**  
**SPECIAL ADMINISTRATIVE CONDITIONS (SAC)**

**Table of contents**

**Chapter I: General**

- Article 1 - Subject of the contract
- Article 2 - Award procedure
- Article 3 - Definitions and duties (article 2 of GAC supplemented)
- Article 4 - Language, applicable law and regulations
- Article 5 - Constituent documents of the contract (article 4 of GAC)
- Article 6 - General applicable instruments
- Article 7 - Communication (GAC articles 6 and 10 supplemented)
- Article 8 - Administrative Orders (article 8 of GAC supplemented)
- Article 9 - Contracts with conditional phases (article 15 of GAC)
- Article 10 - Contractor's personnel (article 15 of GAC supplemented)

**Chapter II: Financial conditions**

- Article 11 - Guarantees and bonds (articles 29 and 41 of GAC supplemented)
- Article 12 - Amount of contract (articles 18 and 19 supplemented)
- Article 13 - Place and method of payment
- Article 14 - Price variation (article 20 of GAC)
- Article 15 - Price revision formulas
- Article 16 - Price updating formulas (article 21 of GAC)
- Article 17 - Work under State supervision (article 22 of GAC supplemented)
- Article 18 - Evaluation of works (article 23 supplemented)
- Article 19 - Evaluation of supplies (article 24 of GAC) supplemented
- Article 20 - Advances (article 28 of GAC)
- Article 21 - Payments for the works (articles 26, 27 and 30 of GAC supplemented)
- Article 22 - Interests on overdue payments (article 31 of GAC supplemented)
- Article 23 - Penalties for delay (article 32 of GAC supplemented)
- Article 24 - Payment in case of a group of enterprises (article 33 of GAC)
- Article 25 - Final detailed account (article 35 of GAC)
- Article 26 - General detailed account (article 35 of GAC)
- Article 27 - Tax and customs schedule (article 36 of GAC)
- Article 28 - Stamp duty and registration (article 37 of GAC)

**Chapter III: Execution of the works**

- Article 29 - Nature of works
- Article 30 - Obligations of the Project Owner (GAC supplemented)
- Article 31 - Execution deadline of contract (article 38 of GAC)
- Article 32 - Roles and responsibilities of the contractor (article 40 of GAC)
- Article 33 - Making available documents and site (article 42 of GAC)
- Article 34 - Insurance of structures and civil responsibility (article 45 of GAC)
- Article 35 - Documents to be furnished by the contractor (article 49 supplemented)
- Article 36 - Organisation and security of sites (article 50 of GAC)
- Article 37 - Implantation of structures (article 52 of GAC)
- Article 38 - Sub-contracting (article 54 of GAC)
- Article 39 - Site laboratory and trials (article 55 of GAC)
- Article 40 - Site logbook (article 56 of GAC supplemented)
- Article 41 - Use of explosives (article 60 of GAC)

**Chapter IV: Acceptance**

- Article 42: - Pre-Acceptance
- Article 43 - Provisional acceptance (article 67 of GAC)
- Article 44 - Documents to be furnished after execution (article 68 of GAC)
- Article 45 - Guarantee time-limit (article 70 of GAC)
- Article 46 - Final acceptance (article 72 of GAC)

**Chapter V: Miscellaneous provisions**

- Article 47 - Termination of the contract (article 74 of GAC)
- Article 48 - Force majeure (article 75 of GAC)
- Article 49 - Differences and disputes (article 79 of GAC)
- Article 50 - Drafting and dissemination of this contract
- Article 51 - Entry into force of the contract
- Article 52 - Information to be posted

## Chapter I: General

**Article 1: Subject of contract:** The purpose of this contract is the Construction of a market shad and 10 stores in Ntaba market IN NDU Subdivision, Donga-Mantung Division, North West Region

**Article 2: Contract award procedure:** This contract is awarded through an Open National Invitation to Tender

**Article 3: Definitions and duties**

### 3.1 General definitions

- **The Contracting Authority:** shall be the **Mayor of NDU**: He awards the contract, ensures the preservation of originals of said contract documents, excluding bids and the transmission of copies to the Ministry in charge of Public Contracts and to the body in charge of regulation.
- **The Contract Engineer:** shall be the **Divisional Delegate of HOUSING AND URBAN DEVELOPMENT** for Donga-Mantung, hereinafter referred to as the Engineer for the construction works.
- **The Authorizing Officer:** is the **Mayor of NDU**. He/she represents the beneficiary administration of the works.
- **The Contract Manager:** shall be **Divisional Delegate of MINCOMMERCE Donga Mantung**, He ensures respect of the administrative, technical and financial conditions and contractual deadlines.
- **The Project Manager** shall be **The Council Development Officer for Ndu Council** : He ensures the interest of the project owner at the definition, preparation, execution and acceptance stages. He shall sign the task sheet of executed works.

**3.2 Security:** This contract may be used as a security subject to any form of transfer of the debt.

In this case:

- The authority in charge of ordering payment shall be the **Mayor of NDU**
- The authority in charge of the clearance of expenditures shall be the **Divisional Controller of Finance**.
- The body or official in charge of payment shall be the **Municipal Treasurer NDU Council**.
- The official competent to furnish information within the context of execution of this contract shall be the **Mayor of Ndu Council**.

**Article 4: Language, applicable law and regulation**

1.4 The language to be used shall be English or French.

1.5 The contractor shall be bound to observe the law, regulations and ordinances in force in Cameroon both within his own organization and in the execution of the contract. If the laws and regulations in force at the date of signature of this contract are amended after the signature of the contract, the possible direct resulting costs shall be taken into account without gain or loss for either party.

**Article 5: Constituent documents of the contract:** The constituent contractual documents of this contract are in order of priority:

- 1) The tender or commitment letter;
- 2) The bidder's tender and its annexes in all provisions not contrary to the General Administrative Conditions (GAC) and the Special Technical Conditions (STC) hereunder;
- 3) The Special Administrative Conditions (SAC);
- 4) The Special Technical Conditions (STC);
- 5) The particular elements necessary for the determination of the contract price, such as, in order of priority: the unit price schedule, the statement of all-in prices, detailed estimates, the breakdown of all-in prices and the sub-details of unit prices;
- 6) Plans;
- 7) The General Administrative Conditions applicable on public works contracts that went into effect by Order No. 033/CAB/PM of 13 February 2007;
- 8) The General Technical Condition(s) applicable on the services forming the subject of the contract.

**Article 6: General instruments in force:** This contract shall be governed by the following general instruments.

1. *Framework Law No. 96/12 of 5 August 1996 on the management of the environment;*
2. *The Mining Code;*
3. *Instruments governing the various professional bodies;*
4. *Decree No. 2001/048 of 23 February 2001 relating to the setting up, organization and functioning of the Public Contracts Regulatory Agency*
5. *Decree No. 2003/651/PM of 16 April 2003 to lay down the procedure for implementing the tax and customs system applicable to public contracts;*
6. *Decree No. 2018/366 of 20<sup>th</sup> June 2018 to institute the Public Contracts Code;*
7. *Decree No. 2012/074 of 8 March 2012 relating to the creation, organisation and functioning of Tenders Boards amended and supplemented by Decree No. 2013/271 of 5 August 2013;*

8. Decree No. 2012/075 of 8 March 2012 to organise the Ministry in charge of Public Contracts;
9. Circular No. 001/CAB/PR of 19 June 2012 relating to the award and control of execution of Public Contracts;
10. Letter No; 00908/MINTP/DR of 1997 to publish guidelines for the consideration of environmental impact of road maintenance;
11. Circular Letter N° 0001879/CL/MINFI of 31st December 2025 relating to the execution, Monitoring and Control of the execution of the Budgets of Regional and Local Authorities for 2026 financial year.
12. Unified Technical Documents (DTU) for building works;
13. Applicable standards;
14. Other instruments specific to the domain concerned with the contract.

#### **Article 7: Communication**

- 1.1 All communications within the framework of this contract shall be written and notifications sent to the following address:
  - a) In the case where the contractor is the addressee: Sir/Madam **THE CONTRACTOR**  
Beyond the time-limit of 15 days fixed in article 6(1) of the GAC to make his domicile known to the Project Owner and Contract Manager, correspondences shall be validly addressed to Ndu Council;
  - b) In the case where the Project Owner is the addressee: Sir **The Mayor of NDU** with a copy addressed to the Contracting Authority, Contract Manager, Contract Engineer, Project Manager and where need be, within the same deadline.
  - c) In the case where the Contracting Authority is: Sir **The Mayor of NDU** with a copy addressed within the same deadline to the Project Owner, Contract Manager, Contract Engineer and Project Manager, where applicable
- 1.2 The contractor shall address all written notifications or correspondences to the Contract Engineer with a copy to the Contracting Authority.

#### **Article 8: Administrative Orders:** The various Administrative Orders shall be established and notified as follows:

- 8.1 The Administrative Order to start execution of works shall be signed by the Contracting Authority and notified to the contractor by the Project Manager with a copy to the Contract Manager, Contract Engineer, the Paying Body, MINMAP and ARMP where applicable.
- 1.2 Administrative Orders with an incidence on the objective, the amount and execution deadline shall be signed by Contracting Authority and notified by the Project Manager to the Contractor with a copy to the Contracting Authority, the Contract Manager, the Contract Engineer, the Project Manager and the Paying Body. The prior endorsement of the Paying Body shall possibly be required before the signature of those that have an incidence on the amount.
- 1.3 Administrative Orders of a technical nature linked to the normal progress of the work and without financial incidence shall be signed directly by Project Manager and notified to the contractor by the Contract Engineer (where applicable) with a copy to the Contracting Authority and Contract Manager.
- 1.4 Administrative Orders serving as warnings shall be signed by the Project Owner and notified to the contractor by the Project Manager with a copy to the Contracting Authority, the Contract Engineer and Project Manager.
- 1.5 Administrative Orders for suspension or resumption of work as a result of the weather or any other case of force majeure shall be signed by the Contracting Authority and notified by the Project manager to the contractor with a copy to the Project Owner, Contract Manager, Contract Engineer and Project Manager.
- 1.6 Administrative Orders prescribing works necessary to remedy disorders which could appear on structures during the guarantee period and not related to normal usage shall be signed by the Project Manager upon the proposal of the Contract Engineer and notified to the contractor by the Contract Engineer.
- 1.7 The contractor has a time-limit of fifteen (15) days to issue reservations on any Administrative Order received. Having reservations shall not free the enterprise of executing the Administrative Orders received.
- 1.8 Concerning Administrative Order signed by the Contracting Authority and notified by the Project Owner, the notification must be done within a maximum of 30 days from the date of transmission by the Contracting Authority to the Project Manager. Beyond this deadline, the Contracting Authority shall establish the default of the Project Owner, take over from him and carry out the said notification.

#### **Article 9: Contracts with conditional phases:**

- 9.1 This contract shall be in one phase only. At the end of a phase, the Project Owner shall carry out the acceptance of the works and issue an attestation of proper execution to the contractor. This attestation shall condition the start of the following conditional phase.
- 9.2 The time-limit granted for notification of the Administrative Order to start execution of a conditional phase shall be five (5) days.

- a) One two thousandth (1/2000<sup>th</sup>) of the initial contract amount all taxes inclusive per calendar day of delay from the first to the 30<sup>th</sup> day beyond the contractual time-limit;
- b) One thousandth (1/1000<sup>th</sup>) of the initial amount of the contract inclusive of all taxes per calendar day beyond the 30<sup>th</sup> day.

23.2 The cumulated amounts of penalties for delay shall be limited to ten percent (10 %) of the initial contract inclusive of all taxes.

#### **B. Specific penalties**

23.3 Independently of penalties for overrun of contractual time-limit, the contractor shall be liable for the following special penalties for the non-observation of the provisions of the contract, especially:

- Late submission of final bond;
- Late submission of insurances;
- Late submission of the draft execution schedule if the lateness is caused by the contractor.

#### **Article 24: Payment in case of a group of enterprises:**

1. In the case of a group of enterprises, indicate the method of payment of co- and sub-contractors, where need be.
2. Indicate the method of payment of sub-contractors, where need be.

#### **Article 25: Final detailed account:**

25.1 After completion of the works and within a maximum time-limit of fourteen (14) days after the date of provisional acceptance, the contractor shall establish, based on joint reports, the draft final detailed account of works executed and which detailed account summarises the total sums to which the contractor may be entitled as a result of the execution of the whole contract.

25.2 The Contract Manager has up to thirty (30) days to notify the corrected and approved draft to the Project Manager.

25.3 The contractor has up to thirty (30) days to return the signed final detailed account.

#### **Article 26: General and final detailed account**

26.1 The Contract Manager or the Project Manager has up to thirty (30) days to *establish the general detailed account and forward to the contractor after final acceptance*.

At the end of the guarantee period which results in the final acceptance of the works, the Contract Manager draws up the general and final detailed accounts of the contract which he has had signed jointly by the contractor and the Contracting Authority. This detailed account includes:

- the final detailed account,
- the balance
- the summary of monthly payments on account.

The signing of the general and final detailed account without reservation by the contractor definitely binds the two parties, puts an end to the contract, except with regard to interest on overdue payments.

26.2 The contractor has up to thirty (30) days to return the signed final detailed account.

**Article 27: Tax and customs regulations:** Decree No. 2003/651/PM of 16 April 2003 lays down the terms and conditions for implementing the tax regulations and customs procedures applicable to public contracts. The taxes applicable to this contract include notably:

- Taxes and dues relating to industrial and commercial profits, including the AIR which is a deduction on company taxes;
- Registration dues in accordance with the Tax Code;
- Dues and taxes attached to the execution of services provided for in the contract;
- o Duties and taxes of entry into Cameroonian territory (customs duties, VAT, computer tax);
- o Council dues and taxes;
- o Dues and taxes relating to the extraction of buildings materials and water.

These elements must be included in the costs which the undertaking imputes on its running costs and constitute one of the elements of the sub-details of prices exclusive of taxes. All taxes inclusive prices mean VAT included.

**Article 28: Stamp duty and registration of contracts:** Seven (7) original copies of the contract shall be stamped by and at the cost of the contractor, in accordance with the applicable regulations.

#### **Chapter III: Execution of works**

**Article 29: Nature of the works:** The works shall include especially: (position or volume of works), See Special Technical Conditions.

### **Article 30: Role and responsibilities of the Project Owner**

30.1 The Project Owner shall be bound to furnish the contractor with information necessary for the execution of his mission and to guarantee, at the cost of the contractor, access to sites of projects.

30.2 The Project Owner shall ensure the contractor of protection against threats, insults, violence, assault and battery, slander or defamation of which he could be victim by reason of or during the exercise of his mission.

### **Article 31: Execution time-limit of the contract:**

31.1 The time-limit for the execution of the works forming the subject of this contract shall be **four (4) months - one hundred and twenty (120) days**.

31.2 This time-limit shall run from the date of notification of the Administrative Order to commence execution of the works.

**Article 32: Role and responsibilities of the contractor:** The detailed and general plan of progress of the works shall be communicated to the Project Manager in **five (05)** copies at the beginning of each.

**Article 33: Provision of documents and site:** A reproducible copy of the plans featuring in the Tender File shall be submitted by *the Contract Manager*. The Project Owner shall make available the site and access ways to the contractor at the appropriate time as the works progress.

**Article 34: Insurance of structures and civil liabilities:** The following insurance policies are required within the scope of this contract in the minimum amounts indicated hereafter within fifteen (15) days of the notification of the contract (*to be adapted*):

- *Liability insurance, business manager;*
- *Comprehensive insurance of the site;*
- *Insurance covering its ten-year obligation, where applicable.*

### **Article 35: Documents to be furnished by the contractor:**

#### **35.1 Programme of works, Quality Assurance Plan and others.**

a) Within a minimum deadline of fifteen (15) days from the date of notification of the Administrative Order to commence execution, the contractor shall submit in six (6) copies for the approval of Contract Manager after the endorsement of the Contract Engineer the execution programme of the works, his work calendar, his draft Quality Assurance Plan and the Environment Management Plan, where applicable.

This programme shall be exclusively presented according to the furnished models.

Two (2) copies of these documents will be returned to him within a deadline of fifteen (15) days from the date of receipt with:

- Either the indication "GOOD FOR EXECUTION";
- Or the indication of their rejection including the reasons for the said rejection.

The contractor has eight (8) days to present a new draft. The Project Engineer and the Contract Manager then have a deadline of five (5) days each to give his approval or possibly make comments. Delay in approving the draft execution schedule shall stay the execution deadline.

The approval given by the Contract Manager or Project Manager does not in any way release the contractor of his responsibilities. Meanwhile, works executed before the approval of the programme shall neither be ascertained nor paid for. The updated and approved schedule will become the contractual schedule.

The contractor shall constantly update on site, a schedule that will take account of real progress of the site. Significant modifications may only be made on the contractual programme upon receiving the approval of the Project Manager. After approval of the execution schedule by the Contract Manager, the latter shall transmit it within five (5) days to the Contracting Authority without staying its execution. However, if important modifications alter the objective of the contract or the nature of the works, the Contracting Authority shall return the execution schedule accompanied by reservations to be lifted within fifteen (15) days of the date of reception.

- b) The Environment Management Plan should bring out notably the choice technical conditions of the site and Secondary life, conditions of the backfill of the extraction sites and conditions for reinstating the works and installation sites.
- c) The contractor shall indicate in this schedule the equipment and methods which he intends to use as well as the personnel he intends to employ.
- d) The approval granted by the Contract Manager or Project Manager shall in no way diminish the responsibility of the contractor with regard to the harmful consequences which their implementation may cause both towards third parties and the respect of clauses of the contract.

### 35.2 Execution draft

- a) The execution plan documents (*calculations and drawings*) necessary for the realisation of all the parts of the structure must be submitted for the endorsement of the *Contract engineer or Project Manager* at most fifteen (15) days prior to the date provided for the commencement of execution of the corresponding part of the structure.
- b) The *Contract engineer* has a deadline of *five (05) days* to examine and make known his observations. The contractor then has a deadline of [04] *four days* to present a new file including the said observations.

35.3 In case of the non-observance of the approval deadlines of the above documents by the Administration, these documents shall be deemed to have been approved.

**Article 36: Organisation and safety on site:** Signboards at the beginning and end of each section must be placed within a maximum deadline of fifteen days after the notification of the Administrative Order to commence work. The services to inform in case of interruption of traffic or along the deviated itinerary are the *Delegated Contracting Authority, Project Owner, contract Engineer*

**ARTICLE 37: Commencement of work:** Before the commencement of work, the authorizing officer shall convene an enlarged site meeting with the following in attendance:

- ❖ The Contracting authority .....(Chairperson)
- ❖ Contract Engineer or his representative .....(Secretary)
- ❖ The Divisional Delegate of MINMAP or his representative; .....(Member)
- ❖ The Project Manager .....(Member)
- ❖ A representative of the Control Brigade, DD MINMAP .....(Member)
- ❖ The Divisional Delegate of MINCOMMERCE or his representative; .....(Member)
- ❖ The Chief of Local Development D/M .....(Member)
- ❖ The Divisional Delegate of MINDDEVEL .....(Member)
- ❖ The Divisional Delegate of MINEPAT or his representative; .....(Member)
- ❖ The contracting partner or duly authorized representative .....(Member)

The authorizing officer (Chairperson) shall schedule for this meeting and invite the members of the commission by a letter of invitation - not more than five (5) working days. **An attendance sheet shall be prepared and signed by all the members on site.**

During this meeting, the commission shall do the following;

- Install the project sign post;
- Fix the Building line, which shall be with respect to main roads, existing structures or natural features on the site;
- Verify the harmony between the building plans and quantities/cost estimates, and note with recommendations any discrepancies;
- Present the site log-book to the contractor;
- Establish and sign an on-the-spot report (minutes).

**Article 38: Setting out of the structures:** The Contract engineer, upon receipt of the contract documents transmitted by the Contracting Authority shall, - within five (5) days verify the proper installation of the site by the contractor, verify the respect of the building line and all other Secondary points and levels of the project, and the accuracy of the setting out by the contractor.

**Article 39: Sub-contracting:** The part of the works that can be sub-contracted shall be 30 % of the initial amount of the contract and its additional clauses.

**Article 40: Site laboratory and trials:** The project engineer has a deadline of three days to approve the contractor's personnel and laboratory as soon as the request is made.

**Article 41: Site logbook:**

40.1 The Site logbook must be systematically jointly signed by the Project Manager or Engineer, where need be and the contractor's representative each day.

40.2 It is a joint document in a single copy. Its pages must be numbered and initialled. No page should be removed. The erased or cancelled parts must be mentioned on the margin for validation.

**NB:** The Site logbook must be such that two carbon copies of each page are left behind.

**Article 42: Use of explosives:** The contractor shall not use any explosives without prior authorization.

## Chapter IV: ACCEPTANCE OF WORKS

**Article 43: Pre- Acceptance:** Before the provisional acceptance of the works, the contractor shall make a written request through the Contracting Authority to the Contract Engineer, who shall then organize a technical visit for pre-acceptance. This visit shall include the following operations.

- Qualitative and quantitative evaluations of the different works that have been executed.
- Findings and statement of the unexecuted task envisaged in the present jobbing order.
- Findings relative to the completion of the work

- Findings on the quantity of works that have been effectively realized.

These operations shall be subject to a site report drawn up and signed on the field, by the following.

- The Contract Engineers..... (Secretary)
- A representative of the Control brigade of Public Contracts..... (Observer)
- A representative of the Contracting Authority..... (Chairperson)
- The Contractor or his Representative..... (Member)

All the members shall be entitled to an indemnity each paid by the project owner.

During this pre-acceptance, the commission shall eventually specify the reserves to be up-lifted and the corresponding works to be effected before the provisional acceptance.

**Article 44: Provisional Acceptance:** The contractor shall request the Authorizing Officer in writing, to schedule and call for the provisional acceptance of the works. The report (minutes) of the Pre- Acceptance shall be attached to the said request. The Authorizing officer shall then fix the date of acceptance in collaboration with the contract Engineers and call for the task by a letter of invitation. The Acceptance Commission shall comprise the following;

- The Authorizing Officer ..... (Chairman)
- The Contract Engineer..... (Secretary)
- The contract Manager..... (Member)
- The representative or the Divisional Delegation of Public contracts ..... (Observer)
- The Project manager..... (Member)
- The Divisional Delegate of MINDEVEL or his representative;..... (Member)
- The Chief of Local Development D/M..... (Member)
- The Contractor or his Representative..... (Member)
- The stores Accountant of Ndu Council..... (Member)

All the members shall be entitled to an indemnity each paid by the project owner.

The commission shall examine the report of the Pre-acceptance and shall proceed to the Provisional Acceptance if satisfied with the works executed. An acceptance report (process - verbal) of the works shall be prepared by the Contract Engineer and signed by all the commission members on the site.

**Article 45: Final acceptance:** Final acceptance shall take place within a maximum deadline of fifteen (15) days from the date of expiry of the period of guarantee. The commission and procedure for final acceptance shall be the same as for Provisional Acceptance

**Article 46: Guarantee Period:** The guarantee period shall last for one (01) year from the date of the provisional acceptance.

## Chapter V: SUNDY PROVISIONS

### Article 47: Termination of the contract (article 74 of the GAC)

The contract may be terminated as provided by Decree N0. 2018/366 of 20th June 2018 and equally under the conditions laid down in articles 74, 75 and 76 of the GAC especially in one of the following cases:

- Delay of more than fifteen (15) calendar days in the execution of an Administrative Order or unjustified stoppage of more than seven (7) calendar days;
- Delay in work resulting in penalties of more than 10 % of the amount of the works;
- Refusal to repeat poorly executed works;
- Default by the contractor;
- Persistent non-payment for services.

**Article 48: Case of force majeure (article 75 of the GAC):** If the contractor were to raise the issue of force majeure, the thresholds below which claims shall not be admitted are:

- Rainfall: 200 millimetres in 24 hours;
- Wind: 40 metres per second;
- Flood: decennial flood frequency.

**Article 49: Disagreements and disputes (article 79 of the GAC):** Disagreements and disputes resulting from the execution of this contract may be settled amicably. Where no amicable solution can be found for a disagreement, it is brought before the competent Cameroonian jurisdiction.

**Article 50: Production and dissemination of this contract:** Ten (10) copies of this contract shall be produced at the cost of the contractor and furnished to the Contract Manager.

**Article 51: Entry into force of this contract:** This contract shall be final only upon its signature by the Contracting Authority. It shall enter into force as soon as it is notified to the contractor by the Contracting Authority.

**Article 52 and last: INFORMATION TO BE POSTED:** The Contractor shall put up a visible sign board (*total height=2.80m, width=1.20m, board thickness=2.5cm at 1,20m above the ground level with poles embedded in concrete*) at the entrance to the site on a place approved by the Contract Engineer, bearing the following text written on one side of the board.

REPUBLIC OF CAMEROON

Peace - Work – Fatherland

THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION

FINANCING: 2026 PUBLIC INVESTMENT BUDGET (MINCOMMERCE)

CONTRACTING AUTHORITY: THE MAYOR OF NDU

AUTHORIZING OFFICER: THE MAYOR OF NDU

CONTRACT MANAGER: DD/MINCOMMERCE/DM

CONTRACT ENGINEER: THE DIVISIONAL DELEGATE OF HOUSING AND URBAN DEVELOPMENT DONGA-MANTUNG

PROJECT MANAGER: CDO NDU COUNCIL

CONTRACTOR:.....

DURATION OF CONTRACT: FOUR MONTHS (120 CALENDAR DAYS)

**DOCUMENT NO. 5:**  
**Special Technical Conditions (STC)**

- I - GENERALITIES
- II- PREPARATORY WORKS-IMPLANTATION
- III- FOUNDATION
- IV - ELEVATION WORKS
- V - ROOF TRUSS AND THE COVERING
- VI - JOINERY AND METAL WORKS
- VII- ELECTRICAL INSTALLATION
- VIII - RENDERING (PLASTERING) AND COATING
- IX - PAINTING
- X- EXTERNAL WORKS
- XI - PROTECTION OF THE ENVIRONMENT
- XII - ORIGIN, QUALITY AND PREPARATION OF MATERIALS

**1 – GENERALITIES:** This present special technical specifications concern the construction of **THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN** NDU Subdivision, Donga-Mantung Division, North West Region. It is the duty of the contractor to realize the structure as per the execution plans that shall be approved by the competent authority. Through the contract Engineer, the contractor shall furnish the owner of the project and other project team members within 15 days from the date of notification to start work with an execution plan showing clearly how he intends to run the work site.

**SIGN-POSTS:** The contractor shall put in place at his expense a sign-posts indicating the ongoing work in conformity with the plans put at his disposal by the contracting authority.

**Hygiene and safety:** The contractor shall ensure total hygiene and security of the site by constructing a temporal latrine and putting up a temporal fence around the project site if need be.

The contractor shall be responsible for the protection of the structures before final reception. He shall be equally responsible for all tools and materials present at the work site. He shall seek an insurance policy to cover theft and fire incidence.

The contractor shall take all preventive measures against accidents. The owner of the project has the right to intervene in case of any emergency without necessary interfering with the activities of the contractor.

The contractor shall verify all dimensions on the plans. For execution, no dimension shall be measured with a scale rule from the plans. The contractor shall check in-situ the possibility of translating the dimensions on plans to the structure before work begins. He shall refer to the Project Engineer in case of any doubt. He shall not on his own modify anything on the structure and shall inform the Project Engineer of any changes that he considers necessary.

All modifications accepted by the contractor shall be accomplished within a specified duration and at his cost without modification of the contract amount. The owner of the project shall have the right to the final choice in case of any modification.

**3 - PREPARATORY WORKS – SETTING OUT:** These works concern the clearing of the site and evacuation of the rubbles, the clearing and levelling of the site where necessary. The setting out will be in respect to the technical plans.

The setting out profile boards will be at least 1.20m from the outside axes, this to facilitate trenching and other earth works and good circulation. The commencement of excavation will be accepted by the Contract Engineer after checking the conformity of the setting out.

**The minimal depth of the excavation trenches shall be of 60cm**, and depending on the bearing capacity of the soil. Where there is black cotton soil or soil with low bearing capacity at the bottom of the trench, the contractor shall continue excavation up to a depth as will be approved by the Contract Engineer. The excavations will be done manually and no concrete or mortar shall be laid on the bottom of the trench without the acceptance of the trench bottom of excavation by the Contract Engineer.

The descriptive notice completes or confirms the indications on the execution plans. In the case of contradictions between the plans and the descriptive notice, the project team shall be contacted for examination, elaboration and conclusion.

These technical specifications have as objective the definition of the consistence of works to be executed in accordance with the plans and according to technical norms for the construction of famer's warehouse building.

**3 – FOUNDATION:** A layer of blinding concrete of 6cm thick, batched at 150 kg/m<sup>3</sup> of firm consistency shall be laid at the bottom of the trench, on which the footings shall rest. The foundation peripheral walls will be of stone masonry or frog filled foundation blocks 20x20x40, laid with cement mortar, on which shall lay a continuous beam of 20 x 20cm in reinforced concrete batched at 350 kg/m<sup>3</sup> of concrete.

The foundation will be filled with earth of good quality in successive compacted layers of 20cm where the fill depth exceeds 30cm. An over-site concrete of thickness 8cm batched at 300kg/m<sup>3</sup> shall be laid over the entire compacted surface of the foundation area.

**The floor shall be in cement grout, smoothly trowel finished on a sand screed of 3mm thick.**

**4 – ELEVATION WORKS:** The elevation walls will be in agglomerated hollow blocks of 15 x 20 x 40cm with a good crushing resistance. The mix for block moulding should give at most 32 blocks per bag of cement for blocks of 15x20x40 cm. They shall be cured for at least 21days before lying on the elevation walls. The reinforced concrete pillars of section 15x15 and 15x30 at 350 kg/m<sup>3</sup> will be cast as one raises the agglomerated hollow blocks walls and this is to permit a good adhesion. The characteristic strength of concrete at 28 days should not be less than 16Mpa. For the maximal spacing of the pillars see building plans. The lintels 15 x 20 in reinforced concrete at 350 kg/m<sup>3</sup> will be levelled to + 2,10m above the level of the finished foundation.

The average height under the ceiling shall be 3,00m.

A binding course of 15 x 20 cm in reinforced concrete at 350 kg/m<sup>3</sup> will be laid above the finished level of the agglomerated hollow blocks walls with fixing wires so as to receive the wooden roof truss.

**5 – ROOF TRUSS AND THE COVERING:** The work of the roof truss shall commence 14 days after the concreting of the wall plate, ie after the concreting of the wall plate, works shall halt for 14 days to allow the structure gain strength before the roof truss is constructed.

- **Trusses:** shall be of locally sawn and treated hard wood (eucalyptus inclusive), shall compose of single frame rafters of 5cmx15cmx4m and spaced at 1.50m interval with a king-post of 200cm high. These rafters will be solidly attached to the wall plate with the help of standby beam iron rods also spaced at 1.50m spacing;

- **Purlins and noggin:** shall consist of 5x8cmx4m locally sawn timber from hard wood (eucalyptus inclusive). All structural timber shall be treated with carbonyl. The timber for the roof work will be of good quality, with the straight grain and free of any defect.

- **Roofing sheets:** shall be in high rib aluminum sheets (Tôle Bac) of type 4/10mm. The sheets shall be fixed onto the purlins using twisted zinc nails 90mm, equipped with bituminous rubbers caps.

- **Facial board** shall be 30cm wide and of high rib aluminum sheets (tôle Bac) of 3.5/10mm thickness, including a lining.

- **Ceiling-** shall be in 4mm thick (red plywood on both sides), fastened in sheets of 60x120 to noggin of 4cm thick or 5x8 and treated with carbonyl. The noggin shall be spaced 60cm center to center and braced appropriately. Eaves shall be equipped with ventilated pre-cast blocks. An access shall be provided into the loft (ceiling of warehouse). The external ceiling shall be in smooth aluminum sheets (tôle lisse) nailed to noggin and fastened with wooden ceiling battens.

## **6 – JOINERY**

### **Doors and Windows:**

- Door shutters (120X220)cm and (90x220)cm shall be made of double metallic panels fixed on metallic angle bars (35x35)mm securely anchored to the walls. The door shutter of the office shall open to the inside while the doors of the warehouse shall open to the outside.

- The window openings (150 X 120)cm shall be fitted with sliding aluminum glazed panel shutters internally and fixed external window protectors (150 X 220)cm of vertical striped metallic tubes (30mm) welded to a frame of angle bar (35x35)mm

**7 – ELECTRICAL INSTALLATION:** The interior facilities (sheaths VGV cables, TH etc...) will be executed according to the norms and the rules concerning electrical installations at the time of the over-site concrete or as the agglomerated hollow blocks walls are being raised. Accessories and luminous elements (sockets, switches etc...) will be of good model. The set of facilities will be joined to a general earth hold.

**8 – RENDERING (PLASTERING) AND COATINGS:** The wall rendering (thickness at least 2cm cm on both sides of the walls) will be of cement mortar at 400 kg/m<sup>3</sup>. There will be an under-coat layer and a finish layer floated and foamed to finish. They must be well cut horizontally and vertically using a **straight edge**. All walls shall receive a base coat of spatadash before plastering is done.

**9 – PAINTING:** A layer of impression in ordinary paint will be applied previously on all the walls as priming layer. The interior walls will be painted in water paint (pantex 800). The external walls will be painted in water resistant paint (pantex 1300 type). Colour tinted tubes will be chosen to achieve the desired **magnolia** colour. The ceiling shall be painted in crystal white glue paint. All metal works shall be painted with oil paint - Glyptal resien lacquer, in two coats. A primary coat of antirust before final painting is done. Skirting shall be carried out in oil paint at 20cm from the floor, externally and internally with coffee brown colours.

**10 – EXTERNAL WORKS: Gutters:** To be excavated 40cm wide and 30cm deep at the rain drops. The walls of gutters are to be constructed in concrete and the floor well rolled and smoothen out with ordinary cement concrete providing a slope of 10% for the flow of water with an offshoot of at least 3m to the environment.

**Prefabricated slabs** of dimensions (120X120)cm wide each shall be provided at the doors of (120X220)cm and (90X220)cm of the office over the gutters at right angles.

**Steps** shall be constructed out of frog filled (15X20X40)cm blocks, 1,20m wide as the case may be. Equally, **a ramps** cast insitu of dimensions (1.20X2.1X0.2)m shall be provided at the main entrance of the building for the handicaped on wheel chairs and also to enable trucks with goods to get right to the main door of the magasin.

**11 - PROTECTION OF THE ENVIRONMENT:** The entrepreneur shall obtain an attestation of environmental impact notice from the council concerned, indicating that the environment impact notice has been carried out by the project owner

The site must be chosen outside of the sensitive zones, in order to limit the site clearing, the extraction of bushes, the setting out of the building and general circulation.

The site must foresee an adequate drainage of waters on the whole surface. The maintenance areas and of washing should be concreted. These maintenance areas should have a slope toward a cesspool provided for the purpose and toward the inside of the platform in order to avoid the out-flow of the polluting products toward the site and the neighbourhood.

At the end the works, the entrepreneur will do all necessary works to the restoration of the various places of the site. The entrepreneur should fold all his material, and equipment. He should demolish all stationary installation, as foundation, support made of concrete or metallic, etc. in order to put back the site in its nearest initial state. No equipment nor materials should be abandoned on the site, nor in the vicinity after the execution of all the works. Left-over materials are to be covered with a layer of earth, and the site has to receive an adequate drainage in order to avoid all erosion as the case may be.

**12 - ORIGIN, QUALITY AND PREPARATION OF MATERIALS:** The fine and coarse aggregates may either be from the river or quarry crushed and must be approved by the Contract Engineer before any use on the site. The sand (0/5) shall have very fine elements settlement of less than 4%. The gravels (5/15 or 15/25) shall be clean and well graded with very fine elements settlement of less than 2%. The cement shall be CPA 325 class from an approved factory.

The reinforcement steel for reinforced concrete shall be of type HA FeE400 for the main reinforcement steel rods and round-smooth RL E235 for the stirrup rings. Any fill material for the foundation and the surroundings structures shall have no particle dimension above 50mm and with plasticity index of less than 35. Fill materials shall also be free from organic elements and shall have a good granularity grading. No black vegetable soil shall be accepted for backfilling.

Stones for masonry works shall be of basalt, gneiss or granite type, be esthetical and should be gotten from the quarry or deposits approved by the Contract Engineer with dimension sizes of not less than 20cm.

### 1) CONCRETE:

**-Ordinary concrete:** specifically lean concrete shall be 5cm thick and laid all round the excavated foundation trenches before the block work is carried out and dosed at 150kg/m<sup>3</sup>.

**- Over-site concrete:** shall be 8cm thick laid on the entire floors and paved area between walls and gutters dosed at 300kg/m<sup>3</sup> over the entire surface.

NB: The external veranda shall be 5cm below the level of the internal floor with 2% slope, sloping to the outside.

**-Reinforced concrete:** shall be specifically for pillars, beams damp proof course (DPC), lintels and tie-beams and their mixture shall be in a proportion of 350kg/m<sup>3</sup>.

NB: All concrete works should be properly cured (i.e. water three times a day for seven days)

### NOTE: Reinforcement Schedule.

Nº	STRUCTURE	MAIN BARS		STIRRUP		Mix	TYPE
		Nos	ϕ	ϕ	Spacings		
1	Damp proof course	4	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-400
2	Lintel (15x20)	4	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-400
3	Veranda Pillars 15x 30	6	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-400
4	Wall pillars 15x15	4	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-400
5	Wall plate (tie-beams) 15x20	4	8mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-400
6	Beams 20x20 and 15x20	4	10mm	6mm	20cm	350kg/m <sup>3</sup>	Fe-E-400

--	--	--	--	--	--	--	--

NB: All rods should preferably be from the local markets.

- **Sand:** Will be free from oxide, organic material of animals or plant origin. Sieving shall vary from 0.08 – 2.5mm for mortar and other resisting surfaces like concrete structure shall vary from 0.16 – 5mm. It shall be river sand and nothing else.

- **Aggregate:** shall consist of natural and homogeneous materials or crushed stones. Tiny layer of grave (dust) shall be removed by sieving, blowing or washing.

- **Water:** To be used for the mixture mortar, concrete and washing of aggregates. Shall be clean and free from impurities; meaning potable water.

- **Cement:** To be used mostly for cement mortar, all concrete mixtures shall satisfy the general conditions laid down by regulation in force. It will be type CPA325 Portland cement and shall not show any trace of uneven mixture. Storage on the building site shall be done on a dry and ventilated floor. Any stock presenting an unsatisfactory pulverulent condition will be discarded and cleared away within four (04) days.

- **Rods:** shall be mild steel reinforcement, Tor or Steel in accordance with the R/C &3 rules. The steel shall be perfectly clean without any trace of rust, non-adhesive to paint or grease.

- **Shuttering:** hard wood, to bear without any noticeable distortion, the load and pressure of concrete, the effect of vibration and weight of workers involved in setting it up.

- **MASONRY:**

-**Blocks-** Load bearing wall shall be mounted in compressed cement blocks of (15x20x40) cm for load bearing walls of PC300 Kg/m<sup>3</sup> (at most 32 blocks per bag of cement). Blocks should show an appreciable degree of resistance to violent pressure.

**All blocks shall be cured for at least 21 days before being used.**

-**Plastering:** All plastering shall be applied using a trowel, float, straight edges and sponge. Cement mortar mix in a proportion of 400kg/m<sup>3</sup> will be used to plaster all previously rejoined areas on all masonry and concrete works, and then thinly floated. The final thickness of the plastering shall not be less (02cm on both sides of the walls). The external walls shall receive a coat of spatadash before plastering is done on it.

-**Screeding:** a smooth layer of ordinary cement screed 400kg/m<sup>3</sup> (1:2) finish shall be spread on the 8cm thick concrete floor and the screed shall be 3cm thick.

**13 GUTTERS:** To be excavated 40cm wide and 30cm deep at the rain drops and to be provided particularly at the frontage and the two ends of the building as the topography of the terrain is relatively flat. The walls of gutters are to be constructed in concrete and the floor will be rolled and smoothen out with ordinary cement concrete providing a slope of 10% for the flow of water for level surfaces.

**15- Wood – Material:** The wood must be pure and should not have nodes, foreign bodies or fractures due to sawing. This shall be locally sawn hard wood (eucalyptus inclusive).

**DOCUMENT N°. 06**  
**THE UNIT PRICE SCHEDULE**

	BILL OF QUANTITIES AND COST ESTIMATES FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET, IN NDU SUB DIVISION, DONGA MANTUNG DIVISION OF THE NORTH WEST REGION.			
S/N	DESCRIPTION OF TASK	UNIT	UNIT PRICE IN FIGURES	UNIT PRICE IN WORD
	<b>100:PRELIMINARY WORKS</b>			
102	Clearing of site	m <sup>2</sup>		
103	Studies and site Installation	ff		
104	Settingout of the building	LS		
105	Execution program and Report of execution, environmental impact notice and as-built plan etc)	ff		
	<b>SUBTOTAL 100</b>			
	<b>200:EARTHWORKS</b>			
201	Levelling of platform	m <sup>2</sup>		
202	Digging of foundation trenches and footings	m <sup>3</sup>		
203	Backfilling with selected Laterite soil	m <sup>3</sup>		
	<b>SUBTOTAL 200</b>			
	<b>300: FOUNDATION</b>			
301	Blinding Concrete	m <sup>3</sup>		
302	Foundation of block 20x20x40cm	m <sup>2</sup>		
303	R.C. for , foundation pillars and ground beams	m <sup>3</sup>		
304	Mass Concrete floor (12cm thick )	m <sup>3</sup>		
	<b>SUBTOTAL 300</b>			
	<b>500: MASONRY WORKS/ELEVATIONS</b>			
501	Blocks of 15x20x40 for wall elevation	m <sup>2</sup>		
502	Plastering of walls with cement mortar dosed at 350kg/m <sup>3</sup>	m <sup>2</sup>		
503	R.C. for pillars, columns, lintels, sale slabs and chain beam dosed at 350kg/m <sup>3</sup>	m <sup>3</sup>		
506	Access ramps for handicaps of 2m wild	U		
	<b>SUBTOTAL 500</b>			
	<b>600: ROOF</b>			
601	Supply and assembling roof trusses including all charges	U		
602	Supply and assembling of Purlins and fascia laths for gables	m <sup>3</sup>		

603	Supply and fixing of ceiling boards of 4mm, including noggings and all other charges	m <sup>2</sup>			
604	Supply and fixing eave or external ceiling with the smooth aluminium of 0.35 including noggings all other charges	m <sup>2</sup>			
605	Supply and fixing hard aluminium roofing sheets (tole bac 5/10mm)	m <sup>2</sup>			
606	Supply and fixing Fascia board sheet (tole bac 3.5/10mm of 30cm height) including lining	ml			
607	Angle sheets of 50cm large	ml			
608	Supply and fixing aliminium sheet for ridge cap	ml			
609	Ventilation of roof with (pre-fabricated) at eaves	U			
	<b>SUBTOTAL 600</b>				
	<b>700: METALLIC/WOOD WORKS</b>				
702	Complete Wooden doors of 70x220	U			
703	Metal doors of 90x220 fixed to wooden frames (with PACO and two pad locks) complete	U			
	<b>SUBTOTAL 700</b>				
	<b>800: PLUMBING WORKS</b>				
801	All plumbing works in wet rooms, PVC 100 for rain water from the roof	LS			
802	Flexible showers, mirror and all complete accessories, with floor drain	U			
803	Complete wash hand basin 50x50	U			
804	Toilet paper holder	U			
805	Septic tank for 80 users	U			
806	Soak away pit for 80 users	U			
807	Toilet pot	U			
808	Inspection chambers	U			
809	Tiling of toilet floor and walls with 5x5 cm ceramic tiles, height 1.8m	m <sup>2</sup>			
	<b>SUBTOTAL 800</b>				
	<b>900: ELECTRICAL INSTALLATIONS/ SOLAR ELECTRIFICATION</b>				
901	Supply and fixing flexible pipes	ml			
902	Supply and fixing cables V.G.V 1.5mm <sup>2</sup>	ml			
903	Supply and fixing cables of TH 2.5mm <sup>2</sup>	ml			
904	Supply and fixing complete floorescent bulbs 1.20 including charges complete (4ft)	U			
905	Supply and fixing embeded Switches	U			

906	Supply and fixing embeded sockets outlets	U			
907	Supply and fixing coper earth cables of 29mm <sup>2</sup> including earth rod, folwing the specifications of standard NFC 15.100	U			
908	Electric control board for all new circuits with a circuit breaker and anti-thunder	U			
910	Fasteners, connectors, cups, junction box, all security charges,connection to existing network in the school where applicable.	Ls			
911	solar electrification	ls			
	<b>SUBTOTAL 900</b>				
	<b>1000: PAINTING</b>				
1001	Preparation of the surfaces	m <sup>2</sup>			
1002	Application of two coats of acrylic paint of type pantex 800 for ceiling	m <sup>2</sup>			
1003	Application of two coats of acrylic paint of type pantex 1300 external wall	m <sup>2</sup>			
1004	Application of two coats of acrylic paint of type pantex 800 for internal wall	m <sup>2</sup>			
1005	Application of two coats of glycero-rophtalic or oil paint skirting 30cm from the floor	m <sup>2</sup>			
	<b>SUBTOTAL 1000</b>				
	<b>1100: EXTERNAL WORKS</b>				
1101	Rain water gutters for drainage 30cmx40cm	ml			
1102	Concreting of External veranda	m <sup>2</sup>			
1103	Supply and laying of drain slabs or covers of 60cm (thickness = 12cm)	u			
	<b>SUBTOTAL 1100</b>				
	<b>1200: HYGIENE AND ENVIRONMENTAL PROTECTION</b>				
1	provision of ten(10) trash cans, one incerating pit(2x2x1.5)m and planting of ten trees well protectd with wire mesh	LS			
	<b>SUBTOTAL 1200</b>				

DOCUMENT N°. 07  
**BILL OF QUANTITIES AND COST ESTIMATES**

	BILL OF QUANTITIES AND COST ESTIMATES FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET, IN NDU SUB DIVISION, DONGA MANTUNG DIVISION OF THE NORTH WEST REGION.				
S/N	DESCRIPTION OF TASK	UNI T	Q'TY	U.P	AMOUNT
	<b>100:PRELIMINARY WORKS</b>				
102	Clearing of site	m <sup>2</sup>	400.00		
103	Studies and site Installation	ff	1.00		
104	Settingout of the building	LS	1.00		
105	Execution program and Report of execution, environmental impact notice and as-built plan etc)	ff	1.00		
	<b>SUBTOTAL 100</b>				
	<b>200:EARTHWORKS</b>				
201	Levelling of platform	m <sup>2</sup>	67.54		
202	Digging of foundation trenches and footings	m <sup>3</sup>	121.00		
203	Backfilling with selected Laterite soil	m <sup>3</sup>	85.60		
	<b>SUBTOTAL 200</b>				
	<b>300: FOUNDATION</b>				
301	Blinding Concrete	m <sup>3</sup>	7.56		
302	Foundation of block 20x20x40cm	m <sup>2</sup>	121.65		
303	R.C. for , foundation pillars and ground beams	m <sup>3</sup>	25.67		
304	Mass Concrete floor (12cm thick )	m <sup>3</sup>	4.56		
	<b>SUBTOTAL 300</b>				
	<b>500: MASONRY WORKS/ELEVATIONS</b>				
501	Blocks of 15x20x40 for wall elevation	m <sup>2</sup>	350.00		
502	Plastering of walls with cement mortar dosed at 350kg/m <sup>3</sup>	m <sup>2</sup>	700.00		
503	R.C. for pillars, columns, lintels, sale slabs and chain beam dosed at 350kg/m <sup>3</sup>	m <sup>3</sup>	30.78		
506	Access ramps for handicaps of 2m wild	U	2.00		
	<b>SUBTOTAL 500</b>				
	<b>600: ROOF</b>				
601	Supply and assembling roof trusses including all charges	U	20.00		
602	Supply and assembling of Purlins and fascia laths for gables	m <sup>3</sup>	4.56		

603	Supply and fixing of ceiling boards of 4mm, including noggings and all other charges	m2	36.65		
604	Supply and fixing eave or external ceiling with the smooth aluminium of 0.35 including noggings all other charges	m <sup>2</sup>	67.00		
605	Supply and fixing hard aluminium roofing sheets (tole bac 5/10mm)	m <sup>2</sup>	150.00		
606	Supply and fixing Fascia board sheet (tole bac 3.5/10mm of 30cm height) including linning	ml	121.00		
607	Angle sheets of 50cm large	ml	240.00		
608	Supply and fixing aliminium sheet for ridge cap	ml	240.00		
609	Ventilation of roof with (pre-fabricated) at eaves	U	6.00		
	<b>SUBTOTAL 600</b>				
	<b>700: METALLIC/WOOD WORKS</b>				
702	Complete Wooden doors of 70x220	U	0.00		
703	Metal doors of 90x220 fixed to wooden frames(with PACO and two pad locks) complete	U	10.00		
	<b>SUBTOTAL 700</b>				
	<b>800: PLUMBING WORKS</b>				
801	All plumbing works in wet rooms, PVC 100 for rain water from the roof	LS	0.00		
802	Flexible showers, mirror and all complete accessories, with floor drain	U	0.00		
803	Complete wash hand basin 50x50	U	0.00		
804	Toilet paper holder	U	0.00		
805	Septic tank for 80 users	U	0.00		
806	Soak away pit for 80 users	U	0.00		
807	Toilet pot	U	0.00		
808	Inspection chambers	U	0.00		
809	Tiling of toilet floor and walls with 5x5 cm ceramic tiles, height 1.8m	m2	0.00		
	<b>SUBTOTAL 800</b>				
	<b>900: ELECTRICAL INSTALLATIONS/ SOLAR ELECTRIFICATION</b>				
901	Supply and fixing flexible pipes	ml	500.00		
902	Supply and fixing cables V.G.V 1.5mm <sup>2</sup>	ml	250.00		
903	Supply and fixing cables of TH 2.5mm <sup>2</sup>	ml	150.00		
904	Supply and fixing complete flourescent bulbs 1.20 including charges complete (4ft)	U	12.00		
905	Supply and fixing embeded Switches	U	12.00		

906	Supply and fixing embeded sockets outlets	U	10.00		
907	Supply and fixing coper earth cables of 29mm <sup>2</sup> including earth rod, folwing the specifications of standard NFC 15.100	U	1.00		
908	Electric control board for all new circuits with a circuit breaker and anti-thunder	U	1.00		
910	Fasteners, connectors, cups, junction box, all security charges,connection to existing network in the school where applicable.	Ls	1.00		
911	solar electrification	Ls	0.00		
	<b>SUBTOTAL 900</b>				
	<b>1000: PAINTING</b>				
1001	Preparation of the surfaces	m <sup>2</sup>	700.00		
1002	Application of two coats of acrylic paint of type pantex 800 for ceiling	m <sup>2</sup>	54.65		
1003	Application of two coats of acrylic paint of type pantex 1300 external wall	m <sup>2</sup>	231.00		
1004	Application of two coats of acrylic paint of type pantex 800 for internal wall	m <sup>2</sup>	78.78		
1005	Application of two coats of glycero-ropthalic or oil paint skirting 30cm from the floor	m <sup>2</sup>	65.67		
	<b>SUBTOTAL 1000</b>				
	<b>1100: EXTERNAL WORKS</b>				
1101	Rain water gutters for drainage 30cmx40cm	ml	100.00		
1102	Concreting of External veranda	m <sup>2</sup>	60.00		
1103	Supply and laying of drain slabs or covers of 60cm (thickness = 12cm)	u	20.00		
	<b>SUBTOTAL 1100</b>				
	<b>1200: HYGIENE AND ENVIRONMENTAL PROTECTION</b>				
1	provision of ten(10) trash cans, one incerating pit(2x2x1.5)m and planting of ten trees well protectd with wire mesh	LS	1.00		
	<b>SUBTOTAL 1200</b>				
	<b>TOTAL WITHOUT TAXES</b>				
	<b>VAT (19.25%)</b>				
	<b>TOTAL AIR(2.2%) or (5.5%)</b>				
	<b>TOTAL WITH TAXE INCLUSIVE (ATI)</b>				
	<b>NET PAYMENT</b>				

**DOCUMENT N°. 8**  
**FRAMEWORK OF SUB-DETAIL OF PRICES**

DESIGNATION :Studies and site installation					
No	Daily out put		Total quantity	Unit	Duration of activity
WORKMAN SHIP	Category	No	Daily wage	Days break up	Amount
	TOTAL A				
EQUIPMENT/MECHINES	Type	No	Daily rate	Days break up	Amount
	TOTAL B				
MATERIAL AND MISCELLANOUS	Type	Unit	Unit cost	Quantity	Amount
	TOTAL C				
D	DIRECT TOTAL COST			A+B+C	
E	GENERAL SITE EXPENSES			Dx%	
F	GENERAL OFFICE EXPENSES			Dx%	
G	NET COST			D+E+F	
H	RISK + BENEFITS			Gx%	
P	TOTAL COST (HT)			G+H	
V	UNIT COST (HT)			P/Q'TY	

Document No. 9:  
Model contract

REPUBLIQUE DU CAMEROUN

-----  
PAIX – TRAVAIL – PATRIE

-----  
REGION DU NORD- OUEST

-----  
DEPARTEMENT DU DONGA MANTUNG

-----  
COMMUNE DE NDU

-----  
COMMISSION INTERNE DE PASSATION  
DES MARCHES



REPUBLIC OF CAMEROON

-----  
PEACE – WORK – FATHERLAND

-----  
NORTH WEST REGION

-----  
DONGA MANTUNG DIVISION

-----  
NDU COUNCIL

-----  
INTERNAL TENDERS BOARD

JOBING ORDER N° ...../JO/ NWR/DMD/NC/NCITB/2026 OF .....2026

Awarded following OPEN NATIONAL INVITATION TO TENDER N° ...../ONIT/NWR/DMD/NC/NCITB/2026 of the..... 2026

FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION,  
DONGA-MANTUNG DIVISION, NORTH WEST REGION  
(EMERGENCY PROCEDURE)

Project Owner: THE MAYOR OF NDU

**HOLDER** : [indicate name and full address of holder]

P.O. Box \_\_\_\_\_, Tel: \_\_\_\_\_ Fax: \_\_\_\_\_

Business Registration N°. \_\_\_\_\_ at

Taxpayer's N°. \_\_\_\_\_

**SUBJECT** : Execution of \_\_\_\_\_ works;  
Lot No. \_\_\_\_\_; Network \_\_\_\_\_

**PLACE:** NTABA, NDU Subdivision **Region:** NORTH WEST

**EXECUTION DEADLINE:** One Hundred and twenty days (04) months

**AMOUNT IN CFA F:**

THT	
TTTC	
VAT (19.25%)	
AIR (Income tax) (5.5% or 2.2%)	
NET PAYABLE	

**FINANCING** : MINCOMMERCE: BIP 2026

**BUDGET HEAD :**

SUBSCRIBED ON: \_\_\_\_\_

SIGNED ON: \_\_\_\_\_

NOTIFIED ON: \_\_\_\_\_

REGISTERED ON: \_\_\_\_\_

**Between:**

The Government of the Republic of Cameroon, represented by \_\_\_\_\_ hereinafter referred to the "Contracting Authority"

**On the one hand,**

**And**

\_\_\_\_\_ **(Contractor)**

P.O. Box \_\_\_\_\_ Tel: \_\_\_\_\_ Fax: \_\_\_\_\_

Business Registration N°. \_\_\_\_\_

Taxpayer's N°. \_\_\_\_\_

Represented by M \_\_\_\_\_, its General Manager, hereinafter referred to as the "Contractor"

**On the other hand,**

Agree on the following:

## **Summary**

Part I: Special Administrative Conditions (SAC)

Part II: Special Technical Conditions (STC)

Part III: Schedule of Unit Prices (SUP)

Part IV: Bill of Quantities and Estimates

Page \_\_\_\_\_ and last page of JOBBING ORDER N° ...../JO/NWR/DMD/NC/NCITB/2026 OF ..... 2026  
AWARDED FOLLOWING OPEN NATIONAL INVITATION TO TENDER N° ...../ONIT/NWR/DMD/NC/NCITB/2026 OF THE  
..... 2026 FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION,  
DONGA-MANTUNG DIVISION, NORTH WEST REGION

With \_\_\_\_\_,

**DURATION OF EXECUTION** 120 days (04) months

**Amount of contract in CFA F:**

THT	
TTTC	
VAT (19.25%)	
AIR (2.2 or 5.5 %)	
<b>NET PAYABLE</b>	

**Read and accepted by the contractor**

(place of signature) \_\_\_\_\_ (date)

**Signature of Contracting Authority**

(place of signature) \_\_\_\_\_ (date)

**Registration**

DOCUMENT No. 10  
MODEL FORMS APPLICABLE

FORM N° 1:  
DECLARATION OF THE INTENTION TO TENDER

**COMPANY'S LETTER HEAD**

DECLARATION OF THE INTENTION TO TENDER

Fiscal stamp  
1500

I, the undersigned Mr, .....

Nationality .....

Function .....

In my capacity as General Manager of ..... P.O. BOX ..... TEL:.....

Hereby acknowledge receipt of the file for Tender Notice

N° ..... of .....

Concerning the .....

.....  
.....  
.....  
And hereby declare my intention to tender for the said project.

Done at ..... On the .....

General Manager

## FORM N° 02

### THE MODEL TENDER LETTER

I (We) the undersigned .....

Acting in the capacity of ..... in the name and on behalf of .....

..... at ..... RC N° ..... by virtue of the power vested in me (us), resident at ..... (Town) ..... P.O.Box....., telephone N°. .... after having studied all the documents of the tender file relating to the Invitation to Tender N°. ...., and after having assessed in my (our) point of view and under my (our) responsibility the nature and difficulties entailed with the execution of the job, I (we) do hereby tender and commit myself (ourselves) to carry out works **FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**, in keeping with the terms and conditions of the tender file in return for the sum of.....FCFA (.....Francs) All Taxes Inclusive, calculated on the basis of the unit prices stated in the Unit Price List and the detailed estimates, appended to this tender. The prices stated are tax inclusive.

I commit myself (we commit ourselves) if my (our) tender is retained, to execute the contract within three (03) months as from the date of notification of the award of contract.

I hereby commit myself (we hereby commit ourselves) to maintain the amount of my (our) tender for a period of sixty (60) days with effect from the deadline for submission of bids.

I (we) hereby request that the amounts due by the Contracting Authority be paid to me (us) in the national currency (FCFA) in account No..... opened in the name of....., in the records of ..... (Bank) at.....

Enclosed with this tender are:

- The price list and the detailed estimates duly filled, dated and signed.
- Other documents which in keeping with the requirements of the Tender file must be enclosed with the tender letter.

Done at....., on.....

Signature(s)

Bidder(s)

For companies, indicate:

Fiscal stamp
1500

*The company (company or trade name, form, nationality and registered office)*

« represented by the undersigned ..... » (Name, first name and status)

For companies without a legal status, indicate:

« We, the undersigned, ..... »

*(For each person: name, first name, company name, nationality, location of the registered office)*

« Constituted in a group of companies for the execution of this contract, jointly commit ourselves ..... »

**FORM N° 03**  
**THE MODEL SURETY BOND**

Bank .....

Reference of guarantee: No. ....

**To the Mayor of NDU Council, Donga Mantung Division, North West Region, Republic of Cameroon**

Invitation to Tender No. ....

**BID BOND FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**

The Contractor (5) ..... hereby submits on ..... to the Mayor of NDU a bid relating **FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**

To this effect, and in keeping with the conditions stated in the Tender file, the bidder shall present to the Mayor of NDU Council acting in the capacity of Contracting Authority, a bid bond amounting to CFA Francs ..... (6).

By this guarantee, we the undersigned,(7).....with our registered office in ....., are committed towards the Mayor of NDU Council , through the bidder for the sum of CFA Francs .....(in figures).....(in words).

By this guarantee, we irrevocably commit ourselves, without any argument or delay, to pay into an account indicated by the Mayor of NDU Council, the amount of the guarantee at the first written request, as soon as the latter shall inform us in writing that the bidder does not keep the commitment he took in his tender.

The request for payment of guarantee shall be countersigned by the Mayor of NDU Council. This guarantee shall be released latest thirty (30) days after the expiration of the validity of the tender or, in case the company shall be the successful bidder, after presentation of the performance bond which shall be kept by the Mayor of NDU Council

The laws as well as the jurisdiction of application for the guarantee shall be those of the Republic of Cameroon.

Done at ..... on .....

Mr (Mrs).....

Signature(s) & stamps .....

(5) Bidder

(6) Stated in the Special regulations governing the invitation to tender

(7) Bank

**FORM N° 04**  
**MODEL BID BOND**

Whereas \_\_\_\_\_ (Hereafter called the "the bidder") has submitted his bids dated \_\_\_\_\_, Here in after called "the bid")

KNOW YE ALL PEOPLE by the presence that WE \_\_\_\_\_, having our registered office at \_\_\_\_\_ hereinafter called "the Bank", are bound onto the Mayor of NDU Council (hereinafter called "the Contracting Authority) in the sum of \_\_\_\_\_ for which payment will and truly be made to the said Contracting Authority, the bank binds itself, its successors, and assigns by the present if our client refuses or incapable of completing the jobs as stipulated in the contract.

We undertake to pay the Contracting Authority up to the above amount upon receipt of his first written demand, without the Contracting Authority having to substantiate his demand, provided that in his demand the Contracting Authority will note that the amount claimed by him is due to him, owing to the occurrence of one or both of the two conditions, specifying the occurred condition or conditions

This guarantee will remain in force up to and including \_\_\_\_\_ ( ) days after the period of bid validity. Any demand in respect thereof should reach the bank not later than the above date.

Sealed with the common seal of the said bank this \_\_\_\_\_ day of \_\_\_\_\_

SIGNATURE OF BANK AUTHORITY

**FORM N° 05**  
**THE MODEL PERFORMANCE BOND (RETENTION BOND)**

Bank .....

Reference of guarantee: No. ....

To: THE MAYOR OF NDU COUNCIL

**REPUBLIC OF CAMEROON**

Invitation to Tender No. ....

**PERFORMANCE BOND FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**

We..... (Bank) have been informed that a contract has been signed between the **Mayor of NDU Council** acting in the capacity of the Contracting Authority, and....., acting as **FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**

In compliance with the provisions of Contract N°. ...., the contractor is bound to present to the **Mayor of NDU Council, Contracting Authority**, a performance bond for the execution of work, covering security, commitments and other obligations incumbent on the contractor under the contract, worth 3% of the amount of the contract all taxes inclusive, i.e. CFA Francs .....

We, .....(bank) do hereby commit ourselves irrevocably and without arguing to pay to the **Mayor of NDU**, at his first written request, and for three (03) months the amount of this bond, that is to say. ...., all the amounts that the contractor may owe the Contracting Authority for failing to fulfil one or more of his obligations under the contract.

The request to partially or fully stake this guarantee shall be the subject of a registered letter of justification with confirmation of receipt and a copy to the contractor clearly stating and supplementing the reasons for his request. This letter shall be countersigned by the **Mayor of NDU Council**. The bank guarantee shall take effect as from the date of notification of the contract. The original of this guarantee shall be kept by the Mayor of NDU Council.

The guarantee shall be released within sixty (60) days with effect from the date of provisional acceptance. After this date, the guarantee shall no longer apply and shall be returned to us without express request.

The laws as well as the jurisdiction of application for the guarantee shall be those of the Republic of Cameroon.

Done at ..... on .....

Mr (Mrs).....

Signature(s) & stamps .....

## FORM N° 06

### MODEL BANK GUARANTEE FOR THE REFUND OF THE START-OFF ADVANCE

Bank .....

Reference of guarantee No.....

To Mayor of NDU Council, Donga-Mantung Division, North West Region, Republic of Cameroon

Invitation to Tender N°. ....

#### BANK GUARANTEE FOR THE REFUND OF THE START-OFF ADVANCE RELATING TO THE CONSTRUCTION WORKS

We..... (Bank) have been informed that a contract shall be signed between the Divisional Delegate of Public Contracts, acting in the capacity of Delegated Contracting Authority, and..... acting as contractor **FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**

In compliance with the provisions of Article ..... of Contract N°. ...., the contractor shall be bound to present to the Mayor of NDU Council, Contracting Authority, a bank guarantee with the purpose to assure the refund of the start-off advance granted to the company and amounting to CFA Francs .....

We, .....(bank) do hereby commit ourselves, irrevocably and without arguing to pay to the Mayor of NDU Council, at the written request of the Mayor of NDU Council, and within four (04) weeks the amount of this guarantee, that is to say. .... all the amounts that the contractor may owe the Contracting Authority for failing to fulfil one or more of his obligations under the contract.

The request to partially or fully stake this guarantee shall be the subject of a registered letter of justification with confirmation of receipt and a copy to the contractor clearly stating and supplementing the reasons for his request. This letter shall be countersigned by the Mayor of NDU Council.

The bank guarantee shall take effect as from the date of payment of the start-off advance. The original of this guarantee shall be kept by the NDU Council Internal Tenders Board. The guarantee shall be released upon refund of the full amount of the advance. After this date, the guarantee shall no longer apply and shall be returned to us without express request.

The laws as well as the jurisdiction of application for the guarantee shall be those of the Republic of Cameroon.

Done at ....., on .....

Mr (Mrs).....

Signature(s) & stamps .....

**FORM N° 07**  
**THE MODEL UNDERTAKING BY THE BIDDER**

Name of project:.....Invitation to tender N°: .....

Construction of a ware house at .....

I (We) the undersigned (8) .....

Acting in the capacity of (9) .....in the name and on behalf of (10)..... at ..... RC N° ..... by virtue of the power vested in me (us), domiciled at P.O.Box..... (Town) ....., telephone No. ...., after having studied all the documents of the tender file relating to the Invitation to Tender No. ...., and after having assessed in my (our) point of view and under my (our) responsibility the nature and difficulties entailed with the execution of the job, I (we) do hereby tender and commit myself (ourselves) to carry out works **FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION** in keeping with the terms and conditions of the tender file.

I commit myself (We commit ourselves) in case my (our) tender is retained, to execute the contract within .....(.....) months as from the date of notification of award of the contract.

I hereby commit myself (We hereby commit ourselves) to maintain the amount of my (our) tender for a period of sixty (60) days with effect from the deadline for submission of bids.

Done at ..... , on .....

Signature(s).....

Bidder(s).....

For companies, indicate:

The company (company or trade name, form, nationality and registered office)

« represented by the undersigned ..... » (name, first name and status)

For companies without a legal status, indicate:

« We, the undersigned, ..... »

(For each person: name, first name, company name, nationality, location of the registered office) « Constituted in a group of companies for the execution of this contract, jointly commit ourselves ..... »

(8) Name, first name, profession, residence

(9) Position in the company

(10) Company name

FORM N° 08  
MODEL OF COMMITMENT OF AVAILABILITY

To Whom It May Concern:

Subject: COMMITMENT OF AVAILABILITY.

I the undersigned, \_\_\_\_\_ a \_\_\_\_\_ (specify diploma or certificate) and holder of National Identity Card N° \_\_\_\_\_ issued on \_\_\_\_\_ at \_\_\_\_\_ Tel: \_\_\_\_\_ is committed and available to work as \_\_\_\_\_ (specify post to be occupied) with \_\_\_\_\_ (name of company) if awarded the contract for \_\_\_\_\_ (indicate the name of project) Donga-Mantung Division of the North West Region. This is in response to Tender N° \_\_\_\_\_

Done in \_\_\_\_\_ the \_\_\_\_\_

Sign: \_\_\_\_\_

## DOCUMENT N°11: ANNEXES

### ANNEX N° 01

#### THE MODEL CURRICULUM VITAE

Name & First name : \_\_\_\_\_

Date of birth : \_\_\_\_\_

Nationality \_\_\_\_\_

Level of education

Languages Spoken	Level	Very good	Good	Average	Poor
ENGLISH	Written				
	Read				
	Spoken				
FRENCH	Written				
	Read				
	Spoken				
LOCAL LANGUAGE OF THE AREA OF THE PROJECT	Written				
	Read				
	Spoken				

Training school: \_\_\_\_\_

Date of admission : \_\_\_\_\_

Date of graduation: \_\_\_\_\_

Diploma obtained: \_\_\_\_\_ Date \_\_\_\_\_

Specific knowledge: Publication, research work \_\_\_\_\_

Date of start of service: \_\_\_\_\_

Nature of service rendered: \_\_\_\_\_

Number of years of service : \_\_\_\_\_

Number of years in the company : \_\_\_\_\_

Date of start of service in the company : \_\_\_\_\_

#### WORK EXPERIENCE (\*)

(\*) – Work attestations issued by the various employers shall be enclosed with this curriculum vitae which shall be signed.

- The curriculum vitae shall highlight the importance of projects in which the personnel has worked and the position he actually held in the said projects.

**ANNEX N° 02**  
**THE MODEL PROFESSIONAL REFERENCES**

N°	Year	Project	Name of Client, Address and Contactable telephone N°	Budgeted Project amount	Contract amount	Period of the contract	Acceptance date
1							
2							

**NB:** For each contract named in the above list, are attached the following:

- Photocopy of first and last pages of the contract,
- Photocopy of provisional or final acceptance report (as the case may be).

Done on ..... at .....

Mr (Mrs) .....

Signature(s).....

**ANNEX N° 03**  
**MODEL EQUIPMENT LIST**

SN	DESIGNATION <i>Description &amp; frame (châssis) number</i>	MARK (& HORSE POWER if vehicle)	REGISTRATION NUMBER <i>(if vehicle)</i>	QUANTITY	STATUS <i>(Hired or owned)</i>
1					
2					
3					
etc					

I the undersigned, \_\_\_\_\_ holder of National Identity Card N° \_\_\_\_\_ issued on \_\_\_\_\_ at \_\_\_\_\_ being Managing Director of this Company called \_\_\_\_\_ testifies that the above information is correct and commit myself to present any of the above equipment and tools at any given time requested. As well any of them must be present at the site before and during each phase at any given moment required or requested by the Authorities in charge of the project I am tendering for.

Remark- For equipment I will take on hire I hereby attached to this form certified attestations (*lease documents*) of commitment between I and the Owner(s) of the equipment(s).

Done on....., at .....

*Signed*

## ANNEX N° 04

### KEY STAFF

DESCRIPTION	NAME	QUALIFICATION	EXPERIENCE	FUNCTION
ADMINISTRATIVE AND TECHNICAL STAFF ON SITE				
SUPPORT STAFF				

**ANNEX N° 05**  
**MODEL OF SUB- DETAIL OF UNIT PRICE**

**ANNEX N° 06**  
**MODEL OF SITE VISIT REPORT**  
*[not more than five (05) pages]*

**I) INTRODUCTION**

TENDER N° (with project title).....

NAME OF COMPANY.....

DATE:..... TIME:.....

**II) COMMENTARY:**

II-1) Nature of the project site.....

II-2) Accessibility to the project site: .....

II-3) Vegetation (trees, shrubs etc).....

II-4) Topography of the site.....

**NB: ATTACHED TO THIS REPORT ARE PICTURES SHOWING ME ON THE SITE AND SO JUSTIFY MY COMMENTARY ABOVE**

III) AVAILABILITY OF SERVICES (water, electricity, etc)

IV) AVAILABILITY OF CONSTRUCTION MATERIALS (stones, sand, gravel, wood etc)

V) DIFFICULTIES: .....

.....

V) CONCLUSION.....

SIGNATURES:

Signature, Name and Stamp of Contractor's Engineer  
Or  
Technical Director, of Enterprise

**ANNEX N° 07**  
**THE EVALUATION GRID**  
**ANNEX 7: EVALUATION GRID**

**FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION  
ADMINISTRATIVE DOCUMENTS.**

DOCUMENT N°	DESCRIPTION
A.1	An undertaking by the bidder (declaration to tender), stamped, dated and signed by the bidder or group representative in conformity with the model attached.
A.2	An attestation of non-bankruptcy not older than 03 months, issued by the chamber of commerce or court of competent jurisdiction of the place of residence of the bidder.
A.3	An attestation of Bank account in the name of the enterprise issued by a bank or any first-order credit institution approved by the Minister in charge of finance.
A.4	Bid security (bank guarantee) of Nine hundred and sixty thousand (960,000 FCFA) from a bank accredited by MINFI and recognized by COBAC (Bank caution) and validated by CDEC.
A.5	Treasury Receipt showing the payment of the tender fee as stipulated in the Tender Notice(96,000frs).
A.6	An attestation of CNPS: current certificate from the National Social Insurance Fund (CNPS) certifying that the bidder has effectively paid his/her social contributions.
A.7	Certificate of non-exclusion attesting that the bidder is not the subject of a temporary or permanent exclusion from Public Contracts, not older than three (03) months issued by ARMP.
A.8	A certificate of tax assessment certifying that the bidder owes no taxes signed by the Director or the head of Tax Center.
A.9	Certificate of categorisation
A.10	A valid Tax payer's card.
A.11	A certified copy of Certificate of Incorporation.
A.12	Group agreement as the case may be.
A.13	Power of Attorney as the case may be signed by a notary.
A.14	The Special Administrative Conditions (SAC/CCAP), initialled on each page and signed, dated and stamped on the last page

**TECHNICAL EVALUATION**

NDU COUNCIL INTERNAL TENDERS BOARD				
TECHNICAL ANALYSIS SUB COMMISION				
THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION				
1	PRESIDENT:			
2	SECRETARY:			
3	MEMBER:			
TENDER No: ..... OF .....				
CONTRACTORS:				
A)				
B)				
C)				
Eliminatory Criteria (See evaluation of administrative files)				
Designation		BIDDERS		
		A	B	C
a. General presentation of bids		EVALUATION (Yes or No)		
a1	Presence of all documents			
a2	Properly bound with spirals			
a3	Separators in colour apart from white			
a4	Order prescribed respected as in the Tender file			
		TOTAL a	/4	/4
b. The company references(if only a receipt of categorization is presented)		/4		
References of the company in civil construction or similar works for the past Five years		EVALUATION (Yes or No)		

b1	At least 02 copies of similar contracts equal to or above the cost of the project (1 <sup>st</sup> and last page).			
b2	minutes of Provisional Reception for projects executed within the last five yrs (pluri annual projects accepted)			
b3	Minutes of final reception of similar projects executed within the past five years			
	<b>TOTAL b</b>	<b>/3</b>	<b>/3</b>	<b>/3</b>
	<b>c. Equipment (if only a receipt of categorization is presented)</b>	<b>EVALUATION (Yes or No)</b>		
c1	Proof of ownership or hire of a liason vehicle (Pick up 4 x 4 or van) (Hired or owned)			
c2	Proof of ownership or hire of a truck of at least 20 tonnes capacity			
C3	Proof of ownership or hire of a manual compactor in good condition			
C4	Proof of ownership of a carpentry kit			
C5	Proof of ownership of a masonry kit			
	<b>TOTAL 2</b>	<b>/5</b>	<b>/5</b>	<b>/5</b>
	<b>d. Personnel of the Enterprise (if only a receipt of categorization is presented)</b>	<b>EVALUATION (Yes or No)</b>		
	Works Engineer: Senior Civil Engineering Technician with at least 03yrs of experience			
d1	Certified copy of valid <i>National Identity Card</i> signed three times on it			
d2	Diploma of senior civil engineering technician, and certified			
d3	CV signed and dated by the Works Engineer			
D4	Attestation of availability duly signed by bearer and dated			
	<b>Site foreman: Civil Engineering Technician or HND with at least 3yrs experience</b>			
d5	Certified copy of valid <i>National Identity Card</i>			
d6	Certified copy of certificate of Foreman			
d7	CV signed and dated by Site Foreman			
d8	Attestation of availability duly signed by bearer and dated			
	<b>Chief builder:CAP F4, at least 3yrs of experience</b>			
d9	Certified copy of valid <i>National Identity Card</i> signed three times on it			
d10	Certified copy of diploma			
d11	Cv signed and dated			
d12	Attestation of availability duly signed by bearer and dated			
	<b>Chief carpenter: At least CAP in wood work/joinery at least three years</b>			
d13	Certified copy of valid <i>National Identity Card</i> signed three times on it			
d14	Certified copy of diploma			
d15	Cv signed and dated			
d16	Attestation of availability duly signed by bearer and dated			
	<b>Chief electrician: CAP in electricity/house lighting at least 3years</b>			
d17	Certified copy of valid <i>National Identity Card</i> signed three times on it			
d18	Certified copy of diploma			
d19	Cv signed and dated			
d20	Attestation of availability duly signed by bearer and dated			
	<b>TOTAL d</b>	<b>/20</b>	<b>/20</b>	<b>/20</b>
	<b>e) Technical Proposals</b>	<b>EVALUATION (Yes or No)</b>		
e1	Attestation of <i>Site Visit</i> signed by the director			
e2	<i>Site Visit</i> report with pictures duly signed by Engineer			
e3	Detailed technical note and proposals			
	<b>TOTAL e</b>	<b>/3</b>	<b>/3</b>	<b>/3</b>
	<b>f) The methodology of intervention and execution of work</b>	<b>EVALUATION (Yes or No)</b>		
f1	Site organisation in teams or options			
f2	Description of the socio - environment measures for site protection			
f3	Dispositions previewed for the securisation of personnel and other users			
f4	Use of local manpower			
f5	CCTP duly initialled and dated on each page and signed on the last page			
	<b>TOTAL f</b>	<b>/5</b>	<b>/5</b>	<b>/5</b>
	<b>g. Planning of execution of works</b>	<b>EVALUATION (Yes or No)</b>		
g1	Coherent planning with respect to tasks			
g2	Manpower deployment plan			
g3	Material deployment plan			
g4	Organisational chat of the enterprise			
	<b>TOTAL g</b>	<b>/4</b>	<b>/4</b>	<b>/4</b>
	<b>I. Pre-financing</b>	<b>EVALUATION (Yes or No)</b>		

e1	Attestation of credibility shall be at least 55% of the bid price			
	<b>TOTAL</b>	/2	/2	/2
	<b>GRAND TOTAL</b>	/46	/46	/46

NB: The minimal technical acceptable mark is 75% of the technical mark, i.e. All bids having less than 75/100 of the technical marks shall be eliminated.

**Resolution:**

IV	FINANCIAL ANALYSIS	EVALUATION		
		A	B	C
1	Unit Price Schedule			
2	Bill of Quantities and Cost Estimate			
3	Sub Detail of Unit Prices			
4	Bidder's Financial Proposal			
NB) The non-existence or Laxity noticed at the study of prices and Arithmetic errors shall be corrected by the Technical Sub Committee with respect to the invitation to Tender				
FINAL RESOLUTION OF THE EVALUATION COMMISSION (use the corrected offer)				

## ANNEX 8: MODELE ATTESTATION OF SITE VISIT

I the undersigned Mr./Mrs./Miss ..... [Surname and Name] The Director of ..... [Name of Company] do testify on my honour that, I Mr./Mrs/Miss ..... (Surname and Name) Director or Engineer of the Company: ..... (Name of Enterprise) have actually visited the site which is going to receive the structure relative to **OPEN NATIONAL INVITATION TO TENDER No. ..../ONIT/NWR/DMD/NC/NCITB/2026 OF ..... 2026 FOR THE CONSTRUCTION OF A MARKET SHED AND 10 STORES IN NTABA MARKET IN NDU SUBDIVISION, DONGA-MANTUNG DIVISION, NORTH WEST REGION**

I declare:

- To have carried out a thorough study of the site taking into consideration all the constraints relative to the execution of the job with respect to norms.
- To establish a unit price schedules taking into account the difficulties of the site relative to the execution of the works and shall on no condition claim the Delegated Contracting Authority for any increase of unit price.

In Testimony Whereof, this present **ATTESTATION OF SITE VISIT** is established and issued to serve the purpose it deserves.

Date .....

Stamp of enterprise

Signature and Names of the Director


**DOCUMENT NO. 12:**  
**List of banking establishments and financial bodies authorized to  
issue bonds for public contracts**

**I- BANKS**

1. Afriland First Bank
2. Banque Atlantique
3. Banque Gabonaise pour le Financement International (BGFI BANK)
4. Banque International du Cameroun pour l'Epargne et le Crédit (BICEC)
5. CITI Bank
6. Commercial Bank of Cameroon (CBC)
7. Ecobank
8. National Financial Credit Bank
9. Société Camerounaise de Banque au Cameroun
10. Société Générale de Banque au Cameroun
11. Standard Chartered Bank Cameroon
12. Union Bank of Cameroon
13. United Bank for Africa.
14. C C A Bank

**II- Insurance companies**

15. Chanas Insurance;
16. Activa Insurance
17. Zenith Insurance



**DOCUMENT N°13:  
WORKING PLANS**