



ADDITIF 1 N° 332 AD/MINTP/SG/DCT/CAO/CEA3/KG/2026 DU 14 AOUT 2026

RELATIF À L'APPEL D'OFFRE NATIONAL OUVERT N°055/AONO/MINTP/CIPM-TERI/2026 DU 07 JUIL 2026, EN PROCÉDURE D'URGENCE POUR L'EXECUTION DES TRAVAUX D'ENTRETIEN DE LA ROUTES EN TERRE CARREFOUR LITIEU (INTER R0606)-MELAH-FOSSONG WENTCHENG (MARCHE WADEUH)-NKUIKOP-FONDONERA (NGUIANGO)-ATSOP-MEKET-MEKELEWOUM-SANTCHOU(TAWANG INTER R0606).DANS LA RÉGION DE L'OUEST (DÉPARTEMENT DE LA MENOUA), PROGRAMME 2025.

FINANCEMENT : BIP DU MINTP, EXERCICE 2025, 2026 et 2027

Les dispositions du Cadre du Bordereau des Prix Unitaires et du Cadre du Détail Quantitatif et Estimatif de l'Appel d'Offres National Ouvert susmentionné sont modifiées ainsi qu'il suit :

AU LIEU DE :

Pièce N° 6 : CADRE DU BORDEREAU DES PRIX

	SÉRIE 100: NETTOYAGE ET TERRASSELMENT		
TM119	DEROCTAGE Ce prix rémunère dans les conditions générales prévues au marché, au mètre cube (m3), les opérations de déroctage y compris toutes sujétions. Le mètre cube à:		
		M3	

Pièce N° 7 : CADRE DU DÉTAIL QUANTITATIF ET ESTIMATIF

DEVIS QUANTITATIF ET ESTIMATIF POUR LES TRAVAUX D'ENTRETIEN DU TRONCON DE ROUTE COMMUNALE : CARREFOUR LITIEU (INTER R0 606) - MELAH - FOSSONG WENTCHENG (MARCHE WADEUH) - NKUIKOP - FONDONERA (NGUIANGO) - ATSOP - MEKET - MOKELEWOUM - SANTCHOU (TAWANG INTER R0 606) ; longueur : 29,000 km

N° Prix	DESIGNATION	Unité	Quantité	P.U. (FCFA)	Montant (FCFA)
SERIE 100 : NETTOYAGE - TERRASSEMENTS					
TM 108a	Remblai provenant d'emprunt	m3	6 975,00		
TM 117	Plus-value aux prix n° 108 et 208a pour transport > 5 km	m3 x km	34 320,00		
Sous Total Série 100					
SERIE 600 : DIVERS					
TM 601d	Béton armé pour poutres de 20 x 40 cm et caniveaux de 50 x 60 cm	m3	8,00		
TM 611a	Provision pour déplacement des réseaux (ENEO, CAMWATER, CAMTEL)	prov	1,00		

LIRE :

Pièce N° 6 : CADRE DU BORDEREAU DES PRIX

	SÉRIE 100: NETTOYAGE ET TERRASSELMENT		
TM119	DEROCTAGE Ce prix rémunère dans les conditions générales prévues au marché, au mètre cube (m3), les opérations de déroctage y compris toutes sujétions. Le mètre cube à:		

		M3	
TM120	Liant Hydraulique Routier Fourniture et mise en œuvre du Liant Hydraulique Routier y/c toutes sujétions Ce prix rémunère, dans les conditions générales prévues au marché, à la tone (t), la scarification de la chaussée en place sur toute sa largeur y compris accotements et, le retraitement des matériaux au produit stabilisant sur une profondeur de 15 à 30 cm, pour couches d'assises de la nouvelle chaussée. Les apports éventuels en matériaux sont rémunérés au Prix 104. Ce prix comprend notamment : • toutes les prestations géotechniques et de topographie nécessaires à l'opération, • la scarification de la chaussée existante après reconstitution éventuelle des accotements et des sections nécessitant des matériaux d'apport pour nivellement ; • la fourniture, le transport et le stockage à pied d'œuvre du produit stabilisant agréé pour mise en œuvre dans le cadre du présent marché ; • l'approvisionnement en eau de qualité pour la mise en œuvre ; • la réalisation de la planche de convenance préalable, à la charge de l'entreprise, et sa validation par le Maître d'Œuvre ; • le retraitement en place des matériaux scarifiés, pour couches d'assises y compris • le réglage des matériaux, et compactage à 97% de l'OPM ; • le contrôle intérieur de l'entreprise tel que défini au CCTP et dans le SOPAQ ; • toutes sujétions de mise en œuvre de faibles quantités ou en faible largeur ; • et toutes sujétions. La Tone à :	t	

Pièce N° 7 : CADRE DU DÉTAIL QUANTITATIF ET ESTIMATIF

DEVIS QUANTITATIF ET ESTIMATIF POUR LES TRAVAUX D'ENTRETIEN DU TRONCON DE ROUTE COMMUNALE : CARREFOUR LITIEU (INTER R0 606) - MELAH - FOSSONG WENTCHENG (MARCHE WADEUH) - NKUIKOP - FONDONERA (NGUIANGO) - ATSOP - MEKET - MOKELEWOUM - SANTCHOU (TAWANG INTER R0 606) ; longueur : 29,000 km					
N° Prix	DESIGNATION	Unité	Quantité	P.U. (FCFA)	Montant (FCFA)
SERIE 100 : NETTOYAGE - TERRASSEMENTS					
TM 108a	Remblai provenant d'emprunt	m3	0		
TM 117	Plus-value aux prix n° 108 et 208a pour transport > 5 km	m3 x km	0		
TM120	Liant Hydraulique Routier	t	881,45		
Sous Total Série 100					
SERIE 600 : DIVERS					
TM 601d	Béton armé pour poutres de 20 x 40 cm et caniveaux de 50 x 60 cm	m3	0		
TM 611a	Provision pour déplacement des réseaux (ENEO, CAMWATER, CAMTEL)	prov	0		

Les modifications suivantes s'appliquent au Cadre du Bordereau des Prix Unitaires et au Cadre du Détail Quantitatif et Estimatif

Le reste sans changement.

14 AOUT 2026

Yaoundé, le _____



ADDENDUM No. 1 **332** /AD/MINTP/SG/DCT/CAO/CEA3/KG/2026 **ASUJ 2026**

RELATING TO NATIONAL OPEN INVITATION TO TENDER No. 055/AONO/MINTP/CIPM-TERI/2026 OF 07 JULY 2026, UNDER EMERGENCY PROCEDURE, FOR THE EXECUTION OF MAINTENANCE WORKS ON THE EARTH ROAD CARREFOUR LITIEU (INTER R0606) – MELAH – FOSSONG WENTCHENG (WADEUH MARKET) – NKUIKOP – FONDONERA (NGUIANGO) – ATSOP – MEKET – MEKELEWOUM – SANTCHOU (TAWANG INTER R0606), IN THE WEST REGION (MENOUA DIVISION), 2025 PROGRAMME.

FUNDING: MINTP PUBLIC INVESTMENT BUDGET, 2025, 2026 AND 2027 FINANCIAL YEARS

The provisions of the Form of the Schedule of Unit Prices and of the Form of the Bill of Quantities and Estimates of the above-mentioned National Open Invitation to Tender are amended as follows:

INSTEAD OF:

Item No. 6: FORM OF THE SCHEDULE OF UNIT PRICES

SERIES 100: CLEARING AND EARTHWORKS			
Price No.	DESCRIPTION	Unit	Unit price (CFAF)
TM 119	ROCK BREAKING This price covers, under the general conditions provided for in the contract, per cubic metre (m3), rock-breaking operations, including all incidentals. Per cubic metre:	m3	

Item No. 7: FORM OF THE BILL OF QUANTITIES AND ESTIMATES

BILL OF QUANTITIES AND ESTIMATES FOR THE MAINTENANCE WORKS ON THE COUNCIL ROAD SECTION: CARREFOUR LITIEU (INTER R0 606) – MELAH – FOSSONG WENTCHENG (WADEUH MARKET) – NKUIKOP – FONDONERA (NGUIANGO) – ATSOP – MEKET – MOKELEWOUM – SANTCHOU (TAWANG INTER R0 606); length: 29.000 km					
Price No.	DESCRIPTION	Unit	Quantity	Unit price (CFAF)	Amount (CFAF)
SERIES 100: CLEARING – EARTHWORKS					
TM 108a	Fill from borrow pit	m3	6,975.00		
TM 117	Extra over prices No. 108 and 208a for haulage exceeding 5 km	m3 x km	34,320.00		
Sub-total Series 100					
SERIES 600: MISCELLANEOUS					
TM 601d	Reinforced concrete for 20 x 40 cm beams and 50 x 60 cm gutters	m3	8.00		
TM 611a	Provisional sum for the diversion of utility networks (ENEO, CAMWATER, CAMTEL)	prov	1.00		

READ:

Item No. 6: FORM OF THE SCHEDULE OF UNIT PRICES

SERIES 100: CLEARING AND EARTHWORKS			
Price No.	DESCRIPTION	Unit	Unit price (CFAF)
TM 119	ROCK BREAKING This price covers, under the general conditions provided for in the contract, per cubic metre (m3), rock-breaking operations, including all incidentals.	m3	


	Per cubic metre:		
	Hydraulic Road Binder Supply and laying of the Hydraulic Road Binder, including all incidentals. This price covers, under the general conditions provided for in the contract, per tonne (t), the scarifying of the existing carriageway over its full width, including the shoulders, and the in-place recycling of the materials with the stabilising agent to a depth of 15 to 30 cm, to form the base layers of the new pavement. Any imported materials are paid for under Price 104. This price includes in particular: – all geotechnical and survey work required for the operation; – the scarifying of the existing carriageway, after any reinstatement of the shoulders and of the sections requiring imported material for levelling; – the supply, haulage and storage on site of the stabilising agent approved for use under this contract; – the supply of water of suitable quality for the works; – the construction of a preliminary trial section, at the Contractor's expense, and its approval by the Project Supervisor; – the in-place recycling of the scarified materials to form the base layers, including trimming of the materials and compaction to 97% of the Modified Proctor Optimum; – the Contractor's internal quality control as defined in the Special Technical Specifications (CCTP) and in the Quality Assurance Organisation Plan (SOPAQ); – all incidentals arising from work in small quantities or over narrow widths; – and all incidentals.		
TM120	Per tonne:		

Item No. 7: FORM OF THE BILL OF QUANTITIES AND ESTIMATES

BILL OF QUANTITIES AND ESTIMATES FOR THE MAINTENANCE WORKS ON THE COUNCIL ROAD SECTION: CARREFOUR LITIEU (INTER R0 606) – MELAH – FOSSONG WENTCHENG (WADEUH MARKET) – NKUIKOP – FONDONERA (NGUIANGO) – ATSOP – MEKET – MOKELEWOUN – SANTCHOU (TAWANG INTER R0 606); length: 29.000 km					
Price No.	DESCRIPTION	Unit	Quantity	Unit price (CFAF)	Amount (CFAF)
SERIES 100: CLEARING – EARTHWORKS					
TM 108a	Fill from borrow pit	m3	0		
TM 117	Extra over prices No. 108 and 208a for haulage exceeding 5 km	m3 x km	0		
TM120	Hydraulic Road Binder	t	881.45		
Sub-total Series 100					
SERIES 600: MISCELLANEOUS					
TM 601d	Reinforced concrete for 20 x 40 cm beams and 50 x 60 cm gutters	m3	0		
TM 611a	Provisional sum for the diversion of utility networks (ENEO, CAMWATER, CAMTEL)	prov	0		

The above amendments apply to the Form of the Schedule of Unit Prices and to the Form of the Bill of Quantities and Estimates.

All other provisions remain unchanged.



14 AOUI 2026
Yaoundé,